

**DELTA HELIX ENERGY LLC
W. M. KAUFMAN W-19
UIC PERMIT APPLICATION
UIC #2D08701056**

12/15/24

CHECKLIST FOR FILING A UIC PERMIT APPLICATION

Please utilize this checklist to ensure you have prepared, completed, and enclosed all required documentation and payment to ensure a timely review of your submittal.

Operator	Delta Helix Energy, LLC		
Existing UIC Permit ID Number	2D08701056-002	UIC Well API Number	4708701056

Office of Oil and Gas Office Use Only	
Permit Reviewer	
Date Received	
Administratively Complete Date	
Approved Date	
Permit Issued	

Please check the fees and payment included.

Fees		Payment Type	
UIC Permit Fee: \$500	☒	Check	☒
Groundwater Protection Plan (GPP) Fee: \$50.00	☐	Electronic	☐
		Other	☐

Please check the items completed and enclosed.



Checklist



UIC-1



Section 1 – Facility Information



Section 2 – Operator Information



Section 3 – Application Information



Section 4 – Applicant/Activity Request and Type



Section 5 – Brief description of the Nature of the Business



CERTIFICATION



Section 6 – Construction



Appendix A Injection Well Form



Appendix B Storage Tank Inventory



Section 7 – Area of Review



Appendix C Wells Within the Area of Review

- N/A ☒ Appendix D Public Service District Affidavit
- ☒ Appendix E Water Sources
- ☒ Appendix F Area Permit Wells
- ☒ Section 8 – Geological Data on Injection and Confining Zones
- ☒ Section 9 – Operating Requirements / Data
- ☒ Appendix G Wells Serviced by Injection Well
- ☒ Section 10 – Monitoring
- ☒ Section 11 – Groundwater Protection Plan (GPP)
- ☒ Appendix H Groundwater Protection Plan (GPP)
- ☒ Section 12 – Plugging and Abandonment
- ☒ Section 13 – Additional Bonding
- ☒ Section 14 – Financial Responsibility
- ☒ Appendix I Financial Responsibility
- ☒ Section 15 – Site Security Plan
- ☒ Appendix J Site Security for Commercial Wells
- ☒ Section 16 – Additional Information
- ☒ Appendix K Other Permit Approvals

****NOTE: For all 2D wells an additional bond in the amount of \$5,000 is required.***

Reviewed by (Print Name): Brad Morris

Reviewed by (Sign): 

Date Reviewed: 5/28/25

Section 1 – 5

UIC-1 Form

 WEST VIRGINIA DEPARTMENT OF ENVIRONMENTAL PROTECTION OFFICE OF OIL AND GAS 601 57th Street, SE Charleston, WV 25304 (304) 926-0450 www.dep.wv.gov/oil-and-gas	UNDERGROUND INJECTION CONTROL (UIC) PERMIT APPLICATION
UIC PERMIT ID # <u>2D08701056002</u> API # <u>4708701056</u> WELL # <u>Kaufman W-19</u>	

Section 1. Facility Information

Facility Name: Kaufman W-19 Disposal		
Address: 1.25 miles East on Kaufman Road (CR 48/3) off of Otto Road (CR 48)		
City: Spencer	State: WV	Zip: 25276
County: Roane	District: Smithfield	7.5' Quad: Spencer
Location description: 1.25 miles East on Kaufman Road (CR 48/3) off of Otto Road (CR 48) on the waters of Millstone Run.		
Location of well(s) or approximate center of field/project in UTM NAD 83 (meters) Latitude: 38.759149		
Northing: 4290082	Easting: 477216	Longitude: -81.262228
Environmental Contact Information:		
Name: Brad Morris	Title: Office Manager	
Phone: 681-229-1558	Email: bmorris@topdrilling.com	

Section 2. Operator Information

Operator Name: Delta Helix Energy, LLC		
Operator ID: 494530855		
Address: 300 Star Avenue, Suite 321		
City: Parkersburg	State: WV	Zip: 26101
County: Roane		
Contact Name: Brian Haught	Contact Title: Operator Manager	
Contact Phone: 681-229-1558	Contact Email: bhaught@topdrilling.com	

Section 3. Applicant Information

Ownership Status: ☒ PRIVATE ☐ PUBLIC ☐ FEDERAL ☐ STATE
☐ OTHER (explain):

SIC code: ☒ 1311 (2D, 2H, 2R) ☐ 1479 (3S) ☐ OTHER (explain):

Section 4. Applicant / Activity Request and Type:

- A. Apply for a new UIC Permit: ☐ 2D ☐ 2H ☐ 2R ☐ 3S
B. Reissue existing UIC Permit: ☒ 2D ☐ 2H ☐ 2R ☐ 3S
C. Modify existing UIC Permit: ☐ 2D ☐ 2H ☐ 2R ☐ 3S
(Submit only documentation pertaining to the modification request)
2D COMMERCIAL FACILITY: ☐ YES ☐ NO

Section 5. Briefly describe the nature of business and the activities to be conducted:

Oil & Natural Gas production. Water Produced from approximately 75 shallow wells is injected into the Big Injun Sand.

APPLICATION CERTIFICATION

In accordance with WV Code 47CSR13.13.11, all UIC permit applications must be signed by one of the following:

1. For a corporation: by a principle corporate officer of at least the level of vice-president;
2. For a partnership or sole proprietorship: by a general partner or the proprietor, respectively;
3. For a municipality, State, Federal, or other public agency: by either a principle executive officer or ranking elected official;
4. Or a duly authorized representative in accordance with 47CSR13.13.11.b.
(A person may be duly authorized by one of the primary entities (1-3) listed above by submitting a written authorization to the Chief of the WVDEP Office of Oil and Gas designating an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility. A duly authorized representative may thus be either a named individual or any individual occupying a named position.)

Delta Helix Energy, LLC

(Company Name)

2D08701056-002 (Kaufman W-19)

(UIC Permit Number)

I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment.
(47CSR13.13.11.d)

B. Douglas Haught

(Print Name)

CEO

(Print Title)

(Signature)

(Date)

5-28-25

Section 6

Construction

Section No. 6

1. The water produced in conjunction with crude oil from the William Kaufman lease is separated from the oil and gathered in a 100 bbl storage tank near the location of Kaufman W- 17. This water along with the water produced from nearby Clover Field Big Injun wells is filtered and injected into Kaufman W- 19. A Schematic of the production facility is shown in the attached Fig No. 1. The attached Fig No. 2 shows the location of the tanks, injection facility, and injection line to W M Kaufman W-19 and W M Kaufman W-7. Figure No. 3 (attached) shows the oil lines and oil and water stock tank locations. The ¼ mile AOR is shown on both Fig Nos 2 and 3. Fig No 3 also shows the lone USDW (James Warden) located within the AOR. Warden's USDW was sampled as well as that of Joseph Lung- located approximately 800' to the east of the AOR boundary.
2. The attached Fig No. 4 is a schematic of the as drilled injection well, W M Kaufman W-19 with Big Injun (injection zone), Big lime and shale (confining layers) marked. Tubing and casing depths along with cement info (TOC) is also shown on the schematic.
3. See Appendices A& B.
4. This disposal well was drilled in 1964 and logged with Gamma Ray / Density/ Caliper logs. A copy of the United States Department of the Interior Report No. 6992 (Reservoir Study of the William Kaufman Clover-Rush Run Oilfield, Roane County, WV by Karl-Heinz Frohne) is enclosed in Fig No. 5. This study provides a detailed study of the reservoir based on a core from W M Kaufman No. 7 located approximately 2600' South-West of Kaufman W-19. Reservoir properties as determined from that study are:

Gross Sand thickness: 24'

Pay thickness: 12.5'

Permeability: .8 md

Porosity: 15%

Connate water saturation: 65%

Kaufman W-19 was completed with a small fracture treatment soon after drilling. Both the Breakdown Pressure and Instantaneous Shut In Pressure were recorded at 1400 psig (surface).

The attached Fig No. 6 is a copy of the McCullough Scintillometer Gamma Ray / Neutron long run at the time the well was drilled. The tops of the relevant formations are marked on this log.

APPENDIX A Injection Well Form

1) GEOLOGIC TARGET FORMATION		Big Injun	
Depth	2202	Feet (top)	2235
		Feet (bottom)	
2) Estimated Depth of Completed Well, (or actual depth of existing well):		2275	Feet
3) Approximate water strata depths:		Fresh 200-400	Feet
		Salt 1245	Feet
4) Approximate coal seam depths:		NONE	
5) Is coal being mined in the area?		Yes ☐	No ☒
6) Virgin reservoir pressure in target formation		960	psig
		Source	Estimated
7) Estimated reservoir fracture pressure		2060 per step-rate test (1987)	
		psig (BHFP)	
8) MAXIMUM PROPOSED INJECTION OPERATIONS:			
Injection rate (bbl/hour)		12	
Injection volume (bbl/day)		50	
Injection pressure (psig)		883	
Bottom hole pressure (psig)		1966	
9) DETAILED IDENTIFICATION OF MATERIALS TO BE INJECTED, INCLUDING ADDITIVES:			
Produced water, bactericides, and other chemicals as may be necessary to maintain water quality.			
Temperature of injected fluid: (°F)		60	
10) FILTERS (IF ANY)			
Cartridge filters at injection pump and well head			
11) SPECIFICATIONS FOR CATHODIC PROTECTION AND OTHER CORROSION CONTROL			
No cathodic protection is utilized at this time.			

APPENDIX A (cont.)

12. Casing and Tubing Program

TYPE	Size	New or Used	Grade	Weight per ft. (lb/ft)	FOOTAGE: For Drilling	INTERVALS: Left in Well	CEMENT: Fill-up (Cu. Ft.)
Conductor	10 3/4	NA	NA	NA	9	9	NA
Fresh Water	8 5/8	N	H-40	28	466	466	CTS
Coal							
Intermediate 1							
Intermediate 2							
Production	4 1/2	N	J-55	9.5	2272	2272	53
Tubing	2 3/8	N	J-55	4.6	2103	2103	
Liners							


TYPE	Wellbore Diameter	Casing Size	Wall Thickness	Burst Pressure	Cement Type	Cement Yield (cu. ft./sk)	Cement to Surface ? (Y or N)
Conductor	DRIVE	10 3/4	NA	NA	NA	NA	N
Fresh Water	10	8 5/8	.264	2950	Reg. Neat	1.18	Y
Coal							
Intermediate 1							
Intermediate 2							
Production	7 7/8	4 1/2	.205	4380	50/50 Poz	1.26	N
Tubing		2 3/8	.167	6770	NA	NA	N
Liners							

PACKERS	Packer #1	Packer #2	Packer #3	Packer #4
Kind:	tension			
Sizes:	4" x 2"			
Depths Set:	2103			

Well Bore Diagram

W.M. Kaufman W-19
API 47-087-01056


Delta Helix Energy, LLC
UIC 2D08701056-003



4708701056

W M Kaufman W-19
47-087-01056

Fig No 4



Drive pipe 9'

8 5/8" csng set @ 466'- CTS

est TOC = 2025'
2078'-2193'

Big Lime

2103'
2209'-2220'
2235'-2277'
TD 2275'

2 3/8" tubing on tension packer
Big Injun perforations
Shale
4 1/2" csng @ 2272'

5/24/2018
Not to scale



4708701056

GEORGE H. HUBBARD (Jr.) VICE

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION


1964 F3

Quadrangle SPENCERPermit No. ROA-1056

WELL RECORD

Oil or Gas Well Oil & Gas
(KIND)Company WOLF'S HEAD OIL REFINING COMPANY, INC.Address P. O. Box 1588, Parkersburg, W. Va.Farm Wm. Kaufman Acres 800Location (waters) Millstone RunWell No. W-19 Elev. 1060.85District Smithfield County RoaneThe surface of tract is owned in fee by Maxel SmithOtto Route Address Spencer, W. Va.Mineral rights are owned by Alfred M. Oppenheimer, II,300 South Lang Avenue Address Pittsburgh 8, Pa.Drilling commenced June 12, 1964Drilling completed June 19, 1964Date Shot - From - To -With -Open Flow /10ths Water in - Inch/10ths Merc. in - InchVolume Drilled w/Rotary (Show Only) - Cu. Ft.Rock Pressure No Test lbs. - hrs.Oil - bbls., 1st 24 hrs.WELL ACIDIZED -WELL FRACTURED 6/27/64 - Used: 1,050 Bbls. Water, 46,000 # Sand, 300 Gal. BDA Acid, 175# J-98,350# J-84, 20 Gal. Deterger and 35 Gal. FrefloRESULT AFTER TREATMENT Gas = 50,000 Cu. Ft.ROCK PRESSURE AFTER TREATMENT 400 Lbs.Fresh Water - Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	10			
Conductor				9			
Red Rock			10	20			
Slate			20	85			
Sand			85	200			
Slate			200	230			
Red Rock			230	265			
Slate			265	295			
Sand			295	395			
Slate			395	420			
Red Rock			420	430			
Sand			430	470			
Slate			470	485			
Red Rock			485	495			
Slate			495	515			
Red Rock			515	525			
Slate			525	675			
Red Rock			675	735			
Sand			735	765			
Red Rock			765	815			
Slate			815	840			
Sand			840	905			
Red Rock			905	925			
Slate			925	965			
Red Rock			965	985			
Slate			985	1245			
Sand			1245	1350			
Slate			1350	1375			
Sand			1375	1400			



Location - Color - Soil - (over) - Oil - Depth - Remarks -

4708701056

[illegible]

Date July 13, 1964

APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC.

By George W. Wilsman
George W. Wilsman, (Title) Agent

UIC Permit No.

Storage Tank Inventory


[illegible]

Operator: Delta Helix Energy, LLC
 UIC Permit No.: 2D08701056

Secondary Containment Calculations
Earth Berm Containment
 (Input Measurements In Blue Cells)

Tank	Tank Dimensions		Capacity		
	Height (Ft)	Dia (Ft)	Barrels	Gallons	Cu Ft
1	15	10	209.8	8812.8	1178.1
2	15	10	209.8	8812.8	1178.1
3	10	8.5	101.1	4244.8	567.4
4			0.0	0.0	0.0
5			0.0	0.0	0.0
6			0.0	0.0	0.0
7			0.0	0.0	0.0
8			0.0	0.0	0.0
9			0.0	0.0	0.0
10			0.0	0.0	0.0
Total			520.7	21,870.4	2,923.6
Enter largest tank as Tank 1.					

Tank	Tank Base Exclusions		
	Dia (Ft)	Depth (Ft)	Vol (CuFt)
1	0	2.50	0.0
2	10	2.50	196.3
3	8.5	2.50	141.9
4	0	2.50	0.0
5	0	2.50	0.0
6	0	2.50	0.0
7	0	2.50	0.0
8	0	2.50	0.0
9	0	2.50	0.0
10	0	2.50	0.0
Total Tank Base Exclusions			338.2
Tank 1 entered as "0" diameter to exclude it from the tank base exclusion calculations.			




Containment Dimensions	
Top Interior Perimeter	
Length (Ft)	Width (Ft)
65.00	20.00
Bottom Interior Perimeter	
Length (Ft)	Width (Ft)
57.00	12.00
Depth (Ft)	
2.50	
Total Containment Volume (CuFt)	2439.1
All containment measurements must be interior dimensions.	

Tank Containment Volume (CuFt)	2439.1
Minus Tank Base Exclusions (CuFt)	338.2
Net Containment Volume (CuFt)	2100.9
Largest Tank Volume (CuFt)	1178.1
Available Containment Volume (CuFt)	178.3%

4708701056

Fig No 1

FACILITY SITE PLAN



HG ENERGY, LLC
SPCC PLAN

Drawn By KAB
File Name Clover Area
Scale _____
Date 11-6-14
Print No. _____

Facility Name: Kaufman, Wm. W-5, W-6,
W-8, W-12, W-13, W-17, W-18, W-20, W-21,
5, 605 & 606

State: WV

County: Roane

District: Smithfield

Name of Nearest Stream:
Millstone Run

Direction & Distance from
Facility: 185° @ 300'

~STORAGE TANKS~

No. 3

Volume bbl: 210

Tank #'s: 321-323

Dike Dimensions: 150' peri. X 2.2' depth

Calculated Capacity: 471 bbl


Section 7

Area of Review


Section No. 7

1. A ¼ mile fixed radius from the injection well, W M Kaufman W-19, was utilized for the AOR investigation.
2. Attached in Fig No 3 is a map showing the wells within the AOR. The wells within the AOR are listed in the attached APPENDIX C. The Well Records available are also enclosed in Fig No. 7. The attached Fig No 8 is a topographic map extending a mile from the Kaufman W-19 injection well. The map shows the facilities and injection, producing, plugged and abandoned wells within the one mile radius.
3. The Local PSD (Clover PSD) was contacted and the required Affidavit obtained. It is enclosed in APPENDIX D.
4. The USDWs in this area vary from approximately 20' to 100'. One USDW is located within the AOR. This well and one additional USDW located 800' to the east of the AOR boundary were sampled. The results of the analysis are shown in the attached APPENDIX E. TDS was measured as part of the analysis. Most of the USDWs in this field were drilled prior to the current owner and they know very little about the wells. The results of the analysis are shown in APPENDIX E.
5. The samples were collected by a WVDEP certified laboratory as set forth in 40CFR Part 136.
6. No corrective action is deemed necessary at this time.
7. This application is for a single disposal well and not an area permit.
8. Groundwater use in this area of Roane County is limited. Located approximately 3 miles from this injection well is the Charles Fork Lake. This lake is utilized as a water source for the City of Spencer as well as recreational activities. It is located on a different drainage than W M Kaufman W-19. Other than the water supply for the City of Spencer the only other know Ground water uses are agricultural.

4708701056



4708701056



- CLOVER FIELD -
Injection Well

Wm. Kaufman No.W-19 (47-087-01056)

ROANE CO., WV

Map Showing All Known Wells Within the Quarter-Mile AOR & WVGES Well Data Spots

8/15/2018

RECEIVED
Office of Oil and Gas
1 2019

JUL 11 2019

WV Department of
Environmental Protection



4708701056

APPENDIX C
Wells within the Area of Review

	API No.	Well No.	Well Type	Well Status	Northing	Easting	Penetrate Injection Zone	Penetrate Confining Zone	Total Vertical Depth	Surface Elevation
1	4708700955	Wines 7	Gas Prod	Active	4290299.5	476794.4	Y	Y	2278	1095
2	4708700988	W-8	Oil Prod	Active	4289673.2	477190.2	Y	Y	2430	1225
3	4708700994	W-12	Oil Prod	Active	4290143.6	476912.3	Y	Y	2380	1152
4	4708700995	W-13	Oil Prod	Active	4290388.4	477106.1	Y	Y	2313	1096
5	4708701032	W-16	Gas Prod	Active	4289685.6	477409.7	Y	Y	2371	1163
6	4708701053	W-17	Oil Prod	Active	4289888.7	477092.4	Y	Y	2190	971
7	4708701055	W-18	Gas Prod	Active	4289919.8	477488.3	Y	Y	2097	875
8	4708701056	W-19	Injector	Active	4290082.0	477216.0	Y	Y	2277	1061
9	4708701068	W-20	Oil Prod	Active	4290470.8	477304.6	Y	Y	2255	1022
10	4708701079	W-21	Oil Prod	Active	4290255.7	477520.7	Y	Y	2260	1046

**See WR-35 Completion Logs
Attached Below**

NOT REQUIRED

(4/25)

APPENDIX D

Public Service District Affidavit

Underground Injection Control Permit applicants must identify all publically recorded drinking water sources within a one (1) mile radius of the proposed injection well facility. If no drinking water sources are present within this radius a written affidavit shall be supplied by the local Public Service District (PSD) as ample verification.

"I certify under penalty of law that (state name of business)

Top Drilling / Delta Helix

has verified with the public service district (state name of PSD)

Clover Public Service District

that there are no such publically recorded sources.

William Spaw


(Signature of Authorized Representative)

Sworn and subscribed to before me this 15th day of October, 2024.

Ella D. Cottrell, my commission expires Dec. 7th 2025.

(Notary Signature)

Ella D. Cottrell



Promoting a healthy environment.



4708701056

DOMESTIC WATER ANALYSES

APPENDIX E

Water Sources

Operator: Delta Helix Energy

Year: 2024

UIC Permit: 2D08701056

		Source # 1	Source# 2
Water Source Name		Joseph Lung	James Warden
Northing		4,289,922.12	4,290,238.23
Easting		477,868.12	477,263.23
Parameter	Units		
Chloride	mg/L	4.9	5.8
Bromide	mg/L	0.10	0.10
Strontium	mg/L	0.093	0.054
Barium	mg/L	0.051	0.14
Iron	mg/L	0.050	0.76
Total Dissolved Solids	mg/L	254	210
pH	SI Units	8.57	6.93
Manganese	mg/L	0.0081	0.10
Aluminum	mg/L	0.020	0.020
Arsenic	mg/L	0.020	0.020
Sodium	mg/L	101	66.3
Calcium	mg/L	2.4	8.5
Sulfate	mg/L	5.0	5.1
MABAS	mg/L	ND	ND

Delta Helix

TABLE 1A. Chemical water quality for stations (KJL) and (KJW) associated with ~~HS~~ Energy's Kaufman Sites. Kirk Environmental, LLP., October 31, 2024.

PARAMETER	SAMPLING STATION	
	KJL	KJW
Field Water Temperature (°C)	16.4	18.0
Field Dissolved Oxygen (mg/L)	7.08	3.64
Field pH (SI Units)	8.57	6.93
Field Conductivity (µS)	561.1	434.0
Aluminum (mg/L)	< 0.020	< 0.020
Arsenic (mg/L)	< 0.020	< 0.020
Barium (mg/L)	0.051	0.14
Calcium (mg/L)	2.4	8.5
Total Iron (mg/L)	< 0.050	0.76
Manganese (mg/L)	0.0081	0.10
Sodium (mg/L)	101	66.3
Strontium (mg/L)	0.093	0.054
TDS (mg/L)	254	210
Bromide (mg/L)	< 0.10	< 0.10
Chloride (mg/L)	4.9	5.8
Sulfate (mg/L)	< 5.0	5.1

Samples collected 10/31/24

KJL = Joseph Lung OSDW Nothing easting 4,289,922.116
 easting 477,868.117

KJW = James Warden USDW Nothing easting 4,290,238.230
 easting 477,263.225

**Laboratory Report**

ED KIRK
KIRK ENVIRONMENTAL,LLP
PO BOX 1783
Beaver, WV 25813

Report Date: 11/26/2024
Date Received: 10/31/2024

Project: KAUFMAN SITES
Pace Project No.: 30730511

Sample: KJL		Lab ID: 30730511001	Collected: 10/31/24 11:55	Matrix: Water		
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
EPA 200.7	Aluminum	ND	mg/L	0.020	11/04/24 17:08	
EPA 200.7	Arsenic	ND	mg/L	0.020	11/04/24 17:08	
EPA 200.7	Barium	0.051	mg/L	0.0050	11/04/24 17:08	
EPA 200.7	Calcium	2.4	mg/L	0.50	11/04/24 17:08	
EPA 200.7	Iron	ND	mg/L	0.050	11/04/24 17:08	
EPA 200.7	Manganese	0.0081	mg/L	0.0050	11/04/24 17:08	
EPA 200.7	Sodium	101	mg/L	0.50	11/04/24 17:08	
EPA 200.7	Strontium	0.093	mg/L	0.010	11/04/24 17:08	N2
SM 2540C-2015	Total Dissolved Solids	254	mg/L	10.0	11/01/24 18:20	
EPA 300.0, Rev 2.1	Bromide	ND	mg/L	0.10	11/20/24 21:28	
EPA 300.0, Rev 2.1	Chloride	4.9	mg/L	1.0	11/20/24 21:28	
EPA 300.0, Rev 2.1	Sulfate	ND	mg/L	5.0	11/20/24 21:28	
	Collected By	EK			11/01/24 09:53	
	Field pH	8.57	Std. Units		11/01/24 09:53	
	Field Temperature, C	16.4	deg C		11/01/24 09:53	
	Field Specific Conductance	561.1	umhos/cm		11/01/24 09:53	
	Oxygen, Dissolved	7.08	mg/L		11/01/24 09:53	

Sample: KJW		Lab ID: 30730511002	Collected: 10/31/24 12:45	Matrix: Water		
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
EPA 200.7	Aluminum	ND	mg/L	0.020	11/04/24 17:10	
EPA 200.7	Arsenic	ND	mg/L	0.020	11/04/24 17:10	
EPA 200.7	Barium	0.14	mg/L	0.0050	11/04/24 17:10	
EPA 200.7	Calcium	8.5	mg/L	0.50	11/04/24 17:10	
EPA 200.7	Iron	0.76	mg/L	0.050	11/04/24 17:10	
EPA 200.7	Manganese	0.10	mg/L	0.0050	11/04/24 17:10	
EPA 200.7	Sodium	66.3	mg/L	0.50	11/04/24 17:10	
EPA 200.7	Strontium	0.054	mg/L	0.010	11/04/24 17:10	N2
SM 2540C-2015	Total Dissolved Solids	210	mg/L	10.0	11/01/24 18:20	
EPA 300.0, Rev 2.1	Bromide	ND	mg/L	0.10	11/20/24 21:48	
EPA 300.0, Rev 2.1	Chloride	5.8	mg/L	1.0	11/20/24 21:48	
EPA 300.0, Rev 2.1	Sulfate	5.1	mg/L	5.0	11/20/24 21:48	
	Collected By	EK			11/01/24 09:56	
	Field pH	6.93	Std. Units		11/01/24 09:56	
	Field Temperature, C	18.0	deg C		11/01/24 09:56	
	Field Specific Conductance	434.0	umhos/cm		11/01/24 09:56	
	Oxygen, Dissolved	3.64	mg/L		11/01/24 09:56	

Sample: KPW		Lab ID: 30730511003	Collected: 10/31/24 10:50	Matrix: Water		
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
EPA 200.7	Aluminum	0.29	mg/L	0.20	11/05/24 13:38	

**Laboratory Report**

ED KIRK
KIRK ENVIRONMENTAL,LLP
PO BOX 1783
Beaver, WV 25813

Report Date: 12/18/2024
Date Received: 12/13/2024

Project: KAUFMAN HOMES

Pace Project No.: 30742291

Sample: KAUFMAN JILUNG		Lab ID: 30742291001	Collected: 12/13/24 10:20		Matrix: Water	
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
SM5540C-2011	LAS Molecular Weight, g/mol	340			12/17/24 12:28	H1,H2
SM5540C-2011	MBAS, Calculated as LAS	ND	mg/L	0.10	12/17/24 12:28	H1,H2,M1,R1
Sample: KAUFMAN JI WODEN		Lab ID: 30742291002	Collected: 12/13/24 10:30		Matrix: Water	
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
SM5540C-2011	MBAS, Calculated as LAS	ND	mg/L	0.10	12/17/24 12:28	H1,H2
SM5540C-2011	LAS Molecular Weight, g/mol	340			12/17/24 12:28	H1,H2

ANALYTE QUALIFIERS

H1	Analysis conducted outside the EPA method holding time.
H2	Extraction or preparation conducted outside EPA method holding time.
M1	Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
R1	RPD value was outside control limits.

Reviewed by:

Beth Johnson
(800)999-0105
beth.johnson@pacelabs.com

Pace Analytical Services Beaver

225 Industrial Park Road, Beaver, WV 25813
Virginia VELAP 460148
West Virginia DEP 060
West Virginia DHHR 00412CM

North Carolina DEQ 466
Kentucky Wastewater Certification KY90039
Pennsylvania DEP 68-00839

LAB USE ONLY - Affix Workorder/Log MTIL 1

NO#: 30742291

ALL SHADED ARE

30742291

Container Preservative Type **

Preservative Types: (1) nitric acid, (2) sulfuric acid, (3) hydrochloric acid, (4) sodium hydroxide, (5) zinc acetate, (6) methanol, (7) sodium bisulfate, (8) sodium thiosulfate, (9) hexane, (A) ascorbic acid, (B) ammonium sulfate, (C) ammonium hydroxide, (D) TSP, (U) Unpreserved, (O) Other

Analyses

Lab Sample Receipt Checklist:

Custody Seals Present/Intact: Y N NA

Custody Signatures Present: Y N NA

Collector Signatures Present: Y N NA

Bottles Intact: Y N NA

Correct Bottles: Y N NA

Sufficient Volume: Y N NA

Samples Received on Ice: Y N NA

YOA -- Headspace Acceptable: Y N NA

USDA Regulated Soils: Y N NA

Samples in Holding Time: Y N NA

Residual Chlorine Present: Y N NA

CL Strips: Y N NA

Sample pH Acceptable: Y N NA

pH Strips: Y N NA

Sulfide Present: Y N NA

Lead Acetate Strips: Y N NA

LAB USE ONLY:

Lab Sample # / Comments:

Lab Sample Temperature Info:

Temp Blank Received: 5 Y N NA

Therm ID#: 2.7

Cooler 1 Temp Upon Receipt: 2.7 °C

Cooler 1 Therm Corr. Factor: 0.1 °C

Cooler 1 Corrected Temp: 2.5 °C

Comments:

Trip Blank Received: Y N NA

HCL MeOH TSP Other

Non Conformance(s): YES / NO

Page 2 of 4

of:

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

Billing Information:

Company: Pace Analytical

Address: Kirk Environmental

Report To: Ed Kirk

Copy To: Crystal Bennett

Customer Project Name/Number: Kaufman Home OS

State: WA

County/City: Time Zone Collected: [] PT [] MT [] CT [] ET

Site Collection Info/Address:

Site/Facility ID #:

Purchase Order #: Quote #:

Turnaround Date Required:

Collected By (print): Jason Smith

Collected By (signature): Jason Smith

Sample Disposal: [] Same Day [] Next Day [] 3 Day [] 4 Day [] 5 Day (Expedite Charges Apply)

[] Dispose as appropriate [] Return [] Archive: [] Hold:

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product (P), Soil/Solid (SL), Oil (OL), Wipe (WP), Air (AR), Tissue (TS), Bioassay (B), Vapor (V), Other (OT)

Customer Sample ID

Matrix *

Comp / Grab

Collected (or Composite Start)

Date

Time

Res

CI

of Ctns

Customer Remarks / Special Conditions / Possible Hazards:

Type of Ice Used: [] Wet [] Blue [] Dry [] None

Packing Material Used:

Radchem sample(s) screened (<500 cpm): Y N NA

Samples received via: FEDEX UPS Client Courier Pace Courier

Lab Tracking #: 2950253

SHORTELDS: PRESENT (<72 hours) Y N N/A

Date/Time: 12/13/24 13:11

Date/Time: 12/13/24 14:00

Date/Time: 12/13/24 16:00

Date/Time: 12/13/24 18:00

Received by/Company: (Signature) BMA 1 PACE

Received by/Company: (Signature) BMA 1 PACE

Received by/Company: (Signature) BMA 1 PACE

Received by/Company: (Signature) BMA 1 PACE

Notes

Profile #

15528

Client

Sample Line Item	Matrix	AG1H	AG1U	AG2S	AG3S	AG4U	BP1N	BP1U	BP1Z	BP2N	BP2S	BP2U	BP3B	BP3N	BP3S	BP3U	BP4N	BP4O	CG3H	WGKU	WGFU	CG1U	AG74	DG9H	DG9S	DG9U	VG9A	VG9B	VG9H	VG9U	GN	SP5T	ZPLC
1								—																									
2																																	
3																																	
4																																	
5																																	
6																																	
7																																	
8																																	
9																																	
10																																	
11																																	
12																																	

Glass			Plastic			Misc.		
DG9H	40mL HCl amber vial	GBOD	300mL BOD Glass Stopper	BP1N	1L HNO ₃ plastic	I	Wipe/Swab	
DG9M	40mL MeOH clear vial	WGKU	8oz clear soil jar	BP1S	1L H ₂ SO ₄ plastic	SP5T	120mL Coliform Na Thiosulfate	
DG9P	40mL TSP amber vial	WGKU	4oz clear soil jar	BP1U	1L unpreserved plastic	ZPLC	Ziploc Bag	
DG9S	40mL H ₂ SO ₄ amber vial	BJFU	4oz unpreserved amber wide	BP1Z	1L NaOH, Zn Acetate	GN	General Unpreserved	
DG9T	40mL Na Thio amber vial	CG3H	250mL clear glass HCl	BP2A	500mL NaOH, Asc Acid plastic	GNN	General Nitric	
DG9U	40mL amber unpreserved	AG1H	1L HCl amber glass	BP2N	500mL HNO ₃ plastic	GNS	General Sulfuric	
VG9A	40mL Asc Acid glass	AG1S	1L H ₂ SO ₄ amber glass	BP2S	500mL H ₂ SO ₄ plastic			
VG9B	40mL Sodium Bisulfate glass	AG1U	1liter unpres amber glass	BP2U	500mL unpreserved plastic			
VG9C	40mL NaOH clear vial	AG2S	500mL H ₂ SO ₄ amber glass	BP2Z	500mL NaOH, Zn Acetate			
VG9H	40mL HCl clear vial	AG3S	250mL H ₂ SO ₄ amber glass	BP3B	250mL NaOH plastic			
VG9T	40mL Na Thio. clear vial	AG3U	250mL unpres amber glass	BP3N	250mL HNO ₃ plastic	WT	Water	
VG9U	40mL unpreserved clear vial	AG74	60mL amber glass NH ₄ Cl	BP3U	250mL unpreserved plastic	SL	Solid	
		AG4U	100mL unpres amber glass	BP3S	250mL H ₂ SO ₄ plastic	OL	Non-aqueous liquid	
				BP4N	125mL HNO ₃ plastic	WP	Wipe	
				BP4O	125mL (NH ₄) 2SO ₄ /NH ₄ OH plastic	DW	Drinking Water	

WO#: 30742291

PM: BMJ Due Date: 12/31/24
CLIENT: BV-KIRKENV

LIMS30 Lab Sample Condition Upon Receipt (West Virgi

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client ☐ 3rd Party Courier ☒ Pace ☐ Other

Tracking #: _____

Custody Seal on Cooler/Box/Containers Present: ☐ yes ☐ no

Seals intact: ☐ yes ☐ no

Thermometer Used 24 Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temperature Observed Temp 0.8 °C Correction Factor: 0.0 °C Final Temp: 0.8 °C

Thermal Preservation Requirement Met Yes ☒ No ☐

pH paper Lot#	Date and Initials of person examining contents: _____
---------------	---

	Yes	No	N/A	
Chain of Custody Present:	☒	☐	☐	1.
Chain of Custody Filled Out:	☒	☐	☐	2.
Chain of Custody Relinquished:	☒	☐	☐	3.
Sampler Name & Signature on COC:	☒	☐	☐	4.
Sample Labels match COC:	☒	☐	☐	5.
-Includes date/time/ID				
Matrix: <u>WT</u>				
Samples Arrived within Hold Time:	☒	☐	☐	6.
Short Hold Time Analysis (<72hr remaining):	☒	☐	☐	7.
Rush Turn Around Time Requested:	☒	☐	☐	8. <u>5 Day</u>
Sufficient Volume:	☒	☐	☐	9.
Correct Containers Used:	☒	☐	☐	10.
-Pace Containers Used:				
Containers Intact:	☒	☐	☐	11.
Orthophosphate field filtered:	☐	☐	☒	12.
Hex Cr Aqueous sample field filtered:	☐	☐	☒	13.
-pH adjusted within 24 hours? (If yes, indicate acid lot #)	☐	☐	☒	
Filtered volume received for Dissolved tests:	☐	☐	☒	14.
All containers have been checked for chemical preservation:	☐	☐	☒	15.
exceptions: VOA, coliform, O&G, LLMercury, Non-aqueous matrix				
All containers meet method/chemical preservation requirements:	☐	☐	☒	Initial when completed
				Date:
				Tests not preserved:
Headspace in VOA Vials:	☐	☐	☒	16.
Trip Blank Present:	☐	☐	☒	17.
				Initial when completed: <u>aw</u>
				Date: <u>12/13/24</u>

Comments: _____

*PM review is documented electronically in LIMS, when the Project Manager closes the SRF Review schedule in LIMS. The status may be reviewed in the Status section of the Workorder Edit Screen.

Section 8

Geological Data Injection and Confining Zones

Section No. 8

The Clover Field is located on the western flank of the Arches Fork Anticline. The reservoir boundary, as determined from early drilling, was controlled on the west and down dip by water and on the east and up dip by a decrease in permeability. The Big Injun Sandstone is the productive interval in this field. The Keener is a very fine grained to coarse grained, tightly cemented, with very low permeability, sandstone. The Keener grades into the oil productive Pocono Big Injun Sandstone. The Big Injun is light gray to light green, very fine to medium grained, moderate to well sorted, sub angular, calcite or dolomite cemented sandstone. The Big Lime overlays the Keener and the Pocono Shale underlies the Big Injun. Both are thick impermeable formations. The Big Injun Sandstone on the Kaufman lease can be described as follows:

Gross Sand thickness: 24'

Pay thickness: 12.5'

Permeability: .8 md

Porosity: 15%

Connate water saturation: 65%

The full core report from W M Kaufman No. 7 is included in the Department of the Interior Report No. 6992 and is shown in Figure No. 5. Also included in the report are isopach and structure maps of the Big Injun that includes the area surrounding this injection well.

A search of the West Virginia Geologic and economic Survey web site revealed data on earthquakes from 1824-2023. There was one event recorded in western Roane County in 2016 (2.51 magnitude). Kanawha and Jackson Counties also recorded a small number of quakes. All the recorded quakes were 20 miles or further from this injection well. A copy of this data is shown in the attached Fig No. 9.

Water injection (both Disposal and Secondary recovery) projects have been active in Roane County since the 1960's. Water injection in the Clover Field has been active since the 1970's with no known cases of induced seismic activity.

The accumulated volume of produced water injected into this well as of 9/30/2024 is 75,843 bbls. Based on this volume and the following reservoir characteristics:

Gross thickness- 33'

Net thickness (pay) -10'

Porosity- 15%

Water saturation – 32%

The Fluid flood front is 301' from the well bore of this injection well.


Section No. 8 (cont)

Fig No. 3 shows the calculated radial distance the water injected into this well has moved in the Big Injun formation. Assuming 2000 barrels of water are injected into this well in a years' time over the next 5 years the flood front would advance and additional 19' to 320' from the injection well W M Kaufman W-19.


Well Bore Diagram

W.M. Kaufman W-19
API 47-087-01056

Delta Helix Energy, LLC
UIC 2D08701056-003



4708701056



McClintock

SCINTILLOMETER

NUCLEAR

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

WELLING NO.

COMPANY White Head Oil & Gas Co.WELL Wm. RaulstonFIELD Clayton PoolCOUNTY RowanLOCATION Smith Field Dist.

OTHER SERVICES

ELEV. 1060.35DATE 10-20-64TIME 1:20 PMAGE 1060.35

ELEVATIONS

LOG MEASURED FROM 5.0 FT. ABOVE PERMANENT DATUMDRILLING MEASURED FROM 10.000 A.L.DATE 10-20-64RUN NO. 1TYPE LOG ONEDEPTH - DRILLER 12.50DEPTH - LOGGER 22.72BOTTOM LOGGED INTERVAL 22.72TOP LOGGED INTERVAL 22.72TYPE FLUID IN HOLE WATERSALINITY - PER. CL. WATERDENSITY - LB./GAL. WATERLEVEL WATERMAY REC. TEMP. DEG. F. WATEROPER. RIG TIME WATERRECORDED BY M. W. S. 2.2 HRSWITNESSED BY W. S. S. 2.2 HRSWITNESSED BY W. S. S. 2.2 HRSWITNESSED BY W. S. S. 2.2 HRSWITNESSED BY W. S. S. 2.2 HRSWITNESSED BY W. S. S. 2.2 HRS

BORE HOLE RECORD				CASING RECORD			
RUN	DATE	FROM	TO	SIZE	WT.	FROM	TO
1	12-3	0	10	10 1/2	40	0	9
2	10-1	10	454	8 1/2	30	0	454
3	8-1	454	1120	7 1/2	20	0	1120
4	12-1	1120	2275	6 1/2	15	0	2275

Fig. 100-6

4708701056

LIME

TAP DENNIS
CAVE 2066'

2066

Plow
CAVE

TAP 1014
LIME 2084'

Big Lime
Top: 2084
Bottom: 2202

2098

2100

2104

BIG
LIME

Wm Kauffman W-19

2162

2183

2200

TAP BIG INJUN
2202

POY

10% to 12%

12% →

TAP POY 2204'

10% to 12% POROSITY

PERFORATED 22

6 GLASS

Bottom POY 2212'

TAP POY 2215'

12% to 13% POROSITY

PERFORATED 22

4 GLASS. ONE

Bottom POY 2222'

PERFORATED 2084

Bottom BIG
INJUN 2226'

2239

+12


2241'
MPC
TD

Big Injun
Top: 2202
Bottom: 2226

TOTAL 10
ALL H466


4708700985 W-7⁻¹⁷⁻

4708701056 W-19

**Pay Sand**

Big Injun Isopach


4708701056
Kaufman W-19



Isopachous Map of the Big Injun Sand, William Kaufman Lease, Clover-Rush Run Oilfield.


4708701056 W-19

8.



4708701056

W-19




0 800 1600
Scale, feet

LEGEND

- Oil well
- ⊗ Gas-injection well

- Structure Contour Map on Top of Big Injun Sand, William Kaufman Lease, Clover-Rush Run Oilfield.



Greenbrier Limestones Isopach/Structure Map

OOG data

Wells_Open-USE

▲ Brine Disposal

— Anticline/Syncline

— Greenbrier Limestone Elevation (Ft)

— Greenbrier Thickness (Ft)

Basemap

▭ county

○ towns

primary roads

— primary

— primary_link

— secondary roads

— residential roads

5,000 0 5,000 10,000 ft



Earthquake Epicenters of West Virginia



1824 through 2024

Publications Policy:

This publication represents interpretations of best available data made by professional geologists and geographers. As in all research work, professional interpretations may vary, and can change with advancements in both technology and data quality. This publication is offered as a service of the State of West Virginia; proper use of the information herein is the sole responsibility of the user.

Permission to reproduce this publication is granted if acknowledgement is given to the West Virginia Geological and Economic Survey.

Map Date: 2/23/2024
Earthquake Data: 2/16/2024
Projection: Transverse Mercator
Horizontal Datum: NAD 1983
Map scale for full
8.5" x 11" display: 1:2,000,000



West Virginia Geological
and Economic Survey
Mont Chateau Research Center
1 Mont Chateau Road
Morgantown, WV 26508-8079
Phone: (304) 594-2331
www.wvgs.wvnet.edu

Map Num	Time (event ID)	County	UTC Year	UTC Month	UTC Day	UTC Hour	UTC Minute	UTC Seconds	Latitude	Longitude	Magnitude	Magnitude Type	Recorded	MMI	Event URL
1	1824-07-15T16:20:00	Wetzel	1824	07	15	16	20	00	39.70000	-80.50000	4.1	mb	Historic	4.0	<NULL>
2	1846-10-19T02:00:00	Jefferson	1846	10	19	02	00	00	39.30000	-77.90000	2.7	<NULL>	Historic	3	<NULL>
3	1853-05-02T14:20:00	Pendleton	1853	05	02	14	20	00	38.50000	-79.50000	4.4	<NULL>	Historic	5	<NULL>
4	1909-04-02T07:25:00	Berkeley	1909	04	02	07	25	00	39.40000	-78.00000	3.6	mb	Historic	5	<NULL>
5	1933-06-15T01:14:36.8	Mingo	1933	06	15	01	14	36.8	37.56800	-81.97300	0.0	<NULL>	Historic	<NULL>	<NULL>
6	1935-11-01T08:30:00	Hardy	1935	11	01	08	30	00	38.90000	-78.90000	3.3	<NULL>	Historic	4	<NULL>
7	1957-03-07T21:05:09	Monongalia	1957	03	07	21	05	09	39.60000	-79.90000	2.9	mb	Historic	3	<NULL>
8	1957-03-13T21:00:41	Monongalia	1957	03	13	21	00	41	39.60000	-79.90000	2.9	mb	Historic	3	<NULL>
9	1963-10-10T00:00:00	Morgan	1963	10	10	00	00	00	39.65500	-78.19700	3.6	<NULL>	Historic	<NULL>	<NULL>
10	1964-11-25T02:50:05	McDowell	1964	11	25	02	50	05	37.40000	-81.50000	4.5	mb	Instrumental	<NULL>	<NULL>
11	1965-04-26T15:26:19.7	McDowell	1965	04	26	15	26	19.7	37.32500	-81.60200	3.5	mblg	Instrumental	<NULL>	<NULL>
12	1966-09-28T00:00:00	Harrison	1966	09	28	00	00	00	39.30000	-80.30000	3.1	<NULL>	Instrumental	4	<NULL>
13	1967-12-16T12:23:33.4	McDowell	1967	12	16	12	23	33.4	37.36000	-81.60400	3.5	mb	Instrumental	<NULL>	<NULL>
14	1969-11-20T01:00:09.3	Mercer	1969	11	20	01	00	09.3	37.44900	-80.93200	4.6	mblg	Instrumental	6	<NULL>
15	1969-11-20T01:00:10.700Z	Mercer	1969	11	20	01	00	10.700	37.449000	-80.932000	4.54	mw	Instrumental	5	https://earthquake.usgs.gov/earthquakes/eventpage/ushis3082/
16	1970-08-11T06:14:25.5	Lincoln	1970	08	11	06	14	25.5	38.23000	-82.05000	2.8	mblg	Instrumental	4	<NULL>
17	1971-04-01T05:05:11	McDowell	1971	04	01	05	05	11	37.40000	-81.60000	3.0	mb	Instrumental	0	<NULL>
18	1972-01-09T23:24:29	McDowell	1972	01	09	23	24	29	37.40000	-81.60000	3.7	mblg	Instrumental	0	<NULL>
19	1972-09-12T15:17:13.7	Monongalia	1972	09	12	15	17	13.7	39.60000	-79.90000	2.9	mb	Historic	3	<NULL>
20	1974-10-20T15:13:55.100Z	Wood	1974	10	20	15	13	55.100	39.095000	-81.593000	3.40	lg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp00008g9/
21	1976-01-30T18:58:49.800Z	Morgan	1976	01	30	18	58	49.800	39.683000	-78.170000	2.80	lg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp0000eu9/
22	1976-05-06T18:46:08.1	Monongalia	1976	05	06	18	46	08.1	39.60000	-79.90000	3.1	mb	Historic	4	<NULL>
23	1976-06-19T05:54:13.900Z	McDowell	1976	06	19	05	54	13.900	37.362000	-81.624000	4.70	mb	Instrumental	6	https://earthquake.usgs.gov/earthquakes/eventpage/usp0000gyg/
24	1976-07-03T20:53:45.08	Mercer	1976	07	03	20	53	45.08	37.32000	-81.13000	2.7	mblg	Instrumental	<NULL>	<NULL>
25	1978-08-14T04:50:05.4	Fayette	1978	08	14	04	50	05.4	37.93900	-80.87400	1.6	mc	Instrumental	<NULL>	<NULL>
26	1979-09-16T09:39:22.6	Pocahontas	1979	09	16	09	39	22.6	38.09900	-80.24000	1.6	mc	Instrumental	<NULL>	<NULL>
27	1979-09-19T00:45:57.4	Pocahontas	1979	09	19	00	45	57.4	38.11000	-80.24300	2.0	mc	Instrumental	<NULL>	<NULL>
28	1979-10-31T08:32:47.3	Raleigh	1979	10	31	08	32	47.3	37.61700	-81.20700	0.8	mc	Instrumental	<NULL>	<NULL>
29	1980-04-10T22:33:15.7	Mercer	1980	04	10	22	33	15.7	37.48700	-81.08600	0.7	mc	Instrumental	<NULL>	<NULL>
30	1980-09-21T10:02:46.3	Pocahontas	1980	09	21	10	02	46.3	38.17500	-80.07000	1.4	mc	Instrumental	<NULL>	<NULL>
31	1980-10-16T03:48:07.6	Pocahontas	1980	10	16	03	48	07.6	38.06600	-80.21500	1.1	mc	Instrumental	<NULL>	<NULL>
32	1980-11-05T21:48:14.2	Pocahontas	1980	11	05	21	48	14.2	38.18800	-79.93600	3.0	ml	Instrumental	<NULL>	<NULL>
33	1980-11-25T07:44:04	Pocahontas	1980	11	25	07	44	04	38.09500	-80.12300	0.6	md	Instrumental	<NULL>	<NULL>
34	1981-11-30T17:33:11	Mingo	1981	11	30	17	33	11	37.63000	-82.20000	2.5	mc	Instrumental	<NULL>	<NULL>
35	1982-06-23T16:17:34.1	Fayette	1982	06	23	16	17	34.1	37.87000	-80.95700	2.5	md	Instrumental	<NULL>	<NULL>
36	1983-01-21T05:33:20.4	Pocahontas	1983	01	21	05	33	20.4	38.06700	-80.14400	0.4	md	Instrumental	<NULL>	<NULL>
37	1983-05-26T01:04:44.8	Monroe	1983	05	26	01	04	44.8	37.50600	-80.31600	2.2	md	Instrumental	<NULL>	<NULL>
38	1983-06-10T00:18:40.4	Greenbrier	1983	06	10	00	18	40.4	37.94800	-80.16300	1.2	md	Instrumental	<NULL>	<NULL>
39	1983-06-10T00:24:57	Greenbrier	1983	06	10	00	24	57	37.95100	-80.18900	1.2	md	Instrumental	<NULL>	<NULL>
40	1983-06-10T00:31:08.3	Greenbrier	1983	06	10	00	31	08.3	37.93800	-80.16800	0.4	md	Instrumental	<NULL>	<NULL>
41	1983-07-20T04:41:40.9	Greenbrier	1983	07	20	04	41	40.9	37.88500	-80.69100	1.6	md	Instrumental	<NULL>	<NULL>
42	1983-07-25T03:27:00.2	Wyoming	1983	07	25	03	27	00.2	37.49600	-81.35200	0.6	md	Instrumental	<NULL>	<NULL>
43	1983-11-13T16:51:06.7	Summers	1983	11	13	16	51	06.7	37.55600	-80.77500	0.4	md	Instrumental	<NULL>	<NULL>
44	1983-11-13T17:50:50.1	Monroe	1983	11	13	17	50	50.1	37.55900	-80.75300	0.7	md	Instrumental	<NULL>	<NULL>
45	1983-11-25T16:27:47.8	Monroe	1983	11	25	16	27	47.8	37.56800	-80.74500	0.7	md	Instrumental	<NULL>	<NULL>
46	1983-12-23T10:51:21.9	Summers	1983	12	23	10	51	21.9	37.76600	-80.83700	0.3	md	Instrumental	<NULL>	<NULL>
47	1984-02-02T05:10:19.7	Mingo	1984	02	02	05	10	19.7	37.71700	-82.21800	1.9	md	Instrumental	<NULL>	<NULL>
48	1984-03-11T04:01:38.9	Summers	1984	03	11	04	01	38.9	37.47400	-80.90000	1.1	md	Instrumental	<NULL>	<NULL>
49	1984-10-09T05:33:31.5	Summers	1984	10	09	05	33	31.5	37.71300	-80.89100	2.1	md	Instrumental	<NULL>	<NULL>
50	1984-12-21T13:12:21.9	Pocahontas	1984	12	21	13	12	21.9	38.19800	-80.20800	1.6	md	Instrumental	<NULL>	<NULL>
51	1985-06-14T07:57:10.2	Mercer	1985	06	14	07	57	10.2	37.53400	-81.02000	0.8	md	Instrumental	<NULL>	<NULL>
52	1986-02-26T21:53:20.8	Pendleton	1986	02	26	21	53	20.8	38.50700	-79.29200	2.3	md	Instrumental	<NULL>	<NULL>
53	1986-12-20T08:13:12.8	Greenbrier	1986	12	20	08	13	12.8	38.05800	-80.64300	1.2	md	Instrumental	<NULL>	<NULL>
54	1989-03-19T10:07:55.8	Logan	1989	03	19	10	07	55.8	37.73500	-82.06400	1.9	md	Instrumental	<NULL>	<NULL>
55	1991-04-22T01:01:20.270Z	Greenbrier	1991	04	22	01	01	20.270	37.941000	-80.207000	3.50	mblg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp0004qn8/
56	1991-06-28T18:34:51.920Z	Kanawha	1991	06	28	18	34	51.920	38.276000	-81.668000	3.20	mblg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp0004thc/
57	1992-03-29T20:16:48.2	Mercer	1992	03	29	20	16	48.2	37.31400	-81.14900	1.4	md	Instrumental	<NULL>	<NULL>
58	1992-05-06T21:20:23.9	Fayette	1992	05	06	21	20	23.9	38.11800	-81.06900	2.3	md	Instrumental	<NULL>	<NULL>
59	1992-11-24T02:26:50.7	Summers	1992	11	24	02	26	50.7	37.45700	-80.88400	1.2	md	Instrumental	<NULL>	<NULL>
60	1994-02-04T07:40:32.4	Nicholas	1994	02	04	07	40	32.4	38.23600	-80.75900	2.1	md	Instrumental	<NULL>	<NULL>

Map Num	Time (event ID)	County	UTC Year	UTC Month	UTC Day	UTC Hour	UTC Minute	UTC Seconds	Latitude	Longitude	Magnitude	Magnitude Type	Recorded	MMI	Event URL
61	1994-06-19T08:36:41.3	Nicholas	1994	06	19	08	36	41.3	38.33900	-80.64000	1.7	md	Instrumental	<NULL>	<NULL>
62	1995-11-15T10:29:24.8	Raleigh	1995	11	15	10	29	24.8	37.71700	-81.04300	2.6	md	Instrumental	<NULL>	<NULL>
63	1995-12-28T23:48:30.4	Fayette	1995	12	28	23	48	30.4	38.08400	-80.96800	2.5	md	Instrumental	<NULL>	<NULL>
64	1996-08-11T09:11:21.3	Greenbrier	1996	08	11	09	11	21.3	37.73100	-80.62800	2.1	mc	Instrumental	<NULL>	<NULL>
65	1997-02-22T14:32:33.1	Fayette	1997	02	22	14	32	33.1	37.92100	-81.02700	2.0	mc	Instrumental	<NULL>	<NULL>
66	1997-03-15T05:56:36.4	Webster	1997	03	15	05	56	36.4	38.34700	-80.48400	1.8	md	Instrumental	<NULL>	<NULL>
67	1998-10-02T10:01:06.9	Kanawha	1998	10	02	10	01	06.9	38.06800	-81.46600	2.5	md	Instrumental	<NULL>	<NULL>
68	2000-10-16T17:56:13.8	Braxton	2000	10	16	17	56	13.8	38.63600	-80.92000	2.5	md	Instrumental	<NULL>	<NULL>
69	2001-12-04T21:15:13.9	Summers	2001	12	04	21	15	13.9	37.72600	-80.75200	3.1	mb	Instrumental	<NULL>	<NULL>
70	2002-03-27T08:25:03.3	Mingo	2002	03	27	08	25	03.3	37.75300	-82.17100	2.1	md	Instrumental	<NULL>	<NULL>
71	2006-07-11T12:01:43.100Z	Greenbrier	2006	07	11	12	01	43.100	37.882167	-80.641333	2.60	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se606219/
72	2008-01-29T01:04:20.700Z	Monroe	2008	01	29	01	04	20.700	37.544833	-80.509833	2.40	mlg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se606830/
73	2009-04-11T18:11:09.070Z	Summers	2009	04	11	18	11	09.070	37.513333	-80.895667	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se607139/
74	2010-04-04T09:19:14.010Z	Braxton	2010	04	04	09	19	14.010	38.599000	-80.916167	3.40	mlg	Instrumental	5	https://earthquake.usgs.gov/earthquakes/eventpage/se608185/
75	2010-04-29T01:36:21.260Z	Braxton	2010	04	29	01	36	21.260	38.685667	-80.814833	2.60	mlg	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se608194/
76	2010-04-29T12:38:53.430Z	Braxton	2010	04	29	12	38	53.430	38.664833	-80.856167	2.70	mlg	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se608196/
77	2010-04-29T23:26:39.470Z	Braxton	2010	04	29	23	26	39.470	38.722000	-80.803000	2.50	mblg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/usp000hc39/
78	2010-05-07T10:26:03.540Z	Braxton	2010	05	07	10	26	03.540	38.602333	-80.912167	2.60	mlg	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se608197/
79	2010-05-08T03:03:00.620Z	Braxton	2010	05	08	03	03	00.620	38.623000	-80.911333	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608198/
80	2010-07-24T09:15:44.130Z	Braxton	2010	07	24	09	15	44.130	38.675333	-80.820167	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608209/
81	2010-07-25T03:48:35.550Z	Braxton	2010	07	25	03	48	35.550	38.679167	-80.797167	2.20	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608210/
82	2010-08-15T04:38:47.380Z	Lewis	2010	08	15	04	38	47.380	38.818333	-80.429833	2.50	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608213/
83	2010-08-21T03:16:21.990Z	Upshur	2010	08	21	03	16	21.990	38.792500	-80.397667	2.50	md	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se608214/
84	2010-08-26T04:22:15.190Z	Raleigh	2010	08	26	04	22	15.190	37.748333	-81.204667	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608215/
85	2010-08-26T04:24:55.390Z	Raleigh	2010	08	26	04	24	55.390	37.727333	-81.204333	2.20	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608216/
86	2010-09-13T15:08:46.470Z	Lincoln	2010	09	13	15	08	46.470	38.099833	-82.034000	2.40	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se608218/
87	2011-08-25T05:59:13.760Z	Greenbrier	2011	08	25	05	59	13.760	37.916000	-80.215333	2.70	md	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se609219/
88	2012-01-10T19:38:58.660Z	Braxton	2012	01	10	19	38	58.660	38.566833	-80.893833	2.80	mlg	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se609646/
89	2012-03-16T15:05:53.570Z	Kanawha	2012	03	16	15	05	53.570	38.234000	-81.748000	2.60	mblg	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/usp000jgbk/
90	2013-03-31T14:01:24.030Z	Braxton	2013	03	31	14	01	24.030	38.645000	-80.833167	3.40	mw	Instrumental	5	https://earthquake.usgs.gov/earthquakes/eventpage/se610164/
91	2013-05-29T21:06:11.100Z	Kanawha	2013	05	29	21	06	11.100	38.365333	-81.275667	2.26	ml	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/ld60041041/
92	2013-07-20T11:38:46.180Z	Gilmer	2013	07	20	11	38	46.180	38.895667	-80.887000	2.70	mlg	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se610199/
93	2013-07-30T06:09:04.850Z	Gilmer	2013	07	30	06	09	04.850	38.839333	-80.908667	2.80	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se610203/
94	2013-08-16T11:02:21.040Z	Gilmer	2013	08	16	11	02	21.040	38.841500	-80.938667	2.60	mlg	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se610207/
95	2013-10-13T09:20:58.550Z	Braxton	2013	10	13	09	20	58.550	38.701167	-80.824167	2.20	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se610225/
96	2013-10-19T08:41:57.430Z	Greenbrier	2013	10	19	08	41	57.430	37.747667	-80.643333	2.20	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se610227/
97	2014-04-14T17:44:27.380Z	Clay	2014	04	14	17	44	27.380	38.453000	-80.889500	2.10	ml	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/ld60066331/
98	2014-06-06T22:15:40.790Z	Jackson	2014	06	06	22	15	40.790	38.643833	-81.585500	2.60	md	Instrumental	3	https://earthquake.usgs.gov/earthquakes/eventpage/se610630/
99	2016-01-17T19:12:49.050Z	Jefferson	2016	01	17	19	12	49.050	39.319333	-77.828333	3.03	ml	Instrumental	1	https://earthquake.usgs.gov/earthquakes/eventpage/ld60108801/
100	2016-08-06T12:39:14.210Z	Mingo	2016	08	06	12	39	14.210	37.863000	-82.128833	2.31	md	Instrumental	1	https://earthquake.usgs.gov/earthquakes/eventpage/se60029113/
101	2016-12-01T01:27:04.780Z	Roane	2016	12	01	01	27	04.780	38.760833	-81.485333	2.51	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60032413/
102	2017-06-21T08:01:32.720Z	Kanawha	2017	06	21	08	01	32.720	38.199500	-81.398500	2.70	md	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se60172362/
103	2017-08-13T06:52:15.080Z	Webster	2017	08	13	06	52	15.080	38.345833	-80.568500	2.01	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60042903/
104	2017-09-13T17:33:10.930Z	Monroe	2017	09	13	17	33	10.930	37.472833	-80.703000	3.20	md	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se60179327/
105	2019-03-04T07:41:54.780Z	Greenbrier	2019	03	04	07	41	54.780	37.838167	-80.704167	2.61	md	Instrumental	2	https://earthquake.usgs.gov/earthquakes/eventpage/se60076828/
106	2020-07-29T00:36:35.820Z	Pocahontas	2020	07	29	00	36	35.820	38.222333	-79.911500	2.43	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60322771/
107	2020-07-30T05:57:13.780Z	Pocahontas	2020	07	30	05	57	13.780	38.222000	-79.908333	2.38	md	Instrumental	4	https://earthquake.usgs.gov/earthquakes/eventpage/se60323026/
108	2021-12-07T10:06:15.620Z	Monroe	2021	12	07	10	06	15.620	37.512000	-80.388500	1.86	md	Instrumental	2	https://earthquake.usgs.gov/earthquakes/eventpage/se60139853/
109	2022-08-10T00:36:34.020Z	Pocahontas	2022	08	10	00	36	34.020	38.160667	-80.013167	2.04	md	Instrumental	2	https://earthquake.usgs.gov/earthquakes/eventpage/se60158843/
110	2023-02-17T21:54:06.190	Mason	2023	02	17	21	54	06.190	38.917000	-82.043000	2.50	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60500438/
111	2024-02-10T10:24:49.840Z	Nicholas	2024	02	10	10	24	49.840	38.2928333	-80.5381667	2.29	md	Instrumental	<NULL>	https://earthquake.usgs.gov/earthquakes/eventpage/se60501603/

Data as of 2/16/2024. For a more detailed listing, please download the West Virginia Earthquake spreadsheet/workbook from <http://www.wvgs.wvnet.edu/www/earthquakes/seismic.html>.

If you view this map and data as a PDF, you can click any of the blue hyperlinked text to view further information on a website.

Some definition of terms are provided with this map. Please consult the West Virginia Earthquake Catalog 202402.xlsx spreadsheet/workbook for complete definitions.




Some Definitions and Explanations:

- **County:** the name of the county where the epicenter was located, derived from spatial selection.
- Dates and times are in Coordinated Universal Time (UTC) for Year, Month, Day, Hours (HH), Minutes (MM) and Seconds (SS). (For Eastern Standard Time, the offset is - 5 hours).
- **Magnitude (Mag):** Magnitude numbers indicative of an earthquake's relative size and is the measured maximum motion as recorded by a seismograph. The numbers are pulled from various sources; the primary source whenever possible.
- **Recorded:** refers to the means by which magnitudes were recorded: if they were reported as "felt" (Historical) or recorded via scientific instrumentation (Instrumental) as retrieved from Source1 or Source2.
- **Latitude and Longitude** values are expressed in decimal degrees for the northern and western hemispheres, respectively.
- **MMI:** The Modified Mercalli Intensity scale for epicenter intensity, usually designated with Roman numerals. Visit USGS at <https://www.usgs.gov/programs/earthquake-hazards/modified-mercalli-intensity-scale> for further information.
- **MagnitudeType:** Magnitude type code; the method used in measuring magnitudes (e.g., *Mb* for "body-wave", *Mc* for "coda amplitude", *Md* for "coda duration").

For other or more detailed earthquake and seismological definitions, please visit the USGS (<https://earthquake.usgs.gov/learn/glossary/>).

Sources (Source1 and Source2):

- USGS ENS – [United States Geological Survey, Earthquake Hazards](#) (A Primary Source)
- VTSSO – [Virginia Tech Seismological Observatory](#) (A Secondary Source)
- ANSS – [Advanced National Seismic System](#)
- CERl – [Center for Earthquake Research and Information](#)
- LDEO – [Lamont-Doherty Earth Observatory](#)
- Wheeler I-2737 – Wheeler, Russell L., [Earthquakes In and Near the Northeastern United States, 1638-1998](#) (Used only as reference here)



Northeastern United States and southeastern Canadian earthquakes from 1990 to 2011.
Image courtesy of the Lamont-Doherty Earth Observatory (Won-Young Kim)
of Columbia University, New York. Used by permission.



West Virginia Geological and
Economic Survey
<https://www.wvgs.wvnet.edu/>

Kaufman Field Study 1967

RESERVOIR STUDY OF THE WILLIAM KAUFMAN LEASE CLOVER-RUSH RUN OILFIELD, ROANE COUNTY, W. VA.

By Karl-Heinz Frohne

* * * * * report of investigations 6992



UNITED STATES DEPARTMENT OF THE INTERIOR
Stewart L. Udall, Secretary

BUREAU OF MINES
Walter R. Hibbard, Jr., Director

This publication has been cataloged as follows:

Frohne, Karl-Heinz

Reservoir study of the William Kaufman lease, Clover-Rush Run oilfield, Roane County, West Virginia. [Washington] U.S. Dept. of the Interior, Bureau of Mines [1967]

17 p. illus., tables. (U. S. Bureau of Mines. Report of investigations 6992)

Includes bibliography.

1. Oil fields--West Virginia--Roane County. 2. Secondary oil recovery. 3. Oil field flooding. I. Title. (Series)

TN23.U7 no. 6992 622.06173

U. S. Dept. of the Int. Library

CONTENTS

	<u>Page</u>
Abstract.....	1
Introduction.....	1
Acknowledgments.....	2
General geology.....	2
Location and topography.....	2
Area structure and stratigraphy.....	2
Field development and lease history.....	4
Development of Clover-Rush Run oilfield.....	4
History of William Kaufman lease.....	4
Coring and logging operations.....	5
Reservoir data.....	5
Structure.....	5
Lithology.....	6
Core analysis.....	7
Log analysis.....	7
Reservoir limits.....	8
Reservoir temperature and pressure.....	8
Permeability.....	9
Reservoir-fluid saturations.....	9
Reservoir-fluid properties.....	10
Reservoir performance.....	10
Primary-performance prediction.....	10
Secondary recovery.....	10
Waterflood prediction.....	10
Gas-injection project.....	11
Summary.....	12
References.....	13
Appendix A.--Core analysis data for Kaufman well P-7.....	14
Appendix B.--Recommended analyses for pressure-volume-temperature samples at pressures below original reservoir pressures.....	15
Appendix C.--Pressure-volume-temperature analysis adjustment procedure..	16

ILLUSTRATIONS

<u>Fig.</u>		
1.	Oil-productive areas in Roane County, W. Va., and the William Kaufman lease in the Glover-Rush Run oilfield.....	3
2.	Generalized geologic column of subsurface formations, Glover-Rush Run oilfield.....	4
3.	Structure contour map on top of Big Injun sand, William Kaufman lease, Glover-Rush Run oilfield.....	5
4.	Isopachous map of the Big Injun sand, William Kaufman lease, Glover-Rush Run oilfield.....	6
5.	Capillary pressure versus water saturation for the Big Injun sand in Kaufman well P-7, Glover-Rush Run oilfield.....	9

ILLUSTRATIONS --Continued

<u>Fig.</u>	<u>Page</u>
6. Production decline curve for the William Kaufman lease, Clover-Rush Run oilfield.....	11
7. Oil and water relative permeability curve for the Big Injun sand in Kaufman well P-7, Clover-Rush Run oilfield.....	11

TABLES

A-1. Core analysis results, Kaufman well P-7.....	14
C-1. Original and adjusted pressure-volume-temperature analyses data, Kaufman well P-7.....	17

RESERVOIR STUDY OF THE WILLIAM KAUFMAN LEASE, CLOVER-RUSH RUN OILFIELD, ROANE COUNTY, W. VA.

by

Karl-Heinz Frohne¹

ABSTRACT

This report presents the findings of a study of a portion of the Clover-Rush Run oilfield located in Roane County, W. Va. The study was made to investigate the possibilities of secondary oil recovery in the Big Injun sandstone underlying the William Kaufman lease. Reservoir properties, original reserves, and primary oil recovery are also presented.

The investigation is based on a core analysis and related laboratory tests, well records, field production data, and subsurface information from the Kaufman property. A theoretical primary oil recovery of 9.7 percent of original oil in place is predicted for the reservoir.

A waterflood performance prediction of a hypothetical pilot area was made by use of a computer. The prediction showed that, based on laboratory oil-water relative permeability curves, the water-injection time needed to initiate oil production is excessive and that the stabilized water-injection and corresponding oil-production rates are very low. This precludes waterflooding the reservoir on an economic basis.

A prediction for secondary oil recovery by gas injection was attempted but could not be completed because essential reservoir data were not available. In July 1965, the lease operator initiated, and is currently conducting, a gas-injection program, but there had been no increase in oil production up to November 1966.

INTRODUCTION

Production records and well logs show that primary oil production from the Big Injun sand has been by solution-gas drive in the Clover-Rush Run oilfield. Solution gas is the most inefficient of natural drives and can be

¹ Petroleum research engineer, Morgantown Petroleum Research Laboratory, Bureau of Mines, Morgantown, W. Va.

expected to recover only 5 to 25 percent (2)² of oil in place. Primary oil recovery from Appalachian area reservoirs is usually in the lower end of this range because of the very low permeability of the hydrocarbon-bearing formations, thus a large part of the oil is unrecovered.

In order to aid the reclamation of this valuable resource, the Bureau of Mines is currently engaged in evaluating methods of increasing the secondary recovery of oil from selected Appalachian area reservoirs. The work, of which this report is a part, is being carried out under the Bureau's Reservoir Evaluation Project by utilizing detailed core analyses and other field data to perform reservoir evaluations and provide secondary recovery recommendations. The plans and objectives of the project have been described in detail in another publication (1).

Even though one of the older Kaufman wells produced from the Big Lime formation, the only zone of consequence underlying the lease is the Big Injun sandstone which is the main area of interest of this report. At the present time, the lease operator is injecting natural gas into the Big Injun formation in order to stimulate oil recovery. This project is described in more detail later in the report.

A preliminary report on the Kaufman lease and the well cored by the Bureau has been published (6).

ACKNOWLEDGMENTS

The cooperation of the Pennzoil Co., operator of the William Kaufman lease, in providing well records, logs, and other data for this report is acknowledged.

GENERAL GEOLOGY

Location and Topography

The Clover-Rush Run oilfield is located in Smithfield and Spencer Districts, Roane County, W. Va. (fig. 1). The area topography is typical of the Appalachian Plateau. Outcropping rocks belong to either the Dunkard Series of the Lower Permian Period or the Monongahela Series of the Pennsylvania Period (5). The rugged terrain, formed by stream erosion of the plateau, consists mainly of narrow V-shaped valleys and steep ridges, although a few bottom lands and flat-topped hills can be found. Maximum elevation differences are on the order of 600 feet.

Area Structure and Stratigraphy

The Clover-Rush Run oilfield lies on the western flank of the Arches Fork anticline, and the Big Injun sand strikes north 30° east (4). In the Kaufman lease area, the sand dips to the northwest at about 70 feet per mile.

²Underlined numbers in parentheses refer to items in the list of references at the end of this report.




FIGURE 1. - Oil-Productive Areas in Roane County, W. Va., and the William Kaufman Lease in the Clover-Rush Run Oilfield.

A generalized geologic column for Roane County illustrates the stratigraphy of the area (fig. 2). Below the outcropping Dunkard and Monongahela formations lie the intermingled sandstones, limestones, shales, and coal seams of the Pennsylvanian Period. Next come the limestones, sands, and shales of the Mississippian Period, including the basal Greenbrier limestone and dolomite and the Keener and Big Injun sandstones which were cored in well P-7 on the William Kaufman lease.


GENERALIZED GEOLOGIC COLUMN			
SYSTEM	FORMATION OR GROUP	ROCK COLUMN	DRILLERS' TERMS
PERMIAN	DUNKARD		WASHINGTON COAL
	MONONGAHELA		
PENNSYLVANIAN	CONEMAUGH		PITTSBURGH COAL
	ALLEGHENY		BIG DUNKARD SAND UPPER FREEPORT COAL
	POTTSVILLE		BURNING SPRINGS SAND
MISSISSIPPIAN	MAUCH CHUNK		ROSEDALE SALT SAND
	GREENBRIER		MAXTON SAND LITTLE LIME BIG LIME
	POCONO		"KEENER" SAND BIG INJUN SAND SQUAW SAND

FIGURE 2. - Generalized Geologic Column of Subsurface Formations, Clover-Rush Run Oilfield.

FIELD DEVELOPMENT AND LEASE HISTORY

Development of Clover-Rush Run Oilfield

The original discovery well for the Clover-Rush Run oilfield was Heasley and Co. well 1, drilled on the L. D. Chambers lease in 1909. An oil-productive area of about 4,200 acres had been outlined by 1926 through development drilling, and by 1961 approximately 350 wells had been completed within the original field limits (fig. 1).

In the summer of 1961 a development boom began; about 60 new wells were drilled, and approximately 1,600 new productive acres were added to the northeastern side of the field by the summer of 1964. A large part of this drilling activity took place on the Kaufman lease.

Initial production from the old wells within the original field boundaries ranged from 2 to 40 barrels of oil per day. The use of hydraulic fracturing then raised the initial oil-production rates of the new development wells to a range of 15 to 250 barrels per day.

History of William Kaufman Lease

The present Kaufman lease (fig. 3) consists of 700 acres and was originally part of a larger Heasley and Co. holding. Sometime between 1909 and 1918, three oil wells were drilled within the lease area. About 1918, the Carter Oil Co. bought the lease and drilled three more producing wells. Next, the Hope Construction and Refining Co. leased the property. By 1920, Hope had also drilled three wells, each of which initially produced less than five barrels of oil per day. Finally the South Penn Oil Co., now the Pennzoil Co., bought the Kaufman lease from Hope in 1943 and completed two new oil wells by 1962.




FIGURE 3. - Structure Contour Map on Top of Big Injun Sand, William Kaufman Lease, Clover-Rush Run Oilfield.

Co. and the Bureau of Mines. The 3½-inch-diameter core was taken with rotary tools using a low-water-loss bentonite water-base mud. The cored interval extended from 2,131 to 2,212 feet with 100-percent recovery.

A group of well logs, including guard, spontaneous potential, 16- and 64-inch normals, continuous velocity, gamma ray-neutron, and caliper, was run after coring operations were completed. The log curves covering the cored interval have been previously published (6).

RESERVOIR DATA

Structure

The Big Injun sandstone underlying the Kaufman lease is at an average depth of 2,200 feet. The reservoir is bounded on the downdip western edge of the field by water and updip by a permeability pinchout which cuts across the northeastern corner of the Kaufman property. The sand ranges in gross thickness from 50 feet on the downdip side of the field to 15 feet updip, and averages 24 feet under the Kaufman lease. Structure and isopachous maps of the Big Injun sand are shown in figures 3 and 4, respectively.

All of the producing wells on the Kaufman lease except one of the wells drilled by South Penn had been abandoned by the summer of 1962 when a new flurry of development activity hit the lease. This drilling program produced 24 new oil wells in the Big Injun sandstone by July 1964 when development was stopped. A permeability pinchout in the formation to the northeast limits the new field addition. The Kaufman property is situated in this area of low to zero permeability, and lease wells had only slight shows of oil on initial completion. After fracturing, however, the wells produced 15 to 50 barrels of oil per day.

CORING AND LOGGING OPERATIONS

Kaufman lease well P-7 was cored in September 1963 by personnel of the Pennzoil




FIGURE 4. - Isopachous Map of the Big Injun Sand, William Kaufman Lease, Clover-Rush Run Oilfield.

Lithology

The cored interval in Kaufman well P-7 included the basal Greenbrier limestone and the Keener and Big Injun sandstone formations. The Greenbrier, locally called Big Lime, is light gray to gray brown, is slightly sandy and oolitic, and contains traces of glauconite (6). The basal section consists of light gray to tan, granular, calcareous, and glauconitic dolomite bottomed by a conglomerate of calcium carbonate, cemented quartz pebbles, and pieces of limestone.

The conglomerate grades into what is known locally as the Keener sandstone which extends from 2,168 to 2,182 feet. This is a white, medium- to coarse-grained, calcareous sandstone with a quartz pebble, limestone fragment, and clay material conglomerate at the bottom.

The Keener is immediately followed by the oil-productive Big Injun, a light-gray, fine-grained, subgraywacke sandstone that covers the interval 2,182 to 2,206 feet. The formation is glauconitic, very slightly calcareous, and contains traces of mica and argillaceous material. The argillaceous matter consists of illite and kaolinite which, together with montmorillonite, coat the quartz grains and occupy some of the pore spaces. The quartz grains are poorly sorted and loosely bonded, primarily by the coating clay material.

Core Analysis

The Kaufman lease contains 800 acres, 567 of which are considered oil productive based on logs and production records of wells. Kaufman well P-7, located near the center of the productive area and one of the best producers on the lease, has a total sand thickness of 24 feet for the Big Injun.

Using 0.1 millidarcy as a limiting minimum permeability, only 12.5 feet, or 52 percent of the total interval of well P-7, are considered effective net sand. This factor has been applied to the effective area gross sand volume of the lease, as determined from the isopachous map, to give an areally weighted average net sand thickness of 12.7 feet.

Core data for the Big Injun sand in Kaufman well P-7 are summarized below:

	Interval	
	Effective	Total
Thickness.....feet..	12.5	24.0
Air permeability..... millidarcy..	.8	.5
Porosity.....percent..	15.2	12.7
Saturation:		
Oil.....do..	8.7	7.4
Water.....do..	65.1	68.0

Complete core analysis data for the portion of the cored interval, which includes the Keener and Big Injun sands, are presented in table A-1.

Log Analysis

Quantitative analyses of the logs run in Kaufman well P-7 gave no conclusive results for the Big Injun reservoir. Water saturations calculated from guard log resistivities and core porosities gave an average value of 25 percent for the gross sand interval. This is much lower than the established area saturation of approximately 50 percent. A possible explanation for the low reading is that fresh-water-mud filtrate may have invaded the logged interval.

Porosities for the Big Injun sandstone were calculated from both neutron and velocity logs. The average neutron log value of 9.5 percent is lower than the core analysis figure of 12.7 percent, which may be due to the presence of free gas saturation in the formation. The velocity log, however, gave a value of 21.7 percent. This high porosity may be the result of velocity log signal attenuation, or cycle skipping; also due to a free-gas saturation.

The caliper log showed that the borehole was very uniform and in-gage through the Big Injun interval, indicating a uniformly hard formation.

Reservoir Limits

As mentioned previously, only 567 acres of the 800-acre Kaufman property are considered commercially oil productive. The remaining 233 acres (fig. 4) have not been assigned reserves. This is based on Kaufman well P-3, the only well drilled on this part of the lease. The exact location of this well is not known, but its approximate position is shown in figure 1. No formal records are available for well P-3, but operating personnel believe that the well was plugged and abandoned shortly after completion. Only a few quarts of oil were bailed out after the well was shot with nitroglycerin.

The eastern side of the commercially nonproductive area is formed arbitrarily by the lease line, and the western and southern sides are based on one-half well spacing from the adjacent row of Kaufman lease wells. During 1964 and 1965, the M & M Drilling Co. of Spencer, W. Va., drilled and completed four gas wells (fig. 1) about 900 feet east of the Kaufman lease. The wells had estimated initial open flows of 1 million cubic feet per day, and oil production ranged from a show to 20 barrels per day.

In view of this production to the east, only a test well, completed with modern techniques in the portion of the lease now considered nonproductive, will determine if the formation underlying this part of the Kaufman property contains any producible oil reserves.

Reservoir Temperature and Pressure

On May 1, 1964, several bottom-hole surveys were taken in Kaufman well P-7. One of the measurements was a reservoir temperature survey which recorded a formation temperature of 74° F for the Big Injun sand.

Leasewide bottom-hole pressure surveys were conducted on three occasions on wells on the Kaufman property. Tests run in November 1963, gave an areally weighted average pressure of 462 psig for the Big Injun sand; in June 1964, the pressure was 379 psig; and in May 1965, it had dropped to 268 psig.

Since the formation in the lease area had been tapped as early as 1909 when reservoir-pressure surveys were unheard of, an original formation pressure had to be estimated. Using established area pressure gradients applicable to the Big Injun sandstone, the original formation pressure was estimated as 700 psig. The original crude oil is assumed to have been saturated at the initial reservoir pressure of 700 psig.


Permeability

Permeability measurements were made in the laboratory on sample plugs cut at 1-foot intervals from the core material from Kaufman well P-7. The average air permeabilities of the gross and net effective intervals of the Big Injun sandstone are 0.5 and 0.8 millidarcy, respectively. These values illustrate the extreme tightness of the sand, especially since well P-7 is considered the best oil producer on the lease. Core analysis results, including a complete list of permeabilities, are given in table A-1.

Reservoir-Fluid Saturations

Oil and water saturations were also measured at 1-foot intervals along the core. Average oil and water saturations of the effective net interval are 8.7 and 65.1 percent, respectively. These values cannot be considered representative since the well was cored with a fresh-water-base drilling mud, and because filtrate invasion and solution-gas expansion undoubtedly took place during coring.

Analysis of the electric log gave an average water saturation of 25 percent over the gross sand interval. This value, also, may be too low because of mud filtrate invasion of the logged formation.



Finally, a graph of capillary pressure versus water saturation (fig. 5) prepared from laboratory test data shows an irreducible water saturation of 51 percent. This value is in agreement with established saturations of the Big Injun sandstone in the area and is used in this report.

To date, no water has been produced from the Kaufman lease, and the 51-percent saturation is considered immobile and equal to the original reservoir water saturation. The original oil saturation would then be 49 percent, based on the assumption that the reservoir was initially 100 percent liquid filled.

FIGURE 5.- Capillary Pressure Versus Water Saturation for the Big Injun Sand in Kaufman Well P-7, Clover-Rush Run Oilfield.

Reservoir-Fluid Properties

Because the area under study has been produced since 1909, no direct analysis of the original reservoir fluids is available. However, a reservoir-fluid sample taken from Kaufman well P-7 in May 1964, when the bottom-hole sampling pressure of the well was 483 psig, was analyzed. By using a technique reported by Clark (1), and several assumed factors, this fluid analysis has been adjusted to represent the original reservoir fluid.

An outline for pressure-volume-temperature analysis tests necessary to fully utilize the above adjustment procedure is given in appendix B. The outline applies where the fluid sampling pressure is lower than the original reservoir pressure. The adjustment procedure and original and adjusted PVT analysis data for Kaufman well P-7 are given in appendix C.

In May 1964, the stock-tank crude oil gravity was 48.3° API at 60° F and the crude oil viscosity was 2.43 centipoises at 77° F.

RESERVOIR PERFORMANCE

Primary-Performance Prediction

The primary-recovery mechanism of the Big Injun sandstone under the Kaufman property is a dissolved-gas or depletion drive. This production method is inherently the most inefficient natural drive and, in the Appalachian area, will usually produce only about 5 to 25 percent of the oil in the reservoir.

The crude oil originally in place was calculated volumetrically, using core, electric log, and fluid analysis data, and was found to be 3,291,000 stock-tank barrels, or 457 barrels per acre-foot. A prediction of primary recovery was then made by analysis (3) of the production-decline curve (fig. 6) for the Kaufman lease. Overall primary recovery over the producing life from the original reservoir pressure of 700 psig to theoretical lease abandonment conditions--10 barrels of oil per day--was calculated to be 319,000 stock-tank barrels of oil. This represents a recovery of 9.7 percent of the oil in place, or 44 barrels per acre-foot, by primary solution-gas drive. Theoretical abandonment conditions would be reached in April 1970.

Secondary Recovery

Waterflood Prediction

A computer prediction for theoretical secondary oil recovery by waterflooding the Big Injun sandstone under the Kaufman property was made. The hypothetical pilot area consisted of a pattern of four 5-spots totaling 23 acres. An essential part of the prediction is based on the oil-water relative permeability curves obtained in the laboratory (fig. 7). As can be seen from the curves, the relative permeability to oil at initial conditions is good. This may explain the initial completion gages of 15 to 50 barrels of oil per day after fracturing. The relative permeability to water, however, stays very low through the laboratory test range of water saturations.




FIGURE 6. - Production Decline Curve for the William Kaufman Lease, Clover-Rush Run Oilfield.




FIGURE 7. - Oil and Water Relative Permeability Curve for the Big Injun Sand in Kaufman Well P-7, Clover-Rush Run Oilfield.

Due to this low relative water permeability, the predicted time required to fill the initial gas saturation space in the pilot area with water and for oil production to begin is 17 years. After fill-up, the stabilized water-injection rate reached was less than one-half barrel per well per day, and the oil-production rates were correspondingly low. These low water-injection and oil-production rates preclude waterflooding the lease on an economic basis under present-day reservoir technology.

Gas-Injection Project

A prediction of secondary-recovery performance by gas injection could not be made because of the absence of essential data, such as a gas-oil relative permeability relationship. Several attempts to determine a K_g/K_o curve in the laboratory failed because of the tightness of the core samples. Reasonable theoretical K_g/K_o curves could not be estimated for the same reason.

At the present time, the lease operator is conducting a gas-injection program on the property. The project was started July 1, 1965, with the reinjection of lease-produced gas into four wells (fig. 3). Lease injection volumes have averaged 400,000 to 500,000 cubic feet per day since the project was begun.

To date, there has been gas breakthrough in several producing wells, including well P-7. The rapidity with which breakthrough occurred in some wells seems to indicate at least partial communication between injection and producing wells. The communication may possibly be through joints or hydraulically induced fractures. An east-west trend in the direction of communication has also been observed.

After 14 months of gas injection, no production increase was noted. In the last few months, however, the rate of decline of oil production has been partially arrested. A program to decrease the high producing gas-oil ratios in order to conserve reservoir energy was recently initiated by selectively choking back some producers.

SUMMARY

Because of the inherent inefficiency of the solution-gas drive, primary recovery will be only a fraction of the oil reserves in the Big Injun sand, and more than 90 percent of the oil will be left behind in the reservoir. Secondary recovery by waterflooding is precluded by the relative oil-water permeability characteristics of the sand, and a prediction of secondary recovery by gas injection could not be made because essential reservoir data were not available. In order to stimulate oil production, the Kaufman lease operator is currently reinjecting natural gas into the producing formation.

REFERENCES

1. Clark, Norman J. Adjusting Oil Sample Data for Reservoir Studies. J. Petrol. Technol., v. 14, No. 2, February 1962, pp. 143-149.
2. Cole, Frank W. Reservoir Engineering Manual. Gulf Publishing Co., Houston, Tex., 1961, pp. 34-35.
3. Guerrero, E. T. How to Determine Performance and Ultimate Recovery by Exponential Decline Curve Analysis. Oil and Gas J., v. 59, No. 21, May 22, 1961, pp. 86-87.
4. Haught, Oscar L. Map of Wirt, Roane and Calhoun Counties Showing Oil and Gas Fields. W. Va. Geol. and Econ. Survey, 1958.
5. Hennen, R. V. Wirt, Roane, and Calhoun Counties. W. Va. Geol. Survey County Repts., 1911, pp. 507, 519-520.
6. Overbey, William K., Jr., and Donald M. Evans. Appalachian Region Oilfield Reservoir Investigations, Basal Greenbrier Limestone and Dolomite and "Keener" and Big Injun Sands, Clover-Rush Run Field, Smithfield District, Roane County, W. Va. Producers Monthly, v. 29, No. 5, May 1965, pp. 22-24.
7. Wasson, James A., Harry R. Johnson, and Dean W. Boley. Secondary Oil Recovery Possibilities--Cow Run Sand, Burning Springs Pool, Wirt County, W. Va. BuMines Rept. of Inv. 6460, 1964, 57 pp.

APPENDIX A. -- CORE ANALYSIS DATA FOR KAUFMAN WELL P-7

TABLE A-1. - Core analysis results, Kaufman well P-7

Sample	Depth, ft	Air permeability, md	Porosity, pct	Fluid saturation, percent pore space		Oil content, bbl/acre-ft	Salinity, equivalent NaCl, ppm
				Oil	Water		
1,304	2,140.0	<0.1	0.1	(1)	(1)	(1)	(1)
1,305	2,141.0	<1	.6	-	-	-	-
1,306	2,142.0	<1	.6	-	-	-	-
1,307	2,148.9	<1	.1	-	-	-	-
1,308	2,150.4	<1	4.9	-	-	-	-
1,309	2,151.0	<1	5.1	-	-	-	-
1,310	2,151.4	<1	4.5	-	-	-	200,000
1,311	2,152.6	<1	6.3	-	-	-	-
1,312	2,161.0	<1	5.4	-	-	-	194,000
1,313	2,165.0	<1	.4	-	-	-	200,000
1,314	2,165.6	.5	1.7	-	-	-	159,000
1,315	2,166.0	<1	1.5	-	-	-	-
1,316	2,166.4	<1	1.5	-	-	-	-
1,317	2,167.0	<1	2.1	-	-	-	-
1,318	2,167.4	<1	1.6	-	-	-	-
1,319	2,168.0	<1	1.9	-	-	-	-
1,320	2,168.5	<1	.6	-	-	-	146,000
1,321	2,169.0	.2	3.2	-	-	-	-
1,322	2,169.6	.3	3.5	8.8	17.1	23	-
1,323	2,170.2	.2	5.4	-	-	-	-
1,324	2,170.9	.2	6.3	4.3	27.8	18	-
1,325	2,171.5	.1	6.1	1.8	16.9	9	13,000
1,326	2,172.0	.5	8.1	4.0	31.8	19	-
1,327	2,172.5	.3	5.7	-	-	-	-
1,328	2,173.0	.3	5.3	-	-	-	-
1,329	2,174.0	.2	5.3	21.4	12.8	90	317,000
1,330	2,175.0	<1	4.0	-	-	-	-
1,331	2,175.5	<1	2.6	4.9	75.1	-	-
1,332	2,177.0	.5	2.4	-	-	-	-
1,333	2,177.8	<1	1.8	-	-	-	116,000
1,334	2,178.2	.1	11.6	-	-	-	-
1,335	2,179.0	.8	11.6	-	-	-	-
1,336	2,179.4	1.7	11.9	5.7	63.5	52	-
1,337	2,180.0	<1	3.5	.1	52.0	1	-
1,338	2,180.5	.6	12.7	-	-	-	178,000
1,339	2,181.0	<1	2.9	-	-	-	-
1,340	2,182.0	.1	12.4	-	-	-	-
1,341	2,182.5	.4	14.8	3.5	70.1	35	-
1,342	2,183.0	.2	11.9	-	-	-	-
1,343	2,184.0	<1	7.8	-	-	-	176,000
1,344	2,185.0	.1	13.3	-	-	-	-
1,345	2,186.0	.1	11.5	2.1	73.9	22	-
1,346	2,187.0	<1	2.6	2.1	85.2	20	188,000
1,347	2,188.0	<1	2.6	-	-	-	-
1,348	2,189.0	.2	13.5	-	-	-	-
1,349	2,190.0	<1	12.0	3.1	69.9	34	190,000
1,350	2,191.0	.4	14.3	3.2	77.0	31	-
1,351	2,192.0	<1	5.2	14.3	56.7	160	-
1,352	2,193.0	.5	16.5	4.6	80.7	19	200,000
1,353	2,194.0	1.0	16.5	9.6	61.3	124	-
1,354	2,195.0	.6	16.5	11.0	61.5	142	-
1,355	2,196.0	1.2	15.4	8.7	61.4	113	188,000
1,356	2,197.0	1.1	15.5	8.6	67.2	104	-
1,357	2,198.0	1.0	15.6	8.8	67.9	106	-
1,358	2,199.0	.5	15.2	9.4	64.8	115	184,000
1,359	2,200.0	.8	16.4	9.2	68.5	109	-
1,360	2,201.0	1.1	15.0	8.9	61.9	115	-
1,361	2,201.7	1.8	15.5	10.3	63.9	120	183,000
1,362	2,209.0	.1	13.1	8.0	64.6	97	-
1,363	2,212.0	.1	10.2	-	-	-	-
Average	-	.4	9.3	7.1	58.1	70	159,000

No test run.

APPENDIX B. --RECOMMENDED ANALYSES FOR PRESSURE-VOLUME-TEMPERATURE SAMPLES
AT PRESSURES BELOW ORIGINAL RESERVOIR PRESSURE

The following tests are considered necessary for maximum use of pressure-volume-temperature (PVT) data in reservoir calculations:

(If the PVT sample is saturated, record test data relative to oil at reservoir temperature and pressure at sampling time; if not saturated, relate the data to oil at saturation pressure and reservoir temperature.)

1. Differential liberation at reservoir temperature at different pressures, including liberated gas, gas specific gravity and compressibility, and oil shrinkage factors.
2. Flash separation of sample oil in 0, 25, 50, and 100 psig separators, recording separator GOR, oil shrinkage, and oil API gravity.
3. Pressure-volume relationship at reservoir temperature, including thermal expansion.
4. Oil viscosity at various pressures, and oil compressibility over several pressure ranges.

The foregoing PVT analysis data can then be adjusted to original reservoir conditions for use in reservoir calculations (1).

APPENDIX C. ---PRESSURE-VOLUME-TEMPERATURE ANALYSIS ADJUSTMENT PROCEDURE

Given a PVT analysis taken at a pressure lower than initial conditions, the procedure and equations outlined below (1) can be used to adjust the PVT data to original reservoir conditions.

- Given
- P_i = estimated original reservoir pressure = 700 psig,
 - P_s = reservoir pressure at PVT sampling time = 468 psig,
 - P = some lower pressure = 400 psig,
 - T_r = reservoir temperature = 74° F,
 - G_{1s} = differentially liberated gas from P_s to P
= 25 scf per bbl of saturated oil at P_s , T_r ,
 - G_1 = adjusted gas value, scf per bbl of saturated oil at P_i , T_r ,
 - B_o/B_{os} = differential shrinkage factor, bbl saturated oil at P per bbl saturated oil at P_s , T_r ,
 - B_o/B_{oi} = adjusted differential shrinkage factor, bbl saturated oil at P per bbl saturated oil at P_i , T_r ,
 - B_o = adjusted formation volume factor, bbl saturated oil at P per bbl stock-tank oil,
 - SF = adjusted flash shrinkage factor, stb oil per bbl initial reservoir oil,
 - CGV = corrective gas volume, cu ft gas per bbl oil at P_s , T_r ,
 - COV = corrective oil volume, bbl oil at P_i , T_r per bbl oil at P_s , T_r .

Find

$$\begin{aligned}
 CGV &= \frac{P_i - P}{P_s - P} (G_{1s}) & (1) \\
 &= \frac{700 - 468}{468 - 400} (25) \\
 &= 85 \text{ scf,}
 \end{aligned}$$

$$\begin{aligned}
 \text{COV} &= 1 + \left[\left(\frac{P_1 - P_s}{P_s - P} \right) \left[(B_o/B_{os} \text{ at } P_s) - (B_o/B_{os} \text{ at } P) \right] \right] \quad (2) \\
 &= 1 + \left[\left(\frac{700 - 468}{468 - 400} \right) [1.0000 - 0.9920] \right] \\
 &= 1.027 \text{ bbl at } p_1, T_r / \text{bbl at } p_s, T_r,
 \end{aligned}$$

$$G_1 = \frac{G_{1s} + \text{COV}}{\text{COV}}, \quad (3)$$

$$B_o/B_{oi} = \frac{B_o/B_{os}}{\text{COV}}, \quad (4)$$

$$B_o = \frac{B_o/B_{oi}}{SF} \quad (5)$$

This adjustment procedure is applied to Kaufman well P-7 in table C-1.

TABLE C-1. - Original and adjusted pressure-volume-temperature analyses data, Kaufman well P-7

Reservoir pressure, psig ¹	G _{1s} ¹	G ₁ ²	B _o /B _{os} ¹	B _o /B _{oi} ²	B _o ²
700.....	-	0	-	1.000	1.264
468.....	4	87	1.0000	.974	1.231
450.....	10	92	.9976	.971	1.228
400.....	29	111	.9920	.966	1.221
300.....	68	149	.9752	.950	1.201
200.....	112	192	.9556	.930	1.176
100.....	166	244	.9306	.906	1.145
0.....	340	414	.8193	.798	1.009

¹Original PVT analysis data.

²Adjusted values.

Section 9

Operating Requirements

Section No. 9

The current operating conditions of this disposal well are:

Average daily volume – 2 bbl.

Maximum daily rate- 50 bbl.

Average daily injection pressure 380 psig

Maximum injection pressure – 686 psig

2. The attached Appendix G lists the wells served by this disposal well
3. The injection fluid was sampled and analyzed for the required constituents. A copy of the analysis is enclosed in Fig No. 10.
4. Currently no additives are utilized in the injection fluid.
5. The tubing / casing annulus is filled with fresh water and packer fluid (corrosion inhibitor (1 gal /1000 gal fresh water)). The MSDS for Baker CRW 1321 (packer fluid) is attached in Fig No. 11.
6. In the event of the discovery of a well failure the injection well will immediately be shut in. The surface casing in this injection well is set at 466' and cemented to surface. The depth of this casing is well below any USDW in the area. If there is a failure in the injection string (tubing) there will still be three levels of protection between the injection fluid and any USDW. These three layers are the 4 ½" casing, 8 5/8" casing, and the cement outside of the 8 5/8" casing. The tubing / casing annulus is shut in with approximately 25 psig held. The well tender checks this pressure when he visits the well. Any failure will be quickly noticed and the well shut in. In the event of a mechanical integrity failure that cannot be repaired immediately the produced water will either be disposed of in a commercial disposal well or the producing wells shut in until the well can be repaired.

	Appendix G		
	Wells Serviced by Injection Wells		
API #	Operator	Well No.	Producing Formation
47-087-03022	Delta Helix Energy, LLC	1	Big Injun
47-087-01955	Delta Helix Energy, LLC	6	Big Injun
47-087-04492	Delta Helix Energy, LLC	601	Big Injun
47-087-02435	Delta Helix Energy, LLC	4	Devonian Shale
47-087-03050	Delta Helix Energy, LLC	1	Big Injun
47-087-02436	Delta Helix Energy, LLC	5	Big Injun
47-087-02994	Delta Helix Energy, LLC	6	Big Injun
47-087-03032	Delta Helix Energy, LLC	7	Big Injun
47-087-03247	Delta Helix Energy, LLC	8	Big Injun
47-087-03035	Delta Helix Energy, LLC	10	Big Injun
47-087-03033	Delta Helix Energy, LLC	11	Big Injun
47-087-02993	Delta Helix Energy, LLC	15	Big Injun
47-087-02438	Delta Helix Energy, LLC	17	Big Injun
47-087-02439	Delta Helix Energy, LLC	18	Big Injun
47-087-00913	Delta Helix Energy, LLC	21	Big Injun
47-087-01076	Delta Helix Energy, LLC	23	Big Injun
47-087-03076	Delta Helix Energy, LLC	2	Big Injun
47-087-02980	Delta Helix Energy, LLC	3	Big Injun
47-087-03075	Delta Helix Energy, LLC	4	Big Injun
47-087-02995	Delta Helix Energy, LLC	14	Big Injun
47-087-01872	Delta Helix Energy, LLC	16	Big Injun
47-087-01927	Delta Helix Energy, LLC	17	Big Injun
47-087-01962	Delta Helix Energy, LLC	18	Big Injun
47-087-01953	Delta Helix Energy, LLC	19	Big Injun
47-087-00970	Delta Helix Energy, LLC	W-2	Big Injun
47-087-00971	Delta Helix Energy, LLC	W-3	Big Injun
47-087-00978	Delta Helix Energy, LLC	W-4	Big Injun
47-087-00984	Delta Helix Energy, LLC	W-5	Big Injun
47-087-00987	Delta Helix Energy, LLC	W-6	Big Injun
47-087-00988	Delta Helix Energy, LLC	W-8	Big Injun
47-087-00992	Delta Helix Energy, LLC	W-10	Big Injun
47-087-00993	Delta Helix Energy, LLC	W-11	Big Injun
47-087-00994	Delta Helix Energy, LLC	W-12	Big Injun
47-087-00995	Delta Helix Energy, LLC	W-13	Big Injun
47-087-00996	Delta Helix Energy, LLC	W-14	Big Injun
47-087-01004	Delta Helix Energy, LLC	W-15	Big Injun
47-087-01032	Delta Helix Energy, LLC	W-16	Big Injun
47-087-01053	Delta Helix Energy, LLC	W-17	Big Injun
47-087-01055	Delta Helix Energy, LLC	W-18	Big Injun
47-087-01068	Delta Helix Energy, LLC	W-20	Big Injun

	Appendix G		
	Wells Serviced by Injection Wells		
API #	Operator	Well No.	Producing Formation
47-087-01079	Delta Helix Energy, LLC	W-21	Big Injun
47-087-02981	Delta Helix Energy, LLC	4	Big Injun
47-087-00894	Delta Helix Energy, LLC	5	Big Injun
47-087-00909	Delta Helix Energy, LLC	6	Big Injun
47-087-00963	Delta Helix Energy, LLC	7	Big Injun
47-087-01923	Delta Helix Energy, LLC	29	Big Injun
47-087-04489	Delta Helix Energy, LLC	604	Big Injun
47-087-04490	Delta Helix Energy, LLC	605	Big Injun
47-087-04491	Delta Helix Energy, LLC	606	Big Injun
47-087-02578	Delta Helix Energy, LLC	3	Devonian Shale
47-087-03040	Delta Helix Energy, LLC	1	Big Injun
47-087-00027	Delta Helix Energy, LLC	2	Big Injun
47-087-03041	Delta Helix Energy, LLC	3	Big Injun
47-087-01026	Delta Helix Energy, LLC	5	Big Injun
47-087-01095	Delta Helix Energy, LLC	6	Big Injun
47-087-01096	Delta Helix Energy, LLC	7	Big Injun
47-087-04493	Delta Helix Energy, LLC	602	Big Injun
47-087-00565	Delta Helix Energy, LLC	2	Big Injun
47-087-02743	Delta Helix Energy, LLC	3	Big Injun
47-087-03061	Delta Helix Energy, LLC	6	Big Injun
47-087-03030	Delta Helix Energy, LLC	10	Big Injun
47-087-03047	Delta Helix Energy, LLC	11	Big Injun
47-087-02988	Delta Helix Energy, LLC	12	Big Injun
47-087-03013	Delta Helix Energy, LLC	13	Big Injun
47-087-03053	Delta Helix Energy, LLC	14	Big Injun
47-087-03048	Delta Helix Energy, LLC	15	Big Injun
47-087-03045	Delta Helix Energy, LLC	17	Big Injun
47-087-03029	Delta Helix Energy, LLC	19	Big Injun
47-087-03031	Delta Helix Energy, LLC	23	Big Injun
47-087-02986	Delta Helix Energy, LLC	24	Big Injun
47-087-00889	Delta Helix Energy, LLC	26	Big Injun
47-087-01027	Delta Helix Energy, LLC	27	Big Injun
47-087-01072	Delta Helix Energy, LLC	28	Big Injun
47-087-01086	Delta Helix Energy, LLC	29	Big Injun
47-087-01873	Delta Helix Energy, LLC	31	Big Injun
47-087-01954	Delta Helix Energy, LLC	32	Big Injun
47-087-02082	Delta Helix Energy, LLC	33	Big Injun

4708701056

Kaufman W-7 & W-19 Injection / Production Facility Quarterly Inspection

To be performed first day of each calendar quarter

Date 10-23-24

Person performing inspection Dakota C.

Produced water tanks

Gas vents ✓

Gas Blanket supply, regulator, piping N/A

Produced water Injection Pump

Suction/discharge piping ✓

Bypass Regulator & line ✓

Water meter ✓

Pressure recorder ✓

Separator

Vessel ✓

Piping ✓

Dump Valves ✓

Regulator ✓

Oil Storage tanks

Tanks ✓

Piping ✓

Items needing attention:

Copies to Forman and Parkersburg office

STEP RATE TEST 1987

RECEIVED
JAN 04 1988

DIVISION OF OIL & GAS
DEPARTMENT OF ENERGY

UIC PERMIT UIC2DO870985

WELLHEAD PRESSURE INCREASE JUSTIFICATION

W. M. KAUFMAN NO. W-7

CLOVER FIELD - BIG INJUN RESERVOIR

PENNZOIL PRODUCTS COMPANY

EXPLORATION & PRODUCTION DIVISION

NOEL W. PUTSCHER

DECEMBER 29, 1987

INTRODUCTION

The purpose of this report is to provide test data to the West Virginia Department of Energy, Division of Oil & Gas, which justifies increasing wellhead injection pressure on Roane 0985 from 694 psig to 1000 psig. The West Virginia Department of Energy recently issued an Underground Injection Control permit for Roane 0985 which limited surface pressure to 694 psig. Pennzoil Products Company, operator of subject well, performed a step-rate test to determine the pressure at which the Big Injun would part in the subject well.

DISCUSSION

A step-rate injectivity test is normally used to estimate fracture pressure in an injection well.¹ Fluid is injected at a series of increasing rates, with each rate preferably lasting the same length of time. In relatively low permeability formations ($k < 5$ md) each injection rate should last about 1 hour; 30 minute injection times are adequate for formations with permeability exceeding 10 md. As few as four rates may be used, but normally six, seven or eight rates are preferred. The analysis consists of plotting injection pressure at the end of each rate vs injection rate. It is preferable to plot bottom-hole pressure, but surface pressure may be used if it is positive throughout the test and friction effects are not significant. The plot should have two straight line segments. The break in the line indicates formation fracture pressure.

TEST RESULTS

On December 16, 1987, a step-rate test was run on Roane 0985. The initial pressure was 545 psi and was increased to 1160 psig, with five points in between. With each rate increase the pressure was read after at least one hour had passed. The results of this test are attached and the parting pressure was found to be 1104 psig. Pennzoil is requesting permission to inject into subject well at a wellhead pressure of 1000 psig.

1 Robert C. Earlougher, Jr., Advances in Well Test Analysis Monograph Series, Society of Petroleum Engineers of AIME, Dallas (1977), Vol. 5, Chapter 7.

STEP RATE TEST
W. M. Kaufman W-7
Clover Field
12/16/87

<u>WHP Press.</u> <u>(psig)</u>	<u>Rate (BPD)</u>
545	49
625	51
840	89
975	114
1040	126
1120	176
1160	269

Step Rate Test
W. M. Kaufman W-7
Clover Field
12/16/87


NWP

Wellhead Press. (psig)

46 0700

10 X 10 TO THE INCH • 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.

K&E



Inj. Rate (BPD)

4708701056

WR-37
12/23/19

**WV DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS
PRE-OPERATION CERTIFICATE FOR LIQUID INJECTION
MECHANICAL INTEGRITY TEST RECORD**

MIT Date: 7/29/20

Operator's Well Name / #: WM Kaufman W-19

API#: 47- 087 - 01056

UIC Permit #: 2D08701056002

Field Name (2R only):

WELL OPERATOR H G Energy LLC

Address: 5260 Dupont Rd
Parkersburg, WV 26101

DESIGNATED AGENT Diane White

Address: 5260 Dupont Rd
Parkersburg, WV 26101

INJECTION FORMATION Big Injun Depth 2202 feet (top) to 2235 feet (bottom)
Perforation Interval 2209'-2220 or Open Hole Interval

INJECTION PERMIT TYPE

☐ 2D Commercial Disposal ☒ 2D Non-Commercial Disposal ☐ 2R Area Permit (EOR) ☐ 3S Solution Mining

INJECTATE TYPE (Check all that apply):

☒ Produced Water ☐ Fresh Water ☐ Completion Flowback Water ☐ Tank & Pipeline Residuals

☐ Drilling Waste Liquids ☐ Solution Mining Waste ☐ Gas (2R) ☐ Other (Specify)

Additives (ie. biocides, inhibitors, etc.) Bactericides and other chemicals necessary to maintain water quality or improve recovery

WELL CONSTRUCTION / CASING PROGRAM

CASING OR TUBING TYPE	SIZE	GRADE	WEIGHT PER FT.	NEW	USED	FOOTAGE USED IN DRILLING	FOOTAGE LEFT IN WELL	CEMENT USED
CONDUCTOR	10 3/4					9	9	CTS
FRESH WATER	8 5/8	H-40	28			466	466	CTS
COAL								
INTERMEDIATE								
PRODUCTION	4 1/2	K-55	9.5	X		2272	2272	45 sks
TUBING	2 3/8	K-55	4.6	X		2103	2103	
LINERS								
PACKER	TYPE: Tension	SIZE: 4" x 2"	DEPTH: 2103'					

MECHANICAL INTEGRITY TEST TYPE

☒ Standard Annulus Pressure Test

Is Test Annulus Filled? ☒ Yes ☐ No If Yes, Specify Fluid Type? fresh water and packer fluid

☐ Pump Line Test ☐ Other (Specify)

MAXIMUM PERMITTED WELLHEAD INJECTION PRESSURE 686 psi **MIT PRESSURE** 1029 psi

MECHANICAL INTEGRITY TEST DESCRIPTION

Pressure tested tubing / casing annulus to 1200 psig for 32 minutes. Chart Attached

(2R Area Permits: If multiple pump lines are tested together, please list wells serviced by the tested pump lines.)

NOTE:

- If the well and the pump line are tested together the MIT pressure must be 1.5 times the maximum permitted injection pressure held for a minimum of 20 minutes with no more than a 5% loss.
- If the well is tested separately, the MIT pressure must be 1.5 times the maximum permitted injection pressure held for a minimum of 20 minutes with no more than a 5% loss.
- If the pump line is tested separately, the MIT pressure shall be the maximum permitted injection pressure plus 100 psi held for a minimum of 20 minutes with no more than a 5% loss. Multiple pump lines can be tested together.
- All MITs must be witnessed by a state inspector. A valid recording chart containing the inspector's signature must accompany this completed form.
- All MITs that fail must be submitted using this form and chart.
- Submit all MIT required documentation to OOG within 30 days of test.
- The mechanical integrity of this well must be demonstrated at least 5 years from this test date and each time work is completed on the well or pump line to continue injection.

The undersigned certify:The MIT was performed on 7/29/20

The well and/or pump line:

☒ demonstrated mechanical integrity or ☐ failed to demonstrate mechanical integrity.The MIT was witnessed by Joe Taylor, Inspector WVDEP - Office of Oil and Gas.H G Energy LLC


Permit Holder Company Name

7/31/20

Date

Roger Heldman

Agent or Responsible Party (Print Name)



Signature

Operations Manager

Title


-----Office of Oil and Gas Use Only:-----

THIS WELL IS AUTHORIZED FOR INJECTION**UP TO A MAXIMUM WELLHEAD INJECTION PRESSURE OF** _____ **psi**

Special Conditions:

UIC Program Manager
 WVDEP-Office of Oil and Gas
Date

4708701056



Section 10

Monitoring

Section No. 10

Pressure and injection volumes are monitored daily for this injection well. These volumes and pressure are recorded by the well tender and reported to his supervisor weekly. In the event the well tender discovers an issue with the injection well or any of the associated facilities he will contact his supervisor immediately to get the issue resolved. The injection information is reported to the WVDEP monthly on Form WR-40. This process has worked successfully for the 30 years this well has been utilized as a disposal well.

Currently the vast majority of the fluid injected at this well is transported by pipeline to the storage tank that serves this injection well. A small portion of the fluid is transported by a small truck with a 500 gal tank from some of the more remote producing wells in this field to the storage tank that serves this injection well. The volumes are recorded and reported weekly. The only fluids injected at this well are those transported via pipeline or small truck from Company operated wells in this field.

INJECTATE ANALYSES

4708701056

FIGURE # 10

W M Kaufman W-7 (2D0870095) & W M Kaufman W-19 (2D08701056)
Injection fluid

Paramater	units	
Chloride	mg/L	125,000
Bromide	mg/L	1,030
Strontium	mg/L	515
Barium	mg/L	174
Iron	mg/L	45.3
Total Dissolved Solids	mg/L	202,000
pH	SI Units	5.62
Specific Gravity		1.132
Manganese	mg/L	1.8
Aluminum	mg/L	0.29
Arsenic	mg/L	0.20
Sodium	mg/L	46,100
Calcium	mg/L	15,300
Sulfate	mg/L	5,000
Radium 226	pCi/L	2.54
Radium 228	pCi/L	11
Gross Alpha	pCi/L	1,685
Gross Beta	pCi/L	1,067

Delta Helix

TABLE 1B. Chemical water quality for station (KPW) associated with ~~HG~~ Energy's Kaufman Water. Kirk Environmental, LLP., October 31, 2024.

PARAMETER	SAMPLING STATION
	KAUFMAN WATER (KPW)
Field Water Temperature (°C)	18.5
Field Dissolved Oxygen (mg/L)	2.44
Field pH (SI Units)	5.62
Field Conductivity (mS)	> 150
DRO (C10-C28)	6.4
ORO (C20-C40)	< 4.0
TPH (C06-C10)	1420
Aluminum (mg/L)	0.29
Arsenic (mg/L)	< 0.20
Barium (mg/L)	174
Calcium (mg/L)	15300
Total Iron (mg/L)	45.3
Manganese (mg/L)	1.8
Sodium (mg/L)	46100
Strontium (mg/L)	515
Benzene (ug/L)	157
Toluene (ug/L)	79.9
Ethylbenzene (ug/L)	3.3
Xylene Total (ug/L)	53.6
TDS (mg/L)	202000
TSS (mg/L)	90.0
Chloride (mg/L)	125000
Bromide (mg/L)	1030
Sulfate (mg/L)	< 5000
TOC (mg/L)	66.7
Gross Alpha (pCi/L)	1.685
Gross Beta (pCi/L)	1,067
Radium-226 (pCi/L)	2.54
Radium-228 (pCi/L)	11.0

56

1.132

Kaufman W-7 & W19 Injectate



GEOCHEMICAL TESTING

Environmental and Energy Analysis

2005 N. Center Ave.
Somerset, PA 15501

814/443-1671
814/445-8666
FAX: 814/445-6729

Thursday, November 7, 2024

Beth Johnson
REIC A DIVISION OF PACE ANALYTICAL
SERVICES LLC
PO BOX 286
225 INDUSTRIAL PARK ROA
BEAVER, WV 25813

Order No.: G2411144

Dear Beth Johnson:

Geochemical Testing received 1 sample(s) on 11/5/2024 for the analyses presented in the following report.

There were no problems with sample receipt protocols and analyses met the TNI/NELAC, EPA, and laboratory specifications except where noted in the Case Narrative or Laboratory Results.

If you have any questions regarding these tests results, please feel free to call.

Sincerely,

Joelle Streczywilk
Environmental Laboratory Manager

Leslie A. Nemeth
Project Manager



Glossary (continued)

- 1 Spike recovery limits are not applicable when the sample concentration exceeds the spike concentration by a factor of four or greater.
- B1 Dilution water blank exceeded method criterion.
- C1 CCV recovery above the acceptance limits. Results may be biased high.
- C2 CCV recovery below the acceptance limits. Results may be biased low.
- C3 ICV recovery above the acceptance limits. Results may be biased high.
- C4 ICV recovery below the acceptance limits. Results may be biased low.
- C5 Positive values verified by second column confirmation.
- C6 Confirmation analysis by another detector or chromatographic column was not performed.
- D1 The analysis did not meet the minimum DO depletion of at least 2 mg/L.
- D2 The analysis did not meet the minimum residual DO of at least 1 mg/L.
- D3 Sample required dilution due to a matrix interference.
- D4 Sample was diluted in the extraction steps due to marked matrix interferences.
- D5 Sample required dilution due to a chloride interference.
- D6 Sample was diluted and the reporting limits were raised to achieve method compliant internal standard recovery.
- D7 Sample was digested at a dilution due to the formation of a post-digestion precipitate.
- 8 Sample was digested at a dilution to achieve method compliant matrix spike recovery.
- D9 Sample was digested at a dilution to meet method compliant digestion criteria.
- E2 Unable to obtain a stable weight within specified limits due to sample matrix. Value is estimated.
- F1 Fecal sample tested positive for residual chlorine.
- H1 Due to under-depletion from the initial dilutions for BOD, the sample was reanalyzed outside the hold time.
- H2 Due to over-depletion from the initial dilutions for BOD, the sample was reanalyzed outside the hold time.
- H3 Sample was re-analyzed outside of hold time due to error during original analysis.
- H4 The Nitrite result used to report Nitrate was analyzed past the 48-hour holding time.
- I1 Internal standard recovery above method acceptance limits. Results are estimated.
- I2 Internal standard recovery was below method acceptance limits. Results are estimated.
- IP One of the instrument performance checks () did not meet the acceptance criteria.
- L1 LCS above the acceptance limits. Result may be biased high.
- L2 LCS below the acceptance limits. Result may be biased low.
- L3 Analyte was spiked into the LCS, but was not recovered.
- M1 Matrix Spike recovery above the acceptance limits.
- M2 Matrix Spike recovery below the acceptance limits.
- 4 The matrix spike failed high for the surrogate.
- M5 The matrix spike failed low for the surrogate.
- M6 The reporting limits were raised due to sample matrix interference.
- M7 Recovery for matrix spike could not be quantified due to matrix interference.
- M8 Analyte was spiked into the MS, but was not recovered.
- M9 Analyte concentration was determined by the method of standard addition (MSA).
- N1 The lab does not hold accreditation from PA-DEP for this parameter by this method
- N2 PADEP does not accredit labs for this analyte by this method.
- N3 The lab is accredited for this method in West Virginia, but not in PA (its primary accrediting body).
- N4 PADEP does not accredit labs for this analyte by this method in drinking water.
- O1 The flashpoint tester cannot detect below 50 degrees F.
- O2 Result is temperature of the sample when flame observed. No flash observed. Result qualified.
- O3 The reporting limits were raised due to the high concentration of non-target compounds.
- O4 Sample was received with headspace.
- O5 Sample was received in incorrect container and is not compliant with 40CFR136 Table II.
- O6 Insufficient sample volume was received to comply with the method.
- P1 The pH of the sample was >2 and is not compliant with 40CFR136 Table II.
- P2 Sample contained residual chlorine and is not compliant with 40CFR136 Table II
- P3 The pH of the sample was <10 and is not compliant with 40CFR136 Table II.
- P4 Field preservation does not meet EPA or method recommendations for this analysis.
- P5 Acid preservation may not be appropriate for the analysis of 2-Chloroethylvinyl ether.
- P6 Sample required additional preservative upon receipt.
- P7 The sample was received unpreserved.
- P8 The pH of the sample was < 9 and is not compliant with 40 CFR136 Table II.
- R Relative Percent Difference (RPD) was above the control limit.
- R1 RPD above control limits between matrix spike and MS duplicates.
- R2 RPD above the control limit between duplicates.
- R3 RSD above the control limit between replicates.
- R4 RPD above control limits between Inorganic Carbon check and spike.
- R5 RPD above control limits between control sample and control sample duplicates.
- S2 Surrogate recovery in the blank was below the control limit.
- S3 Surrogate recovery in the blank was above the control limit.
- S4 Surrogate recovery in the LCS is above the control limit.
- S5 Surrogate recovery in the LCS is below the control limit.
- SR Analyte recovery was outside the accepted recovery limits and above the control limit for RPD.
- T3 Target analyte found in trip/field blank.
- TC The MS tune check (tailing factor) did not meet the acceptance criteria.

Geochemical Testing

Date: 07-Nov-24

CLIENT: REIC A DIVISION OF PACE ANALYTIC

Project:

Lab Order: G2411144

CASE NARRATIVE

No problems were encountered during analysis of this workorder, except if noted in this report.

Under West Virginia's Laboratory Certification Program, Geochemical Testing's Laboratory Certificate I.D. is 141.

Glossary:

H - Method Hold Time exceeded and is not compliant with 40CFR136 Table II.

U - The analyte was not detected at or above the listed concentration, which is below the laboratory quantitation limit.

B - Analyte detected in the associated Method Blank

Q1 - See case narrative ND - Not Detected

MCL - Contaminant Limit J - Indicates an estimated value.

Q - Qualifier QL - Quantitation Limit DF - Dilution Factor

S - Surrogate Recovery outside accepted recovery limits

T - Sample received above required temperature and is not compliant with 40CFR136 Table II.

T1 - Sample received above required temperature

MDA - Minimum Detectable Activity.

** - Value exceeds Action Limit

TICs - Tentatively Identified Compounds.

E - Value above quantitation range



Laboratory Results

Geochemical Testing

Date: 07-Nov-24

CLIENT:	REIC A DIVISION OF PACE ANALYTIC	Client Sample ID:	30730511003
Lab Order:	G2411144		KPW
Project:		Collection Date:	10/31/2024 10:50:00 AM
Lab ID:	G2411144-001	Sampled By:	Pace
Matrix:	AQUEOUS	DateReceived:	11/5/2024 9:50:34 AM

Analyses	Result	Q	MDL	PQL	Units	DF	Date Prepared	Date Analyzed
SPECIFIC GRAVITY								
Specific Gravity	1.132		Analyst: MAG 0.3000	0.300		1		ASTM D1429-08 11/06/24 8:07 AM



Delta Helix

TABLE 1C. Chemical water quality for stations (UKS) and (LKS) associated with ~~HE~~ Energy's
Kaufman Sites. Kirk Environmental, LLP., October 31, 2024.

PARAMETER	SAMPLING STATION	
	UKS	LKS
Field Water Temperature (°C)	13.0	12.8
Field Dissolved Oxygen (mg/L)	6.16	2.24
Field pH (SI Units)	7.32	6.54
Field Conductivity (µS)	632.4	351.5
Stream Flow (ft³/s)	< 1 gpm	0.0
DRO (C10-C28)	< 0.19	< 0.20
ORO (C20-C40)	< 0.38	< 0.40
TPH (C06-C10)	< 200	< 200
Aluminum (mg/L)	0.087	< 0.020
Arsenic (mg/L)	< 0.020	< 0.020
Barium (mg/L)	0.19	0.22
Calcium (mg/L)	54.6	28.5
Total Iron (mg/L)	0.13	0.17
Manganese (mg/L)	0.16	0.40
Sodium (mg/L)	20.1	10.3
Strontium (mg/L)	0.35	0.21
Benzene (ug/L)	< 1.0	< 1.0
Toluene (ug/L)	< 1.0	< 1.0
Ethylbenzene (ug/L)	< 1.0	< 1.0
Xylene Total (ug/L)	< 3.0	< 3.0
TDS (mg/L)	247	150
TSS (mg/L)	15.0	15.0
Chloride (mg/L)	13.4	35.7
Bromide (mg/L)	< 0.10	0.13
Sulfate (mg/L)	28.8	10.9
TOC (mg/L)	4.2	4.0

UKS - upper stream sample

LKS - lower stream sample



Sample: KPW		Lab ID: 30730511003	Collected: 10/31/24 10:50		Matrix: Water	
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
EPA 200.7	Arsenic	ND	mg/L	0.20	11/05/24 13:38	
EPA 200.7	Barium	174	mg/L	0.50	11/05/24 13:40	
EPA 200.7	Calcium	15300	mg/L	50.0	11/05/24 13:40	
EPA 200.7	Iron	45.3	mg/L	0.50	11/05/24 13:38	
EPA 200.7	Manganese	1.8	mg/L	0.050	11/05/24 13:38	
EPA 200.7	Sodium	46100	mg/L	500	11/06/24 18:23	
EPA 200.7	Strontium	515	mg/L	10.0	11/06/24 18:23	N2
SM 2540C-2015	Total Dissolved Solids	202000	mg/L	1000	11/01/24 18:20	
SM 2540D-2015	Total Suspended Solids	90.0	mg/L	5.0	11/01/24 11:16	
EPA 300.0, Rev 2.1	Bromide	1030	mg/L	100	11/20/24 22:08	
EPA 300.0, Rev 2.1	Chloride	125000	mg/L	1000	11/20/24 22:08	
EPA 300.0, Rev 2.1	Sulfate	ND	mg/L	5000	11/20/24 22:08	D3
SM 5310B-2014	Total Organic Carbon	66.7	mg/L	1.0	11/05/24 21:44	
	Collected By	EK			11/01/24 10:04	
	Field pH	5.62	Std. Units		11/01/24 10:04	
	Field Temperature, C	18.5	deg C		11/01/24 10:04	
	Field Specific Conductance	>150 ms	umhos/cm		11/01/24 10:04	
	Oxygen, Dissolved	2.44	mg/L		11/01/24 10:04	
EPA 8015C	TPH (C10-C28)	6.4	mg/L	2.0	11/11/24 21:14	
EPA 8015C	TPH (C28-C40)	ND	mg/L	4.0	11/11/24 21:14	CH
EPA 8015C	TPH (C06-C10)	1420	ug/L	200	11/04/24 17:16	
EPA 8260D	Benzene	157	ug/L	1.0	11/04/24 15:48	
EPA 8260D	Ethylbenzene	3.3	ug/L	1.0	11/04/24 15:48	
EPA 8260D	Toluene	79.9	ug/L	1.0	11/04/24 15:48	
EPA 8260D	Xylene (Total)	53.6	ug/L	3.0	11/04/24 15:48	

Sample: UKS		Lab ID: 30730511004	Collected: 10/31/24 11:20	Matrix: Water		
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
EPA 200.7	Aluminum	0.087	mg/L	0.020	11/04/24 17:14	
EPA 200.7	Arsenic	ND	mg/L	0.020	11/04/24 17:14	
EPA 200.7	Barium	0.19	mg/L	0.0050	11/04/24 17:14	
EPA 200.7	Calcium	54.6	mg/L	0.50	11/04/24 17:14	
EPA 200.7	Iron	0.13	mg/L	0.050	11/04/24 17:14	
EPA 200.7	Manganese	0.16	mg/L	0.0050	11/04/24 17:14	
EPA 200.7	Sodium	20.1	mg/L	0.50	11/04/24 17:14	
EPA 200.7	Strontium	0.35	mg/L	0.010	11/04/24 17:14	N2
SM 2540C-2015	Total Dissolved Solids	247	mg/L	10.0	11/01/24 20:10	
SM 2540D-2015	Total Suspended Solids	15.0	mg/L	2.5	11/01/24 11:16	
EPA 300.0, Rev 2.1	Bromide	ND	mg/L	0.10	11/20/24 22:28	
EPA 300.0, Rev 2.1	Chloride	13.4	mg/L	1.0	11/20/24 22:28	
EPA 300.0, Rev 2.1	Sulfate	28.8	mg/L	5.0	11/20/24 22:28	
SM 5310B-2014	Total Organic Carbon	4.2	mg/L	1.0	11/05/24 22:35	
	Collected By	EK			11/01/24 10:07	
	Field pH	7.32	Std. Units		11/01/24 10:07	
	Field Temperature, C	13.0	deg C		11/01/24 10:07	
	Field Specific Conductance	632.4	umhos/cm		11/01/24 10:07	
	Oxygen, Dissolved	6.16	mg/L		11/01/24 10:07	
	Flow	<1 gpm			11/01/24 10:07	
EPA 8015C	TPH (C10-C28)	ND	mg/L	0.19	11/07/24 04:55	
EPA 8015C	TPH (C28-C40)	ND	mg/L	0.38	11/07/24 04:55	
EPA 8015C	TPH (C06-C10)	ND	ug/L	200	11/04/24 17:52	
EPA 8260D	Benzene	ND	ug/L	1.0	11/04/24 14:57	
EPA 8260D	Ethylbenzene	ND	ug/L	1.0	11/04/24 14:57	
EPA 8260D	Toluene	ND	ug/L	1.0	11/04/24 14:57	
EPA 8260D	Xylene (Total)	ND	ug/L	3.0	11/04/24 14:57	



Sample: LKS		Lab ID: 30730511005	Collected: 10/31/24 12:20	Matrix: Water		
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers
EPA 200.7	Aluminum	ND	mg/L	0.020	11/04/24 17:16	
EPA 200.7	Arsenic	ND	mg/L	0.020	11/04/24 17:16	
EPA 200.7	Barium	0.22	mg/L	0.0050	11/04/24 17:16	
EPA 200.7	Calcium	28.5	mg/L	0.50	11/04/24 17:16	
EPA 200.7	Iron	0.17	mg/L	0.050	11/04/24 17:16	
EPA 200.7	Manganese	0.40	mg/L	0.0050	11/04/24 17:16	
EPA 200.7	Sodium	10.3	mg/L	0.50	11/04/24 17:16	
EPA 200.7	Strontium	0.21	mg/L	0.010	11/04/24 17:16	N2
SM 2540C-2015	Total Dissolved Solids	150	mg/L	10.0	11/01/24 20:11	
SM 2540D-2015	Total Suspended Solids	15.0	mg/L	2.5	11/01/24 11:16	
EPA 300.0, Rev 2.1	Bromide	0.13	mg/L	0.10	11/20/24 12:55	
EPA 300.0, Rev 2.1	Chloride	35.7	mg/L	1.0	11/20/24 12:55	
EPA 300.0, Rev 2.1	Sulfate	10.9	mg/L	5.0	11/20/24 12:55	
SM 5310B-2014	Total Organic Carbon	4.0	mg/L	1.0	11/05/24 22:52	
	Collected By	EK			11/01/24 10:08	
	Field pH	6.54	Std. Units		11/01/24 10:08	
	Field Temperature, C	12.8	deg C		11/01/24 10:08	
	Field Specific Conductance	351.5	umhos/cm		11/01/24 10:08	
	Oxygen, Dissolved	2.24	mg/L		11/01/24 10:08	
	Flow	0.0			11/01/24 10:08	
EPA 8015C	TPH (C10-C28)	ND	mg/L	0.20	11/07/24 05:19	
EPA 8015C	TPH (C28-C40)	ND	mg/L	0.40	11/07/24 05:19	
EPA 8015C	TPH (C06-C10)	ND	ug/L	200	11/04/24 18:10	
EPA 8260D	Benzene	ND	ug/L	1.0	11/04/24 15:22	
EPA 8260D	Ethylbenzene	ND	ug/L	1.0	11/04/24 15:22	
EPA 8260D	Toluene	ND	ug/L	1.0	11/04/24 15:22	
EPA 8260D	Xylene (Total)	ND	ug/L	3.0	11/04/24 15:22	

Sample: TRIP BLANK		Lab ID: 30730511006		Collected: 10/31/24 00:00		Matrix: Water	
Method	Parameters	Results	Units	Report Limit	Analyzed	Qualifiers	
EPA 8015C	TPH (C06-C10)	ND	ug/L	200	11/04/24 18:28		
EPA 8260D	Benzene	ND	ug/L	1.0	11/04/24 14:31		
EPA 8260D	Ethylbenzene	ND	ug/L	1.0	11/04/24 14:31		
EPA 8260D	Toluene	ND	ug/L	1.0	11/04/24 14:31		
EPA 8260D	Xylene (Total)	ND	ug/L	3.0	11/04/24 14:31		

Sample: KPW		Lab ID: 30730511003		Collected: 10/31/24 10:50		Matrix: Water	
PWS:	Site ID:	Sample Type:					
Parameters	Method	Act ± Unc (MDC)	Carr Trac	Units	Analyzed	CAS No.	Qual
Gross Alpha	EPA 900.0	329 ± 886 (1,685)		pCi/L	11/21/24 19:12	12587-46-1	
		C:NA T:NA					
Gross Beta	EPA 900.0	670 ± 606 (1,067)		pCi/L	11/21/24 19:12	12587-47-2	
		C:NA T:NA					
Radium-226	EPA 903.1	490 ± 70.7 (2.54)		pCi/L	11/21/24 15:14	13982-63-3	
		C:NA T:100%					
Radium-228	EPA 904.0	347 ± 65.1 (11.0)		pCi/L	11/18/24 15:11	15262-20-1	
		C:84% T:93%					

SAMPLE QUALIFIERS

Sample: 3441786

[1] Post-analysis pH measurement indicates pH > 2.


Sample: 3441787

[1] Post-analysis pH measurement indicates pH > 2.

ANALYTE QUALIFIERS

CH The continuing calibration for this compound is outside of Pace Analytical acceptance limits. The results may be biased high.

D3 Sample was diluted due to the presence of high levels of non-target analytes or other matrix interference.



ANALYTE QUALIFIERS

- N2 The lab does not hold NELAC/TNI accreditation for this parameter but other accreditations/certifications may apply. A complete list of accreditations/certifications is available upon request.
- S4 Surrogate recovery not evaluated against control limits due to sample dilution.

Reviewed by:

Beth Johnson
(800)999-0105
beth.johnson@pacelabs.com

Pace Analytical Services Pennsylvania

1638 Roseytown Rd Suites 2,3&4, Greensburg, PA 15601

ANAB DOD-ELAP Rad Accreditation #: L2417

ANABISO/IEC 17025:2017 Rad Cert#: L24170

Alabama Certification #: 41590

Arizona Certification #: AZ0734

Arkansas Certification

California Certification #: 2950

Colorado Certification #: PA01547

Connecticut Certification #: PH-0694

EPA Region 4 DW Rad

Florida/TNI Certification #: E87683

Georgia Certification #: C040

Guam Certification

Hawaii Certification

Idaho Certification

Illinois Certification

Indiana Certification

Iowa Certification #: 391

Kansas Certification #: E-10358

Kentucky Certification #: KY90133

KY WW Permit #: KY0098221

KY WW Permit #: KY0000221

Louisiana DHH/TNI Certification #: LA010

Louisiana DEQ/TNI Certification #: 04086

Maine Certification #: 2023021

Maryland Certification #: 308

Massachusetts Certification #: M-PA1457

Michigan/PADEP Certification #: 9991

Missouri Certification #: 235

Montana Certification #: Cert0082

Nebraska Certification #: NE-OS-29-14

Nevada Certification #: PA014572023-03

New Hampshire/TNI Certification #: 297622

New Jersey/TNI Certification #: PA051

New Mexico Certification #: PA01457

New York/TNI Certification #: 10888

North Carolina Certification #: 42706

North Dakota Certification #: R-190

Ohio EPA Rad Approval: #41249

Oregon/TNI Certification #: PA200002-015

Pennsylvania/TNI Certification #: 65-00282

Puerto Rico Certification #: PA01457

Rhode Island Certification #: 65-00282

South Dakota Certification

Tennessee Certification #: TN02867

Texas/TNI Certification #: T104704188-22-18

Utah/TNI Certification #: PA014572223-14

USDA Soil Permit #: 525-23-67-77263

Vermont Dept. of Health: ID# VT-0282

Virgin Island/PADEP Certification

Virginia/VELAP Certification #: 460198

Washington Certification #: C868

West Virginia DEP Certification #: 143

West Virginia DHHR Certification #: 9964C

Wisconsin Approve List for Rad

Pace Analytical Services Beaver

225 Industrial Park Road, Beaver, WV 25813

Virginia VELAP 460148

West Virginia DEP 060

West Virginia DHHR 00412CM

North Carolina DEQ 466

Kentucky Wastewater Certification KY90039

Pennsylvania DEP 68-00839

Face Analytical

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

Billing Information:

Company: Kirk Environmental

Address: Ed Kirk

Report To: Crystal Bennett

Copy To: Kaufman sites

Customer Project Name/Number:

Phone: Site/Facility ID #:

Email: Purchase Order #:

Quote #: Turnaround Date Required:

Collected By (print): Ed J. Kirk

Collected By (signature): [Signature]

Sample Disposal: [X] Dispose as appropriate [] Return [] Archive [] Hold:

Rush: [] Same Day [] 3 Day [] 4 Day [] 5 Day [] Expedite Charges Apply

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Wastewater (WW), Product (P), Soil/Solid (SL), Oil (OL), Wipe (WP), Air (AR), Tissue (TS), Bioassay (B), Vapor (V), Other (OT):

Customer Sample ID

Matrix *

Comp / Grab

Collected for Composite Start

Date Time

Res Cl

Composite End

Date Time

of Ctns

Wet Blue Dry None

Packing Material Used

Radchem sample(s) screened (<500 cpm):

Date/Time: 10/31/24 1530

Received by/Company: (Signature)

Date/Time: 10/31/24 1530

Received by/Company: (Signature)

Date/Time: 10/31/24 1530

Received by/Company: (Signature)

Site Collection Info/Address:

State: County/City: Time Zone Collected: [] PT [] MT [] CT [] ET

Compliance Monitoring? [X] Yes [] No

DW PWS ID #: DW Location Code:

Immediately Packed on Ice: [X] Yes [] No

Field Filtered (if applicable): [] Yes [X] No

Analysis:

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

Container Preservative Type **

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

LAB USE ONLY - Affix Workorder/Log-in Label Here or List Face Workorder Number or MTL Log-in Number Here

WO#: 30730511

PM: BMJ

Due Date: 12/13/24

CLIENT: BV-KIRKENV

LIMS30 Lab Sample Condition Upon Receipt (West Virginia)

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☒ Client ☐ 3rd Party Courier ☐ Pace ☐ Other

Tracking #:

Custody Seal on Cooler/Box/Containers Present: ☐ yes ☒ no

Seals Intact: ☐ yes ☐ no

Thermometer Used

26

Type of Ice: ☒ Wet ☐ Blue ☐ None

Cooler Temperature

Observed Temp

0.4

°C

Correction Factor:

0

°C

Final Temp:

0.4

°C

Thermal Preservation Requirement Met Yes ☒ No ☐

pH paper Lot#

204524

Date and Initials of person examining

contents: 10/31/24 (J-NP)

	Yes	No	N/A	
Chain of Custody Present:	☒	☐	☐	1.
Chain of Custody Filled Out:	☒	☐	☐	2. # of containers missing on 2 COCs
Chain of Custody Relinquished:	☒	☐	☐	3.
Sampler Name & Signature on COC:	☒	☐	☐	4.
Sample Labels match COC:	☒	☐	☐	5.
-Includes date/time/ID				
Matrix: WT				
Samples Arrived within Hold Time:	☒	☐	☐	6.
Short Hold Time Analysis (<72hr remaining):	☒	☐	☐	7.
Rush Turn Around Time Requested:	☒	☐	☐	8.
Sufficient Volume:	☒	☐	☐	9.
Correct Containers Used:	☒	☐	☐	10.
-Pace Containers Used:	☒	☐	☐	
Containers Intact:	☒	☐	☐	11.
Orthophosphate field filtered:	☒	☐	☐	12.
Hex Cr Aqueous sample field filtered:	☒	☐	☐	13.
-pH adjusted within 24 hours? (If yes, indicate acid lot #)	☒	☐	☐	
Filtered volume received for Dissolved tests:	☒	☐	☐	14.
All containers have been checked for chemical preservation:	☒	☐	☐	15.
exceptions: VOA, coliform, O&G, LLMercury, Non-aqueous matrix				
All containers meet method/chemical preservation requirements:	☒	☐	☐	
Initial when completed: ZC				Date: 11/1/24
Tests not preserved:				
Headspace in VOA Vials:	☒	☐	☐	16.
Trip Blank Present:	☒	☐	☐	17.
Initial when completed: ZC				Date: 11/1/24

Comments:

*PM review is documented electronically in LIMS, when the Project Manager closes the SRF Review schedule in LIMS. The status may be reviewed in the Status section of the Workorder Edit Screen.

CHAIN-OF-CUSTODY Analytical Request Document										LAB USE ONLY - Affix Workorder/Login Label Here or List Pace Workorder Number or WTL Log-In Number Here									
Company: <i>Pace Analytical</i> Address: <i>Kirk Environmental</i> Report To: <i>Ed J. Kirk</i> Copy To: <i>Cynthia Brown</i> Customer Project Name/Number: <i>Kirkman sites</i> Phone: _____ Email: _____ Collected By (print): <i>Ed J. Kirk</i> Quote #: _____ Turnaround Date Required: <i>10/24/04</i> Rush: _____ Sample Disposal: _____ Dispose as appropriate: _____ Archive: _____ Hold: _____ * Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product (P), Soil/Solid (SL), Oil (OL), Wipe (WP), Air (AR), Tissue (TS), Bioassay (B), Vapor (V), Other (OT)										Container Preservation Type ** 1 1 2 3 *Preservative Types: (1) nitric acid, (2) sulfuric acid, (3) hydrochloric acid, (4) sodium hydroxide, (5) zinc acetate, (6) methanol, (7) sodium bisulfate, (8) sodium thiosulfate, (9) hexane, (A) ascorbic acid, (B) ammonium sulfate, (C) ammonium hydroxide, (D) TSP, (U) Unpreserved, (O) Other									
Billing Information: State: / County/City: / Time Zone: ☐ PT ☐ MT ☐ CT ☐ ET										Lab Sample Receipt Checklist: Custody Seals Present/Intact: Y N NA Custody Signatures Present: Y N NA Collector Signatures Present: Y N NA Bottles Intact: Y N NA Correct Bottles: Y N NA Sufficient Volume: Y N NA Samples Received on Ice: Y N NA VOA - Headspace Acceptable: Y N NA USDA Regulated Soils: Y N NA Samples in Holding Time: Y N NA Residual Chlorine Present: Y N NA CL Strips: _____ Sample pH Acceptable: Y N NA pH Strips: _____ Sulfide Present: Y N NA Lead Acetate Strips: _____ LAB USE ONLY: Lab Sample # / Comments: _____									
Site Collection Info/Address: State: / County/City: / Time Zone: ☐ PT ☐ MT ☐ CT ☐ ET										Analyses Fe, Mn, Al, As, Na, Cu, Sulfate Chloride, Bromide, Strontium, Barium spec grav, TSS, TDS, TOC Rad 226, Rad 238 Gross Alpha, Gross Beta									
Compliance Monitoring? ☒ Yes ☐ No DW PWS ID #: _____ DW Location Code: _____ Immediately Packed on Ice: ☒ Yes ☐ No Field Filtered (if applicable): ☐ Yes ☒ No Analysis: _____										Lab Sample Temperature Info: Temp Blank Received: Y N NA Therm ID#: 260 Cooler 1 Temp Upon Receipt: 14 °C Cooler 1 Therm Corr Factor: 0 °C Cooler 1 Corrected Temp: 14 °C Comments:									
Customer Remarks / Special Conditions / Possible Hazards: DO 2.44 mg/L Temp 18.5 °C Cond > 150 ms pH 5.62 Relinquished by/Company: (Signature) <i>Ed J. Kirk</i> Date/Time: 10/23/04 15:30 Relinquished by/Company: (Signature) _____ Date/Time: _____ Relinquished by/Company: (Signature) _____ Date/Time: _____										Customer Sample ID KPW Matrix * GW Comp / Grab grab Collected (or Composite Start) Date: 10/24/04 Time: 10:50 Composite End Date: _____ Time: _____ Res CI # of Ctns									
Type of Ice Used: ☒ Wet ☐ Blue ☐ Dry ☐ None Packing/Material Used: _____ Radchem sample(s) screened (<500 cpm): Y N NA Received by/Company: (Signature) _____ Date/Time: 10/23/04 15:30 Received by/Company: (Signature) _____ Date/Time: 10/24/04 23:00 Received by/Company: (Signature) _____ Date/Time: _____										Lab Tracking #: 2959226 Samples received via: FEDEX UPS Client Courier Pace Courier Date/Time: 10/24/04 15:47 Date/Time: 10/24/04 23:00 Date/Time: _____ Table #: _____ Actual: _____ Template: _____ Prelogin: _____ PM: _____ PB: _____									
Customer Remarks / Special Conditions / Possible Hazards: DO 2.44 mg/L Temp 18.5 °C Cond > 150 ms pH 5.62 Relinquished by/Company: (Signature) _____ Date/Time: _____ Relinquished by/Company: (Signature) _____ Date/Time: _____ Relinquished by/Company: (Signature) _____ Date/Time: _____										Lab Sample Temperature Info: Temp Blank Received: Y N NA Therm ID#: 260 Cooler 1 Temp Upon Receipt: 14 °C Cooler 1 Therm Corr Factor: 0 °C Cooler 1 Corrected Temp: 14 °C Comments:									
Customer Remarks / Special Conditions / Possible Hazards: DO 2.44 mg/L Temp 18.5 °C Cond > 150 ms pH 5.62 Relinquished by/Company: (Signature) _____ Date/Time: _____ Relinquished by/Company: (Signature) _____ Date/Time: _____ Relinquished by/Company: (Signature) _____ Date/Time: _____										Lab Sample Temperature Info: Temp Blank Received: Y N NA Therm ID#: 260 Cooler 1 Temp Upon Receipt: 14 °C Cooler 1 Therm Corr Factor: 0 °C Cooler 1 Corrected Temp: 14 °C Comments:									

	DC#_Title: ENV-FRM-GBUR-0088 v07_Sample Condition Upon Receipt-Greensburg
	Effective Date: 01/04/2024

Client Name: Kirk Env.

Project #: 80703081

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client ☐ Commercial ☐ Pace ☒ Other Nice's Initial / Date

Tracking Number: 000-00

Examined By: CB 11-4-24

Custody Seal on Cooler/Box Present: ☒ Yes ☐ No

Seals Intact: ☒ Yes ☐ No

Thermometer Used: 14 Type of Ice: wet Blue None

Labeled By: CB 11-4-24

Temped By: CB 11-4-24

Cooler Temperature: Observed Temp 2.9 °C Correction Factor: -0.5 °C Final Temp: 2.9 °C

Temp should be above freezing to 6°C

Comments:	Yes	No	NA	pH paper Lot# <u>601041</u>	D.P.D. Residual Chlorine Lot #
Chain of Custody Present	☒				
Chain of Custody Filled Out:	☒				
-Were client corrections present on COC		☒			
Chain of Custody Relinquished	☒				
Sampler Name & Signature on COC:	☒				
Sample Labels match COC:	☒				
-Includes date/time/ID					
Matrix: <u>WT</u>					
Samples Arrived within Hold Time:	☒				
Short Hold Time Analysis (<72hr remaining):		☒			
Rush Turn Around Time Requested:		☒			
Sufficient Volume:	☒				
Correct Containers Used:	☒				
-Pace Containers Used		☒			
Containers Intact:	☒				
Orthophosphate field filtered:			☒		
Hex Cr Aqueous samples field filtered:			☒		
Organic Samples checked for dichlorination			☒		
Filtered volume received for dissolved tests:			☒		
All containers checked for preservation:	☒				
exceptions: VOA, coliform, TOC, O&G, Phenolics, Radon, non-aqueous matrix					
All containers meet method preservation requirements:	☒			Initial when completed <u>CB</u>	Date/Time of Preservation
				Lot# of added Preservative	
8260C/D: Headspace in VOA Vials (> 6mm)			☒		
624.1: Headspace in VOA Vials (0mm)			☒		
Radon: Headspace in RAD Vials (0mm)			☒		
Trip Blank Present:			☒	Trip blank custody seal present? YES or NO	
Rad Samples Screened <.05 mrem/hr.	☒			Initial when completed <u>CB</u>	Date: <u>11-4-24</u> Survey Meter SN: <u>2004100</u>
Comments:					

Note: For NC compliance samples with discrepancies, a copy of this form must be sent to the DEHNR Certification office. PM Review is documented electronically in LIMS through the SRF Review schedule in the Workorder Edit Screen.

Qualtrax ID: 55680

WO#: 30730511

PH: BMJ Due Date: 12/13/24
CLIENT: BV-KIRKENV

LIMS30 Lab Sample Condition Upon Receipt (West Virginia)

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☒ Client ☐ 3rd Party Courier ☐ Pace ☐ Other _____

Tracking #: _____

Custody Seal on Cooler/Box/Containers Present: ☐ yes ☒ no

Seals intact: ☐ yes ☐ no

Thermometer Used

26

Type of Ice: Wet Blue None

Cooler Temperature

Observed Temp

0.4

°C

Correction Factor: 0

°C

Final Temp: 0.4

°C

Thermal Preservation Requirement Met Yes ☒ No ☐

pH paper Lot#

204524

Date and Initials of person examining

contents: 10/31/24 (J-NP)

	Yes	No	N/A	
Chain of Custody Present:	☒	☐	☐	1.
Chain of Custody Filled Out:	☒	☐	☐	2. # of ctns missing on 2 COCs
Chain of Custody Relinquished:	☒	☐	☐	3.
Sampler Name & Signature on COC:	☒	☐	☐	4.
Sample Labels match COC:	☒	☐	☐	5.
-Includes date/time/ID				
Matrix: <u>WT</u>				
Samples Arrived within Hold Time:	☒	☐	☐	6.
Short Hold Time Analysis (<72hr remaining):	☒	☐	☐	7.
Rush Turn Around Time Requested:	☒	☐	☐	8.
Sufficient Volume:	☒	☐	☐	9.
Correct Containers Used:	☒	☐	☐	10.
-Pace Containers Used:	☒	☐	☐	
Containers Intact:	☒	☐	☐	11.
Orthophosphate field filtered:	☒	☐	☐	12.
Hex Cr Aqueous sample field filtered:	☒	☐	☐	13.
-pH adjusted within 24 hours? (If yes, indicate acid lot #)				
Filtered volume received for Dissolved tests:	☒	☐	☐	14.
All containers have been checked for chemical preservation:	☒	☐	☐	15.
exceptions: VOA, coliform, O&G, LLMercury, Non-aqueous matrix				
All containers meet method/chemical preservation requirements:	☒	☐	☐	Initial when completed: <u>zc</u> Date: <u>11/1/24</u>
				Tests not preserved:
Headspace in VOA Vials:	☒	☐	☐	16.
Trip Blank Present:	☒	☐	☐	17.
				Initial when completed: <u>zc</u> Date: <u>11/1/24</u>

Comments: _____

*PM review is documented electronically in LIMS, when the Project Manager closes the SRF Review schedule in LIMS. The status may be reviewed in the Status section of the Workorder Edit Screen.



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Certificate of Analysis 4113738

Beth Johnson
Pace Analytical Services LLC Beaver
225 Industrial Park Rd
Beaver, WV 25813

Customer ID: 44-102122
Report Printed: 11/20/2024 15:12

Project Name: WV SDWA Beth Johnson	Workorder: 4113738
------------------------------------	--------------------

Dear Beth Johnson

Enclosed are the analytical results for samples received by the laboratory 11/12/2024 10:58.

The results relate to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services LLC Kentucky - Madisonville

If you have any questions concerning this report, please feel free to contact me.



#460210 Madisonville, KY
#460291 Pikeville, KY
#E871136 Englewood, OH

This page is included as part of the Analytical Report and must be retained as a permanent record thereof.

Melissia Brown, Project Coordinator



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

SAMPLE SUMMARY

Lab ID	Client Sample ID/Alias	Matrix	Date Collected	Date Received	Sampled By
4113738-01	DBP Sample/30732801001 48 Union Camp Rd	Drinking Water	11/08/2024 10:03	11/12/2024 10:58	Julia Childers
4113738-02	DBP Sample/30732801002 48 Union Camp Rd	Drinking Water	11/08/2024 10:03	11/12/2024 10:58	Julia Childers
4113738-03	DBP Sample/30732801003 292 Koons Run Rd	Drinking Water	11/08/2024 10:53	11/12/2024 10:58	Julia Childers
4113738-04	DBP Sample/30732801004 292 Koons Run Rd	Drinking Water	11/08/2024 10:53	11/12/2024 10:58	Julia Childers
4113738-05	DBP Sample/30732801005 Trip Blank	Drinking Water	11/08/2024 10:03	11/12/2024 10:58	Julia Childers

Work Order Comments:

The individual THM / HAA components are rounded then reported.

The total THM / HAA values are calculated from the sum of actual values for the individual analytes. This value is then rounded. It is possible for the total value not to match the sum of the individual components.

If this data is used for regulatory purposes, the total values will be the actual sum of the individual analytes.



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

ANALYTICAL RESULTS

Lab Sample ID: 4113738-01

Sample Collection Date Time: 11/08/2024 10:03

Description: DBP Sample 30732801001 48 Union Camp Rd

Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Volatile Organic Compounds Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Total Trihalomethanes	0.071		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM
Bromodichloromethane	0.012		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM
Bromoform	ND	u	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM
Chloroform	0.058		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM
Dibromochloromethane	0.002		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 09:45	CLM

ANALYTICAL RESULTS

Lab Sample ID: 4113738-02

Sample Collection Date Time: 11/08/2024 10:03

Description: DBP Sample 30732801002 48 Union Camp Rd

Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Gas Chromatography Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Bromoacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Dibromoacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Dichloroacetic Acid	0.006		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Monochloroacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Trichloroacetic Acid	0.018		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD
Total HAA5	0.024		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 22:55	CDD

Surrogate: 2,3-Dibromopropionic aci 107 % 70-130 11/14/2024 08:45 11/14/2024 22:55 CDD EPA 552.3



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

ANALYTICAL RESULTS

Lab Sample ID: 4113738-03

Description: DBP Sample 30732801003 292 Koons Run Rd

Sample Collection Date Time: 11/08/2024 10:53

Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Volatile Organic Compounds Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Total Trihalomethanes	0.048		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM
Bromodichloromethane	0.010		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM
Bromoform	ND	u	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM
Chloroform	0.037		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM
Dibromochloromethane	0.001		mg/L	0.001	0.0005	EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:17	CLM

ANALYTICAL RESULTS

Lab Sample ID: 4113738-04

Description: DBP Sample 30732801004 292 Koons Run Rd

Sample Collection Date Time: 11/08/2024 10:53

Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Gas Chromatography Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Bromoacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Dibromoacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Dichloroacetic Acid	0.012		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Monochloroacetic Acid	ND	u	mg/L	0.001		EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Trichloroacetic Acid	0.015		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD
Total HAA5	0.027		mg/L	0.001	0.0005	EPA 552.3	11/14/2024 08:45	11/14/2024 23:13	CDD

Surrogate: 2,3-Dibromopropionic aci 104 % 70-130 11/14/2024 08:45 11/14/2024 23:13 CDD EPA 552.3



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

ANALYTICAL RESULTS

Lab Sample ID: 4113738-05
Description: DBP Sample 30732801005 Trip Blank

Sample Collection Date Time: 11/08/2024 10:03
Sample Received Date Time: 11/12/2024 10:58

Matrix: Drinking Water

Discharge/Site No:

Regulatory ID: WV3301706

Volatile Organic Compounds Madisonville

Analyte	Result	Flag	Units	MRL	MDL	Method	Prepared	Analyzed	Analyst
Total Trihalomethanes	ND	u	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM
Bromodichloromethane	ND	u	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM
Bromoform	ND	u	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM
Chloroform	ND	u	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM
Dibromochloromethane	ND	u	mg/L	0.001		EPA 524.2 REV 4.1	11/14/2024 11:15	11/15/2024 10:49	CLM

Notes for work order 4113738

- Samples collected by PACE personnel are done so in accordance with procedures set forth in PACE field services SOPs.
 - Results contained in this report are only representative of the samples received.
 - PACE does not provide interpretation of these results unless otherwise stated.
 - All Waste Water analyses comply with methodology requirements of 40 CFR Part 136.
 - All Drinking Water analyses comply with methodology requirements of 40 CFR Part 141.
 - Unless otherwise noted, all quantitative results for soils are reported on a dry weight basis.
 - The Chain of Custody document is included as part of this report.
 - All Library Search analytes should be regarded as tentative identification based on the presumptive evidence of the mass spectra.
- Concentrations reported are estimated values.

Qualifiers

- M1 Matrix spike recovery was high; the method control sample recovery was acceptable.
- U Target analyte was analyzed for, but was below detection limit (the value associated with the qualifier is the laboratory method detection limit in our LIMS system).
- Y5 MS/MSD RPD exceeded the method control limit.

Standard Qualifiers/Acronyms

- MDL Method Detection Limit
- MRL Minimum Reporting Limit
- ND Not Detected
- LCS Laboratory Control Sample
- MS Matrix Spike
- MSD Matrix Spike Duplicate
- DUP Sample Duplicate
- % Rec Percent Recovery
- RPD Relative Percent Difference
- > Greater than
- < Less than



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Volatile Organic Compounds Madisonville - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

Batch BDK1449 - VOC - Prep

Blank (BDK1449-BLK1)

Prepared: 11/14/2024 11:15, Analyzed: 11/15/2024 7:38

Total Trihalomethanes	ND	0.001	mg/L							U
Total Trihalomethanes	ND	0.001	mg/L							U
Bromodichloromethane	ND	0.001	mg/L							U
Bromodichloromethane	ND	0.001	mg/L							U
Bromoform	ND	0.001	mg/L							U
Bromoform	ND	0.001	mg/L							U
Chloroform	ND	0.001	mg/L							U
Chloroform	ND	0.001	mg/L							U
Dibromochloromethane	ND	0.001	mg/L							U
Dibromochloromethane	ND	0.001	mg/L							U

Surrogate: Bromofluorobenzene	0.0251		mg/L	0.0250		101	70-130
Surrogate: Bromofluorobenzene	0.0251		mg/L	0.0250		101	70-130
Surrogate: Toluene-d8	0.0254		mg/L	0.0250		102	70-130
Surrogate: Toluene-d8	0.0254		mg/L	0.0250		102	70-130
Surrogate: 1,2-Dichlorobenzene-d4	0.0254		mg/L	0.0250		102	70-130
Surrogate: 1,2-Dichlorobenzene-d4	0.0254		mg/L	0.0250		102	70-130

LCS (BDK1449-BS1)

Prepared: 11/14/2024 11:15, Analyzed: 11/15/2024 7:06

Bromodichloromethane	0.025	0.001	mg/L	0.0250		100	70-130
Bromodichloromethane	0.025	0.001	mg/L	0.0250		100	70-130
Bromoform	0.025	0.001	mg/L	0.0250		98.1	70-130
Bromoform	0.025	0.001	mg/L	0.0250		98.1	70-130
Chloroform	0.024	0.001	mg/L	0.0250		97.7	70-130
Chloroform	0.024	0.001	mg/L	0.0250		97.7	70-130
Dibromochloromethane	0.024	0.001	mg/L	0.0250		96.0	70-130
Dibromochloromethane	0.024	0.001	mg/L	0.0250		96.0	70-130

Surrogate: Bromofluorobenzene	0.0255		mg/L	0.0250		102	70-130
Surrogate: Bromofluorobenzene	0.0255		mg/L	0.0250		102	70-130
Surrogate: Toluene-d8	0.0256		mg/L	0.0250		102	70-130
Surrogate: Toluene-d8	0.0256		mg/L	0.0250		102	70-130
Surrogate: 1,2-Dichlorobenzene-d4	0.0250		mg/L	0.0250		99.8	70-130
Surrogate: 1,2-Dichlorobenzene-d4	0.0250		mg/L	0.0250		99.8	70-130



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Volatile Organic Compounds Madisonville - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BDK1449 - VOC - Prep										
Matrix Spike (BDK1449-MS1)		Source: 4113747-01								
Prepared: 11/14/2024 11:15, Analyzed: 11/15/2024 18:18										
Bromodichloromethane	0.032	0.001	mg/L	0.0250	0.006	106	65-135			
Bromodichloromethane	0.032	0.001	mg/L	0.0250	0.006	106	65-135			
Bromoform	0.025	0.001	mg/L	0.0250	ND	98.8	65-135			
Bromoform	0.025	0.001	mg/L	0.0250	ND	98.8	65-135			
Chloroform	0.060	0.001	mg/L	0.0250	0.033	105	65-135			
Chloroform	0.060	0.001	mg/L	0.0250	0.033	105	65-135			
Dibromochloromethane	0.026	0.001	mg/L	0.0250	ND	102	65-135			
Dibromochloromethane	0.026	0.001	mg/L	0.0250	0.0006	99.8	65-135			
Surrogate: Bromofluorobenzene	0.0257		mg/L	0.0250		103	65-135			
Surrogate: Bromofluorobenzene	0.0257		mg/L	0.0250		103	65-135			
Surrogate: Toluene-d8	0.0255		mg/L	0.0250		102	65-135			
Surrogate: Toluene-d8	0.0255		mg/L	0.0250		102	65-135			
Surrogate: 1,2-Dichlorobenzene-d4	0.0254		mg/L	0.0250		102	70-130			
Surrogate: 1,2-Dichlorobenzene-d4	0.0254		mg/L	0.0250		102	70-130			
Matrix Spike Dup (BDK1449-MSD1)		Source: 4113747-01								
Prepared: 11/14/2024 11:15, Analyzed: 11/15/2024 18:50										
Bromodichloromethane	0.033	0.001	mg/L	0.0250	0.006	109	65-135	2.48	30	
Bromodichloromethane	0.033	0.001	mg/L	0.0250	0.006	109	65-135	2.48	30	
Bromoform	0.024	0.001	mg/L	0.0250	ND	97.8	65-135	1.02	30	
Bromoform	0.024	0.001	mg/L	0.0250	ND	97.8	65-135	1.02	30	
Chloroform	0.061	0.001	mg/L	0.0250	0.033	108	65-135	1.53	30	
Chloroform	0.061	0.001	mg/L	0.0250	0.033	108	65-135	1.53	30	
Dibromochloromethane	0.026	0.001	mg/L	0.0250	ND	104	65-135	1.40	30	
Dibromochloromethane	0.026	0.001	mg/L	0.0250	0.0006	101	65-135	1.40	30	
Surrogate: Bromofluorobenzene	0.0259		mg/L	0.0250		104	65-135			
Surrogate: Bromofluorobenzene	0.0259		mg/L	0.0250		104	65-135			
Surrogate: Toluene-d8	0.0257		mg/L	0.0250		103	65-135			
Surrogate: Toluene-d8	0.0257		mg/L	0.0250		103	65-135			
Surrogate: 1,2-Dichlorobenzene-d4	0.0251		mg/L	0.0250		100	70-130			
Surrogate: 1,2-Dichlorobenzene-d4	0.0251		mg/L	0.0250		100	70-130			



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Gas Chromatography Madisonville - Quality Control


Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC Limits	RPD	RPD Limit	Notes
Batch BDK1272 - 552.3 Extraction HAA									
Blank (BDK1272-BLK1)									
Prepared: 11/14/2024 8:45, Analyzed: 11/14/2024 18:26									
Bromoacetic Acid	ND	0.001	mg/L						U
Dibromoacetic Acid	ND	0.001	mg/L						U
Dichloroacetic Acid	ND	0.001	mg/L						U
Monochloroacetic Acid	ND	0.001	mg/L						U
Trichloroacetic Acid	ND	0.001	mg/L						U
Total HAA5	ND	0.001	mg/L						U
Surrogate: 2,3-Dibromopropionic acid	0.00973		mg/L	0.0100		97.3	70-130		
LCS (BDK1272-BS1)									
Prepared: 11/14/2024 8:45, Analyzed: 11/14/2024 19:02									
Bromoacetic Acid	0.023	0.001	mg/L	0.0250		92.2	70-130		
Dibromoacetic Acid	0.025	0.001	mg/L	0.0250		98.1	70-130		
Dichloroacetic Acid	0.023	0.001	mg/L	0.0250		92.0	70-130		
Monochloroacetic Acid	0.023	0.001	mg/L	0.0250		93.8	70-130		
Trichloroacetic Acid	0.024	0.001	mg/L	0.0250		97.6	70-130		
Total HAA5	0.118	0.001	mg/L	0.125		94.7	70-130		
Surrogate: 2,3-Dibromopropionic acid	0.0100		mg/L	0.0100		100	70-130		
Matrix Spike (BDK1272-MS1) Source: 4113713-01									
Prepared: 11/14/2024 8:45, Analyzed: 11/15/2024 1:53									
Bromoacetic Acid	0.064	0.001	mg/L	0.0250	ND	255	70-130		M1, Y5
Dibromoacetic Acid	0.024	0.001	mg/L	0.0250	ND	96.6	70-130		
Dichloroacetic Acid	0.059	0.001	mg/L	0.0250	0.035	98.9	70-130		
Monochloroacetic Acid	0.029	0.001	mg/L	0.0250	0.001	113	70-130		
Trichloroacetic Acid	0.079	0.001	mg/L	0.0250	0.053	106	70-130		
Total HAA5	0.256	0.001	mg/L	0.125	0.089	134	70-130		M1
Surrogate: 2,3-Dibromopropionic acid	0.00995		mg/L	0.0100		99.5	70-130		
Matrix Spike (BDK1272-MS2) Source: 4113714-01									
Prepared: 11/14/2024 8:45, Analyzed: 11/15/2024 2:29									
Bromoacetic Acid	0.032	0.001	mg/L	0.0250	ND	126	70-130		
Dibromoacetic Acid	0.025	0.001	mg/L	0.0250	ND	98.6	70-130		
Dichloroacetic Acid	0.042	0.001	mg/L	0.0250	0.017	97.5	70-130		
Monochloroacetic Acid	0.030	0.001	mg/L	0.0250	ND	122	70-130		
Trichloroacetic Acid	0.045	0.001	mg/L	0.0250	0.021	98.4	70-130		
Total HAA5	0.174	0.001	mg/L	0.125	0.038	108	70-130		
Surrogate: 2,3-Dibromopropionic acid	0.0103		mg/L	0.0100		103	70-130		



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Gas Chromatography Madisonville - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BDK1272 - 552.3 Extraction HAA										
Matrix Spike Dup (BDK1272-MSD1)		Source: 4113713-01								
Prepared: 11/14/2024 8:45, Analyzed: 11/15/2024 2:11										
Bromoacetic Acid	0.023	0.001	mg/L	0.0250	ND	93.7	70-130	92.5	30	Y5
Dibromoacetic Acid	0.026	0.001	mg/L	0.0250	ND	104	70-130	7.69	30	
Dichloroacetic Acid	0.061	0.001	mg/L	0.0250	0.035	106	70-130	2.91	30	
Monochloroacetic Acid	0.030	0.001	mg/L	0.0250	0.001	117	70-130	3.14	30	
Trichloroacetic Acid	0.082	0.001	mg/L	0.0250	0.053	118	70-130	3.91	30	
Total HAA5	0.223	0.001	mg/L	0.125	0.089	108	70-130	13.6	30	
Surrogate: 2,3-Dibromopropionic acid	0.0107		mg/L	0.0100		107	70-130			
Matrix Spike Dup (BDK1272-MSD2)		Source: 4113714-01								
Prepared: 11/14/2024 8:45, Analyzed: 11/15/2024 2:47										
Bromoacetic Acid	0.033	0.001	mg/L	0.0250	ND	131	70-130	4.07	30	M1
Dibromoacetic Acid	0.025	0.001	mg/L	0.0250	ND	98.5	70-130	0.0406	30	
Dichloroacetic Acid	0.042	0.001	mg/L	0.0250	0.017	99.8	70-130	1.40	30	
Monochloroacetic Acid	0.032	0.001	mg/L	0.0250	ND	127	70-130	4.46	30	
Trichloroacetic Acid	0.045	0.001	mg/L	0.0250	0.021	99.1	70-130	0.398	30	
Total HAA5	0.177	0.001	mg/L	0.125	0.038	111	70-130	1.97	30	
Surrogate: 2,3-Dibromopropionic acid	0.0106		mg/L	0.0100		106	70-130			



Analyte	Certifications
---------	----------------

Total Trihalomethanes	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Total Trihalomethanes	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Bromodichloromethane	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Bromodichloromethane	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Bromoform	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Bromoform	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Chloroform	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Chloroform	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Dibromochloromethane	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)
Dibromochloromethane	KY Drinking Water Mdv (00030) IN Drinking Water Mdv (C-KY-02) VA NELAC MDV (460210) WV Drinking Water Mdv (9959 M) TN Drinking Water (02819) ADEM Drinking Water Mdv (41880)

[illegible]



Pace Analytical Services, LLC
P.O. Box 907
Madisonville, KY 42431
270.821.7375
www.pacelabs.com

Sample Acceptance Checklist for Work Order 4113738	
Shipped By: UPS	Temperature: 2.80° Celcius
Condition	
Check if Custody Seals are Present/Intact	☐
Check if Custody Signatures are Present	☒
Check if Collector Signature Present	☒
Check if bottles are intact	☒
Check if bottles are correct	☒
Check if bottles have sufficient volume	☒
Check if samples received on ice	☒
Check if VOA headspace is acceptable	☒
Check if samples received in holding time.	☒
Check if samples are preserved properly	☒

Internal Transfer Chain of Custody

4113738

Pace

☐ Rush Multiplier ☒ X
☐ Samples Pre-Logged into eCOC

State Of Origin: WV

Cert. Needed: ☒ Yes ☐ No

Workorder: 30732801 Workorder Name: WV3301706

Owner Received Date: 11/8/2024 Results Requested By: 11/25/2024

Subcontract To

Pace Analytical Madisonville
825 Industrial Rd
Madisonville, KY 42431
Phone (270)824-2211

Beth Johnson
Pace Beaver West Virginia
225 Industrial Park RD
Beaver, WV 25813
Phone (800)999-0105

Item	Sample ID	Sample Type	Collect Date/Time	Lab ID	Matrix	Preserved Containers		Trip Blank	WV DW HAAS	WV DW TTHM	LAB USE ONLY			
						Meq	Other				S2THM1	S2HAA1	S2THM2	S2HAA2
1	48 UNION CAMP RD	PS	11/8/2024 10:03	30732801001	Drinking	3				X	X			
2	48 UNION CAMP RD	PS	11/8/2024 10:03	30732801002	Drinking	3			X					
3	292 KOONS RUN RD	PS	11/8/2024 10:53	30732801003	Drinking	3			X		X			
4	292 KOONS RUN RD	PS	11/8/2024 10:53	30732801004	Drinking	3			X		X			
5	TRIP BLANK	PS	11/8/2024 00:00	30732801005	Water	1		X					X	

Transfers	Released By	Date/Time	Received By	Date/Time	WV3301706	RT	DS001	EM	Comments
1	f 11-11-24	1431	<i>[Signature]</i>	11-12-24					
2				1050					
3									

Cooler Temperature on Receipt	°C	Custody Seal	Y or N	Received on Ice	Y or N	Samples Intact	Y or N
-------------------------------	----	--------------	--------	-----------------	--------	----------------	--------

***In order to maintain client confidentiality, location/name of the sampling site, sampler's name and signature may not be provided on this COC document.

This chain of custody is considered complete as is since this information is available in the owner laboratory.

Thermometer Serial Number
230753815
240381205
Temperature 58°C



Ship To:
Pace Analytical Madisonville
825 Industrial Rd
Madisonville, KY 42431
Phone (270)824-2211

INTER_LABORATORY WORK ORDER # 30732801

(To be completed by sending lab)

Sending Project No:	30732801
Receiving Project No:	
Check Box for Consolidated Invoice:	☐
Date Prepared:	11/11/24
REQUESTED COMPLETION DATE:	11/25/2024

Sending Region	IR30-Pittsburgh	Sending Project Mgr.	Beth Johnson
Receiving Region	IR44-Madisonville	External Client	GREATER HARRISON COUNTY PSD
State of Sample Origin	WV	QC Deliverable	PACKAGEDD

All questions should be addressed to sending project manager.

Requested Reportable Units _____ Report Wet or Dry Weight? Wet _____ Cert. Needed _____

WORK REQUESTED						
Method Description	Container Type	Quantity of containers	Preservative	Quantity of Samples	Acode	Acode Desc
WV DW HAA5	DG74		Other	2	SI-30MSSV	SUB PASI MSS
Trip Blank	VG9C		MeCl	1	SI-34MSV	SUB PASI MSV
WV DW TTHM	VG9C		MeCl	2	SI-34MSV	SUB PASI MSV

Special Requirements: Report F, QC Lmts, MDLs, Reg Lmts (F), West Virginia CMDP (1667)

FOR ANALYTICAL WORK COMPLETED THIS SECTION ALSO

Return Samples to Sending Region: ☐ Yes ☒ No

DISPOSITION of FORM

Original sent to the receiving lab - Copy kept at the sending lab.

When work completed: Original sent to the ABM at the receiving laboratory. Copies are made to corporate as needed.

CHAIN-OF-CUSTODY Analytical Request Document

Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Chain Terms and Conditions found at <https://www.greaterharrison.com/chain-of-custody-terms.pdf>
Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

Company: Greater Harrison Co. PSD
Address: 151 Peninsula Park Ave
PO BOX 190 West Milford WV 26451
Report To: Julia Childers jchilders@ghpsd.com
Copy To: Brenda Louk
brenda.ghpsd@gmail.com
Customer Project Name/Number:

Billing Information:
151 Peninsula Park Ave
West Milford WV 26451
Email To: jchilders@ghpsd.com
Site Collection Info/Address:
State: Country/City: Time Zone Collected:
Site/Facility ID #: Compliance Monitoring?
Purchase Order #: DW PWS ID #3301706
Quote #: DW Location Code:
Turnaround Date Required: November 12, 2024
Immediately Packed on ice:
Push: (Expedite Charges Apply)
[] Same Day [] Next Day
[] 2 Day [] 3 Day
[] 4 Day [] 5 Day
Analysis:

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Wastewater (WW), Product (P), Soil/Solid (SL), Oil (OL), Wipe (WP), Air (AB), Tissue (TS), Biossary (B), Vapor (V), Other (OT)

Customer Sample ID	Matrix *	Comp / Grab	Date	Time	Composite End	Res	# of Cans	Container Type: Plastic (P) or Glass (G)
48 Union Camp Rd	DW	Grab	11/8/2024	10:34	11/8/2024	1	1	G
292 Koons Run Rd	DW	Grab	11/8/2024	05:34	11/8/2024	1	1	G
TRIP BLANK								

Customer Remarks / Special Conditions / Possible Hazards:
Type of Ice Used: Wet Dry None
Pending Material Used:

Relinquished by/Company: (Signature) Julia Childers
Date/Time: 11-8-24 12:24 PM
Relinquished by/Company: (Signature) BMM / PACE
Date/Time: 11/8/24 14:00
Relinquished by/Company: (Signature)
Date/Time: 11/8/24 16:00
Received by/Company: (Signature) BMM / PACE
Date/Time: 11/8/24 13:22
Received by/Company: (Signature)
Date/Time: 11/8/24 14:00
Received by/Company: (Signature)
Date/Time: 11/8/24 16:00

LAB USE ONLY- Affix Workday/Logix Label Here or List Pesa Workorder Number or APRIL Line-In #107-1247
W0#: 30732801
ALL BOI
Container Pcs:
Preservative Types: (S) nitric acid, (M) methanol, (T) sodium thiosulfate, (B) sodium borohydride, (P) TSP, (U) Unpreserved, (O) Other
30732801

Lab Profile/Line:	Lab Sample Receipt Checklist:
	Custody Seal Present/Intact Y N NA
	Custody Signatures Present Y N NA
	Collector Signature Present Y N NA
	Bottles Intact Y N NA
	Correct Bottles Y N NA
	Surfactant Volume Y N NA
	Samples Received on Ice Y N NA
	Headspace Acceptable Y N NA
	USDA Regulated Soils Y N NA
	Samples in Holding Time Y N NA
	Residual Chlorine Present Y N NA
	CI Strips: Y N NA
	Sample pH Acceptable Y N NA
	pH Strips: Y N NA
	Sulfide Present Y N NA
	Lead Acetate Strips: Y N NA
	LAB USE ONLY: Lab Sample # / Comments:

LAB Sample Temperature Info:
Temp Blank Received: Y N NA
Therm ID: Y N NA
Cooler 1 Temp Upon Receipt: 7.0
Cooler 1 Therm Corr. Factor: 0.0
Cooler 1 Corrected Temp: 7.0
Comments: B R-COAT, 2C 11/8/24
Trip Blank Received: Y N NA
HCL MeOH TSP Other
Non Conformance(s):
YES / NO
Page: 14 of 14

MSDS SHEETS

CHEMICAL ADDITIVES

Section 1. Identification

Product name : CRW132 CORROSION INHIBITOR
Product code : CRW132

Relevant identified uses of the substance or mixture and uses advised against

Identified uses : Corrosion Inhibitor.

Print date : 1/16/2020

Validation date : 1/16/2020

Version : 4.01

Supplier's details : Baker Petrolite LLC
12645 W. Airport Blvd.
Sugar Land, TX 77478
For Product Information/SDSs Call: 800-231-3606
(8:00 a.m. - 5:00 p.m. CST, Monday - Friday) 281-276-5400

Emergency telephone number (with hours of operation) : CHEMTREC: 800-424-9300 (U.S. 24 hour)
Baker Petrolite: 800-231-3606
(001)281-276-5400
CHEMTREC Int'l 01-703-527-3887 (International 24 hour)

Section 2. Hazards identification

OSHA/HCS status : This material is considered hazardous by the OSHA Hazard Communication Standard (29 CFR 1910.1200).

Classification of the substance or mixture : FLAMMABLE LIQUIDS - Category 3
ACUTE TOXICITY (oral) - Category 4
ACUTE TOXICITY (dermal) - Category 4
ACUTE TOXICITY (Inhalation) - Category 4
SKIN IRRITATION - Category 2
SERIOUS EYE DAMAGE - Category 1
SPECIFIC TARGET ORGAN TOXICITY (SINGLE EXPOSURE) (optic nerve) - Category 1
AQUATIC HAZARD (ACUTE) - Category 2

GHS label elements

Hazard pictograms :



Signal word : Danger

Hazard statements : Flammable liquid and vapor.
Harmful if swallowed, in contact with skin or if inhaled.
Causes serious eye damage.
Causes skin irritation.
Causes damage to organs. (optic nerve)
Toxic to aquatic life.

Precautionary statements

Section 2. Hazards identification

- Prevention** : Wear protective gloves: > 8 hours (breakthrough time): Nitrile or Neoprene gloves. 4H gloves.. Wear eye or face protection. Wear protective clothing. Keep away from heat, hot surfaces, sparks, open flames and other ignition sources. No smoking. Use explosion-proof electrical, ventilating, lighting and all material-handling equipment. Use only non-sparking tools. Take precautionary measures against static discharge. Keep container tightly closed. Use only outdoors or in a well-ventilated area. Avoid release to the environment. Do not breathe vapor. Do not eat, drink or smoke when using this product. Wash hands thoroughly after handling.
- Response** : IF exposed: Call a POISON CENTER or physician. IF INHALED: Remove person to fresh air and keep comfortable for breathing. Call a POISON CENTER or physician if you feel unwell. IF SWALLOWED: Call a POISON CENTER or physician if you feel unwell. Rinse mouth. IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water or shower. IF ON SKIN: Wash with plenty of soap and water. Call a POISON CENTER or physician if you feel unwell. Take off contaminated clothing and wash it before reuse. If skin irritation occurs: Get medical attention. IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue rinsing. Immediately call a POISON CENTER or physician.
- Storage** : Store locked up. Store in a well-ventilated place. Keep cool.
- Disposal** : Dispose of contents and container in accordance with all local, regional, national and international regulations.
- Supplemental label elements** : Avoid contact with skin and clothing. Wash thoroughly after handling.
- Hazards not otherwise classified** : Prolonged or repeated contact may dry skin and cause irritation.

Section 3. Composition/information on ingredients

Substance/mixture : Mixture

Ingredient name	%	CAS number
Methanol	20 - 30	67-56-1
Quaternary ammonium compounds	5 - 10	Trade secret.
Alkylpyridine salts	5 - 10	Trade secret.
Ammonium bisulfite	1 - 5	10192-30-0

Section 4. First aid measures

Description of necessary first aid measures

- Eye contact** : Get medical attention immediately. Call a poison center or physician. Immediately flush the eye(s) continuously with lukewarm, gently flowing water for at least 20-60 minutes while holding the eyelid(s) open. Check for and remove any contact lenses. Chemical burns must be treated promptly by a physician.
- Inhalation** : Remove victim to fresh air and keep at rest in a position comfortable for breathing. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway. In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
- Skin contact** : Get medical attention immediately. Call a poison center or physician. Wash affected area with soap and mild detergent for at least 20 - 60 minutes. Wash skin thoroughly with soap and water or use recognized skin cleanser. Remove contaminated clothing and shoes. Wash contaminated clothing thoroughly with water before removing it, or wear gloves. Chemical burns must be treated promptly by a physician. Wash clothing before reuse. Clean shoes thoroughly before reuse.

Section 4. First aid measures

Ingestion : Wash out mouth with water. If material has been swallowed and the exposed person is conscious, give small quantities of water to drink. Do not induce vomiting unless directed to do so by medical personnel. If vomiting occurs, the head should be kept low so that vomit does not enter the lungs. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and get medical attention immediately. Maintain an open airway.

Most important symptoms/effects, acute and delayed

Potential acute health effects

Eye contact : Causes serious eye damage.
Inhalation : Harmful if inhaled.
Skin contact : Harmful in contact with skin. Causes skin irritation. Defatting to the skin.
Ingestion : Harmful if swallowed.

Over-exposure signs/symptoms

Eye contact : pain, watering, redness
Inhalation : No specific data.
Skin contact : pain or irritation, redness, dryness, cracking, blistering may occur
Ingestion : stomach pains

Indication of immediate medical attention and special treatment needed, if necessary

Notes to physician : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.
Specific treatments : No specific treatment.
Protection of first-aiders : No action shall be taken involving any personal risk or without suitable training. If it is suspected that fumes are still present, the rescuer should wear an appropriate mask or self-contained breathing apparatus. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

See toxicological information (Section 11)

Section 5. Fire-fighting measures

Extinguishing media

Suitable extinguishing media : Use dry chemical, CO₂, alcohol-resistant foam or water spray (fog).
Unsuitable extinguishing media : Do not use water jet.

Specific hazards arising from the chemical : Flammable liquid and vapor. Runoff to sewer may create fire or explosion hazard. In a fire or if heated, a pressure increase will occur and the container may burst, with the risk of a subsequent explosion. The vapor/gas is heavier than air and will spread along the ground. Vapors may accumulate in low or confined areas or travel a considerable distance to a source of ignition and flash back. This material is toxic to aquatic life. Fire water contaminated with this material must be contained and prevented from being discharged to any waterway, sewer or drain.

Hazardous thermal decomposition products : carbon dioxide, carbon monoxide, nitrogen oxides, sulfur oxides, halogenated compounds

Section 5. Fire-fighting measures

- Special protective actions for fire-fighters** : Promptly isolate the scene by removing all persons from the vicinity of the incident if there is a fire. No action shall be taken involving any personal risk or without suitable training. Move containers from fire area if this can be done without risk. Use water spray to keep fire-exposed containers cool.
- Special protective equipment for fire-fighters** : Fire-fighters should wear appropriate protective equipment and self-contained breathing apparatus (SCBA) with a full face-piece operated in positive pressure mode.

Section 6. Accidental release measures

Personal precautions, protective equipment and emergency procedures

- For non-emergency personnel** : No action shall be taken involving any personal risk or without suitable training. Evacuate surrounding areas. Keep unnecessary and unprotected personnel from entering. Do not touch or walk through spilled material. Shut off all ignition sources. No flares, smoking or flames in hazard area. Do not breathe vapor or mist. Provide adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Put on appropriate personal protective equipment.
- For emergency responders** : If specialized clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".
- Environmental precautions** : Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers. Inform the relevant authorities if the product has caused environmental pollution (sewers, waterways, soil or air). Water polluting material. May be harmful to the environment if released in large quantities.

Methods and materials for containment and cleaning up

- Small spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.
- Large spill** : Stop leak if without risk. Move containers from spill area. Use spark-proof tools and explosion-proof equipment. Approach release from upwind. Prevent entry into sewers, water courses, basements or confined areas. Wash spillages into an effluent treatment plant or proceed as follows. Contain and collect spillage with non-combustible, absorbent material e.g. sand, earth, vermiculite or diatomaceous earth and place in container for disposal according to local regulations (see Section 13). Dispose of via a licensed waste disposal contractor. Contaminated absorbent material may pose the same hazard as the spilled product. Note: see Section 1 for emergency contact information and Section 13 for waste disposal.

If RQ (Reportable Quantity) is exceeded, report to National Spill Response Office at 1-800-424-8802.

Section 7. Handling and storage

Precautions for safe handling

- Protective measures** : Put on appropriate personal protective equipment (see Section 8). Do not get in eyes or on skin or clothing. Do not breathe vapor or mist. Do not ingest. Avoid release to the environment. Use only with adequate ventilation. Wear appropriate respirator when ventilation is inadequate. Do not enter storage areas and confined spaces unless adequately ventilated. Keep in the original container or an approved alternative made from a compatible material, kept tightly closed when not in use. Store and use away from heat, sparks, open flame or any other ignition source. Use explosion-proof electrical (ventilating, lighting and material handling) equipment. Use only non-sparking tools. Take precautionary measures against electrostatic discharges. Empty containers retain product residue and can be hazardous. Do not reuse container.

Section 7. Handling and storage

Advice on general occupational hygiene : Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed. Workers should wash hands and face before eating, drinking and smoking. Remove contaminated clothing and protective equipment before entering eating areas. See also Section 8 for additional information on hygiene measures.

Conditions for safe storage, including any incompatibilities : Store in accordance with local regulations. Store in a segregated and approved area. Store in original container protected from direct sunlight in a dry, cool and well-ventilated area, away from incompatible materials (see Section 10) and food and drink. Store locked up. Eliminate all ignition sources. Separate from oxidizing materials. Keep container tightly closed and sealed until ready for use. Containers that have been opened must be carefully resealed and kept upright to prevent leakage. Do not store in unlabeled containers. Use appropriate containment to avoid environmental contamination. See Section 10 for incompatible materials before handling or use.

Section 8. Exposure controls/personal protection

Control parameters

Occupational exposure limits

Ingredient name	Exposure limits
Methanol	ACGIH TLV (United States, 3/2018). Absorbed through skin. STEL: 328 mg/m³, 0 times per shift, 15 minutes. STEL: 250 ppm, 0 times per shift, 15 minutes. TWA: 262 mg/m³, 0 times per shift, 8 hours. TWA: 200 ppm, 0 times per shift, 8 hours. NIOSH REL (United States, 10/2016). Absorbed through skin. STEL: 325 mg/m³, 0 times per shift, 15 minutes. STEL: 250 ppm, 0 times per shift, 15 minutes. TWA: 260 mg/m³, 0 times per shift, 10 hours. TWA: 200 ppm, 0 times per shift, 10 hours. OSHA PEL (United States, 5/2018). TWA: 260 mg/m³, 0 times per shift, 8 hours. TWA: 200 ppm, 0 times per shift, 8 hours. OSHA PEL 1989 (United States, 3/1989). Absorbed through skin. STEL: 325 mg/m³, 0 times per shift, 15 minutes. STEL: 250 ppm, 0 times per shift, 15 minutes. TWA: 260 mg/m³, 0 times per shift, 8 hours. TWA: 200 ppm, 0 times per shift, 8 hours.
Quaternary ammonium compounds	None.
Alkylpyridine salts	None.
Ammonium bisulfite	None.

Consult local authorities for acceptable exposure limits.

If OSHA permissible exposure levels are shown above they are the OSHA 1989 levels or are from subsequent OSHA regulatory actions. Although the 1989 levels have been vacated the 11th Circuit Court of Appeals, Baker Hughes recommends that these lower exposure levels be observed as reasonable worker protection.

Appropriate engineering controls : Use only with adequate ventilation. Use process enclosures, local exhaust ventilation or other engineering controls to keep worker exposure to airborne contaminants below any recommended or statutory limits. The engineering controls also need to keep gas, vapor or dust concentrations below any lower explosive limits. Use explosion-proof ventilation equipment.

Section 8. Exposure controls/personal protection

Individual protection measures

- | | |
|-------------------------------|---|
| Hygiene measures | : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location. |
| Eye/face protection | : Wear chemical safety goggles. When transferring material wear face-shield in addition to chemical safety goggles. If inhalation hazards exist, a full-face respirator may be required instead. |
| Hand protection | : Chemical-resistant gloves: Nitrile or Neoprene gloves. 4H gloves. |
| Skin protection | : Wear long sleeves and chemical resistant apron to prevent repeated or prolonged skin contact. |
| Respiratory protection | : If a risk assessment indicates it is necessary, use a properly fitted supplied air respirator complying with an approved standard. Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator. |

Section 9. Physical and chemical properties

Appearance

- | | |
|---|---|
| Physical state | : Liquid. |
| Color | : Amber. [Dark] |
| Odor | : Pungent. Amine-like. |
| Odor threshold | : Not available. |
| pH | : 4 to 5 |
| | : Neat - without dilution. |
| Melting/freezing point | : Not available. |
| Boiling point | : Not available. |
| Initial Boiling Point | : Not available. |
| Flash point | : Closed cup: 31.1°C (88°F) [PMCC] |
| Burning time | : Not applicable. |
| Burning rate | : Not applicable. |
| Evaporation rate | : Not available. |
| Flammability (solid, gas) | : Highly flammable in the presence of the following materials or conditions: open flames, sparks and static discharge and heat. |
| Lower and upper explosive (flammable) limits | : Not available. |
| Vapor pressure | : 45.5 kPa (341.3 mm Hg, 6.6 psig) @ 54.4°C, 130 F (Reid) |
| Vapor density | : >1 [Air = 1] |
| Relative density | : 0.97 (15.6°C) |
| Density | : 8.08 (lbs/gal) |
| Solubility in water | : Soluble |
| Partition coefficient: n-octanol/water | : Not available. |
| Auto-ignition temperature | : Not available. |
| Decomposition temperature | : Not available. |
| Viscosity | : Dynamic (15.6°C): 8 cP |
| VOC | : Not available. |
| Pour Point | : -40°C (-40°F) |

Section 10. Stability and reactivity

- Reactivity** : No specific test data related to reactivity available for this product or its ingredients.
- Chemical stability** : The product is stable.
- Possibility of hazardous reactions** : Under normal conditions of storage and use, hazardous reactions will not occur.
- Conditions to avoid** : Avoid all possible sources of ignition (spark or flame). Do not pressurize, cut, weld, braze, solder, drill, grind or expose containers to heat or sources of ignition. Do not allow vapor to accumulate in low or confined areas.
- Incompatible materials** : Reactive or incompatible with the following materials: oxidizing materials and reducing materials.
Methanol is incompatible and may react with acetyl bromide, alkyl aluminum solutions, beryllium hydride, boron trichloride, nitric acid, cyanuric chloride, dichloromethane, diethylzinc, metals (granulated forms of aluminum and magnesium – including aluminum and zinc salts), phosphorus III oxide, and potassium tert-butoxide.
- Hazardous decomposition products** : Under normal conditions of storage and use, hazardous decomposition products should not be produced.

Section 11. Toxicological information

Information on toxicological effects

Acute toxicity

Product/Ingredient name	Result	Species	Dose	Exposure
Methanol	LC50 Inhalation Gas.	Rat	145000 ppm	1 hours
	LC50 Inhalation Gas.	Rat	64000 ppm	4 hours
	LD50 Dermal	Rabbit	15800 mg/kg	-
	LD50 Oral	Human	500 mg/kg	-
	LD50 Oral	Rat	5600 mg/kg	-

Irritation/Corrosion

No applicable toxicity data

Sensitization

No applicable toxicity data

Mutagenicity

No applicable toxicity data

Carcinogenicity

No applicable toxicity data

Reproductive toxicity

No applicable toxicity data

Teratogenicity

No applicable toxicity data

Specific target organ toxicity (single exposure)

Name	Category	Route of exposure	Target organs
Methanol	Category 1	Oral	optic nerve

Section 11. Toxicological information

Specific target organ toxicity (repeated exposure)

Not applicable.

Aspiration hazard

Not available.

Information on the likely routes of exposure : Routes of entry anticipated: Dermal, Inhalation.

Potential acute health effects

Eye contact : Causes serious eye damage.
Inhalation : Harmful if inhaled.
Skin contact : Harmful in contact with skin. Causes skin irritation. Defatting to the skin.
Ingestion : Harmful if swallowed.

Potential chronic health effects

General : Prolonged or repeated contact can defat the skin and lead to irritation, cracking and/or dermatitis.
Carcinogenicity : No known significant effects or critical hazards.
Mutagenicity : No known significant effects or critical hazards.
Teratogenicity : No known significant effects or critical hazards.
Developmental effects : No known significant effects or critical hazards.
Fertility effects : No known significant effects or critical hazards.

Numerical measures of toxicity

Acute toxicity estimates

Route	ATE value
Oral	321.6 mg/kg
Dermal	1003.3 mg/kg
Inhalation (vapors)	10.03 mg/l

Section 12. Ecological information

Toxicity

Product/ingredient name	Result	Species	Exposure
CRW132 CORROSION INHIBITOR	Acute EC50 16.912 mg/l Marine water	Algae - Ulva pertusa	96 hours
	Acute EC50 10000000 µg/l Fresh water	Daphnia - Daphnia magna	48 hours
	Acute LC50 2500000 µg/l Marine water	Crustaceans - Crangon crangon	48 hours
	Acute LC50 100 mg/l Fresh water	Fish - Pimephales promelas	96 hours
	Chronic NOEC 9.96 mg/l Marine water	Algae - Ulva pertusa	96 hours
	Acute LC50 2.61 mg/l	Daphnia	48 hours
	Acute LC50 3 ppm	Daphnia	48 hours
	Acute LC50 2.3 mg/l	Fish - Fathead minnow	96 hours
	Acute LC50 2.3 mg/l	Fish - Sheepshead minnow	96 hours

Persistence and degradability

Not available.

Section 12. Ecological information

Other adverse effects : No known significant effects or critical hazards.

Section 13. Disposal considerations

Disposal methods : Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible. This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Vapor from product residues may create a highly flammable or explosive atmosphere inside the container. Do not cut, weld or grind used containers unless they have been cleaned thoroughly internally. Avoid dispersal of spilled material and runoff and contact with soil, waterways, drains and sewers.

Section 14. Transport information

	DOT Classification	TDG Classification	IMDG	IATA
UN number	UN1992	UN1992	UN1992	UN1992
UN proper shipping name	FLAMMABLE LIQUID, TOXIC, N.O.S. (Contains: Methanol)	FLAMMABLE LIQUID, TOXIC, N.O.S. (Contains: Methanol)	FLAMMABLE LIQUID, TOXIC, N.O.S. (Contains: Methanol)	FLAMMABLE LIQUID, TOXIC, N.O.S. (Contains: Methanol)
Transport hazard class(es)	3 (6.1)  	3 (6.1)  	3 (6.1)  	3 (6.1)  
Packing group	III	III	III	III
Environmental hazards	No.	No.	No.	No.

Additional information

DOT Classification : **Reportable quantity** 16722.2 lbs / 7591.9 kg [2067.6 gal / 7826.7 L]. Package sizes shipped in quantities less than the product reportable quantity are not subject to the RQ (reportable quantity) transportation requirements.

TDG Classification : Product classified as per the following sections of the Transportation of Dangerous Goods Regulations: 2.18-2.19 (Class 3), 2.26-2.36 (Class 6).

IMDG : **Emergency schedules** F-E S-D

Special precautions for user : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

Transport in bulk according to Annex II of MARPOL and the IBC Code : Not available.

DOT Reportable Quantity Methanol, 2070 gal of this product.
Ammonium bisulfite, 24752 gal of this product.

Marine pollutant Not available.

Section 14. Transport information

North-America NAERG : 131

Section 15. Regulatory information

U.S. Federal regulations : TSCA 12(b) one-time export: No products were found.
 TSCA 12(b) annual export notification: No products were found.
 United States inventory (TSCA 8b): All components are listed or exempted.
 Clean Water Act (CWA) 307: No products were found.
 Clean Water Act (CWA) 311: ammonium hydrogensulphite

United States - Clean Air Act Section 112(b) Hazardous Air Pollutants (HAPs) :

List name	Status	Ingredient name	Name on list	Conc.
United States - Clean Air Act Section 112(b) Hazardous Air Pollutants (HAPs)	Listed	Methanol	Methanol	20 - 30

SARA 302/304 : No products were found.

SARA 311/312

Classification : Fire hazard
 Immediate (acute) health hazard

SARA 313

	Product name	CAS number	%
Supplier notification	Methanol Ammonium bisulfite	67-56-1 10192-30-0	20 - 30 1 - 5

California Prop. 65

⚠ WARNING: This product can expose you to methanol, which is known to the State of California to cause birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov.

Canada

Canada (CEPA DSL): : All components are listed or exempted.

Section 16. Other information

National Fire Protection Association (U.S.A.)



History

Date of printing : 1/16/2020

☑ Indicates information that has changed from previously issued version.

Notice to reader

NOTE: The information on this SDS is based on data which is considered to be accurate. Baker Hughes, however, makes no guarantees or warranty, either expressed or implied of the accuracy or completeness of this information.

The conditions or methods of handling, storage, use and disposal of the product are beyond our control and may be beyond our knowledge. For this and other reasons, we do not assume responsibility and expressly disclaim liability for loss, damage or expense arising out of or in any way connected with the handling, storage, use or disposal of this product.

This SDS was prepared and is to be used for this product. If the product is used as a component in another product, this SDS information may not be applicable.

Section 11

Groundwater Protection Plan

Section No. 11

Please see APPENDIX H for Ground Water Protection Plan for this facility.

APPENDIX H

GROUNDWATER PROTECTION PLAN

Facility Name: Clover Produced Water DisposalCounty: Roane

Facility Location:

Postal Service Address:	Kaufman Rd, Spencer, WV 25276		
Latitude :	38 Degrees 45' 32"	Longitude:	81 Degrees 15' 45"

Contact Information:

Person:	Brad Morris
Phone Number:	681-229-1558
E-mail Address:	bmorris@topdrilling.com

Date: 12/15/24

1. A list of all operations that may contaminate the groundwater.

Tank failure / leak
 Pipeline failure / leak
 Fluids (bactericide, corrosion inhibitor, etc) transfer
 Stuffing box failure
 well completion / work over activities

2. A description of procedures and facilities used to protect groundwater quality from the list of potential contaminant sources above.

Secondary containment is installed around tanks adequate to hold the volume of the largest tank. Pipelines are routinely monitored and patrolled for leaks. Pipelines are registered with the WV 811 to minimize possibility of being damaged by others. Pressure monitoring - Shut down controls on pump. Work over fluids are properly contained and disposed of. The injection well is monitored for mechanical integrity failures and pressure tested ever five years.

3. List procedures to be used when designing and adding new equipment or operations.

Non corrosive materials are utilized as much as possible. Shut down controls installed on injection pump.

4. Summarize all activities at your facility that are already regulated for groundwater protection.

This facility is currently covered by an existing UIC permit No. 2D0871056. Storage tanks are registered under WV Tank regulations. Any Spills or leaks are reported to WVDEP / EPA.

5. Discuss any existing groundwater quality data for your facility or an adjacent property.

There are no known ground water quality issues in this area. Only two of the residences with in the AOR utilize water wells for domestic use. The analytical results from these two wells are enclosed with this application.

6. Provide a statement that no waste material will be used for deicing or fill material on the property unless allowed by another rule.

No waste material is or will be used for deicing or fill material.

7. Describe the groundwater protection instruction and training to be provided to the employees. Job procedures shall provide direction on how to prevent groundwater contamination.

The operators of this facility are instructed to routinely monitor tank conditions, secondary containment conditions, and patrol injection lines. They are trained yearly regarding ground water protection. Part of this training involves prevention of oil & chemical spills and the prompt clean up / remediation of any spills. Prior to the release of any storm water from secondary containment it is tested t assure that it meets guidelines for discharge.

4708701056

8. Include provisions for inspections of all GPP elements and equipment. Inspections must be made quarterly at a minimum.

Secondary containment, pipelines, and injection equipment are inspected and documented a minimum of every 90 days. The injection well and producing wells are visited several times weekly. The wellheads are inspected for any indication of mechanical integrity. Any issues are addressed when discovered. The majority of the production pipelines and the injection lines are located parallel to roadways which are traveled several times weekly.

Signature: _____

Brad J. [Signature]

Date: 12/15/24

Section 12

Plugging and Abandonment

Section No. 12

This injection well has surface casing set at 466' and cemented to surface. The 4 ½" casing is set at 2272' and cemented to approximately 2025'. See schematic – Fig No. 4. The well will be plugged to the standards set by WVDEP at the time it is plugged. If this well was to be plugged today it would be plugged as follows:

Plug No. 1- 2200'-2100'

Free point, cut, & POH w/ 4 1/2" casing – est 1975'

Plug No. 2 -2025'-1925' (adjusted for casing cut above)

Plug No. 3 -1110'-1010'

Plug No. 4 – 515'-415' (base of surface casing)

Plug No. 5 – 100'-0'

6 % gel between cement plugs.

Section 13

Additional Bonding

Section No. 13

An additional \$5000 bond was posted at the time Delta Helix Energy LLC purchased these assets, and the bond will remain in place.

Section 14

Financial Responsibility

Section No. 14

See APPENDIX I

APPENDIX I

Requirement for Financial Responsibility to Plug/Abandon an Injection Well

In accordance with WV Code 47CSR13.13.7.g, all UIC permits shall require the permittee to maintain financial responsibility and resources to close, plug, and abandon underground injection wells in a manner prescribed by the Chief. The permittee must show evidence of financial responsibility to the Chief by submission of a surety bond, or other adequate assurance, such as a financial statement or other material acceptable to the Chief. This certification must be signed by one of the following:

1. For a corporation: by a principle corporate officer of at least the level of vice-president;
2. For a partnership or sole proprietorship: by a general partner or the proprietor, respectively;
3. For a municipality, State, Federal, or other public agency: by either a principle executive officer or ranking elected official;
4. Or a duly authorized representative in accordance with 47CSR13.13.11.b.
(A person may be duly authorized by one of the primary entities (1-3) listed above by submitting a written authorization to the Chief of the WVDEP Office of Oil and Gas designating an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility. A duly authorized representative may thus be either a named individual or any individual occupying a named position.)

Delta Helix Energy, LLC

(Company Name)

2D0871056-002

(UIC Permit Number)

I certify in accordance with 47CSR13.13.7.g., that the company/permit holder cited above will maintain financial responsibility and resources to close, plug, and abandon underground injection wells(s) in a manner prescribed by the Chief of the Office of Oil and Gas and that documents to support this requirement are on record with the same.

B Douglas Haught

(Print Name)

CEO

(Print Title)

(Signature)

12-16-24

(Date)

Section 15

Site Security Plan

Section No. 15

This injection facility is remotely located and accessed via a roadway shared with a few residences. When unattended a locked gate blocks access to this facility. Please see APPENDIX J

APPENDIX J

Site Security for Commercial Facilities

Provide a detailed description of the method(s) utilized at the facility to restrict or prohibit illegal dumping of unauthorized waste or vandalism at the facility.

1. Complete enclosure of all wells, holding tank/pits and manifold assemblies within a chain link or other suitable fencing; and
2. Require that all gates and other entry points be locked when the facility is unattended; or
3. Providing tamper-proof seals for the master valve on each well (a "lock-out" or chain & padlock system would be more secure; however, these devices could create a potential safety hazard if the well needed to be quickly shut in due to an emergency); and
4. Installing locking caps on all valves and connections on holding tanks, unloading racks, and headers.

This is not a commercial facility

Section 16

Additional Information

Section No. 16

See APPENDIX K

APPENDIX K

**Identify permit or construction approvals received
or applied for under the following programs:**

Permit/approvals	ID Number
Hazardous Waste Management Program under RCRA	
NPDES Program	
Prevention of Significant Deterioration (PSD)	
Nonattainment Program	
Dredge or Fill	
NPDES/NPDES – Stormwater	
WVDEP – Office of Waste Management (OWM) – Solid Waste Facility	
WVDEP – OWM – RCRA (Hazardous Waste TSD or Transporter)	
WVDEP – OWM – UST	
CERCLA – Superfund	
WV Voluntary Remediation – Brownfields	
FIFRA – Federal Insecticide, Fungicide and Rodenticide Act	
Well Head Protection Program (WHPP)	
Underground Injection Control (UIC)	2D0871056-002
Toxic Substances Control Act (TSCA)	
Best Management Plans	
Management of Used Oil	
Other Relevant Permits (Specify):	
WV DEP Tank Registrations	See Appendix B

2D08701056

Delta Helix Energy, LLC

Wells in the Area of Review

4708701056

APPENDIX C
Wells within the Area of Review

	API No.	Well No.	Well Type	Well Status	Northing	Easting	Penetrate Injection Zone	Penetrate Confining Zone	Total Vertical Depth	Surface Elevation
1	4708700955	Wines 7	Gas Prod	Active	4290299.5	476794.4	Y	Y	2278	1095
2	4708700988	W-8	Oil Prod	Active	4289673.2	477190.2	Y	Y	2430	1225
3	4708700994	W-12	Oil Prod	Active	4290143.6	476912.3	Y	Y	2380	1152
4	4708700995	W-13	Oil Prod	Active	4290388.4	477106.1	Y	Y	2313	1096
5	4708701032	W-16	Gas Prod	Active	4289685.6	477409.7	Y	Y	2371	1163
6	4708701053	W-17	Oil Prod	Active	4289888.7	477092.4	Y	Y	2190	971
7	4708701055	W-18	Gas Prod	Active	4289919.8	477488.3	Y	Y	2097	875
8	4708701056	W-19	Injector	Active	4290082.0	477216.0	Y	Y	2277	1061
9	4708701068	W-20	Oil Prod	Active	4290470.8	477304.6	Y	Y	2255	1022
10	4708701079	W-21	Oil Prod	Active	4290255.7	477520.7	Y	Y	2260	1046

☒ Btm Hole Log

Wines 7

[illegible]

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700955	McKown, C. I. & Son, Inc.	2016	0												
4708700955	McKown, C. I. & Son, Inc.	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700955	McKown, C. I. & Son, Inc.	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700955	McKown, C. I. & Son, Inc.	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700955	McKown, C. I. & Son, Inc.	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700955	McKown, C. I. & Son, Inc.	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700955	McKown, C. I. & Son, Inc.	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

4708700955

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700955	Original Loc	Mahonig Ss/Big Dunk	Past WVGES Staff Geologist	245	Reasonable	35	Reasonable	1095	Ground Level
4708700955	Original Loc	Maxton	Well Record	1940	Reasonable	5	Reasonable	1095	Ground Level
4708700955	Original Loc	Little Lime	Past WVGES Staff Geologist	2028	Reasonable	37	Reasonable	1095	Ground Level
4708700955	Original Loc	Pencil Cave	Well Record	2065	Reasonable	10	Reasonable	1095	Ground Level
4708700955	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	2075	Reasonable	110	Reasonable	1095	Ground Level
4708700955	Original Loc	Big Lime	Well Record	2075	Reasonable	110	Reasonable	1095	Ground Level
4708700955	Original Loc	Big Injun (Price&eq)	Past WVGES Staff Geologist	2185	Reasonable	53	Reasonable	1095	Ground Level
4708700955	Original Loc	Squaw	Well Record	2243	Reasonable	7	Reasonable	1095	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 10

4708700955

1-3-66
WB

Wines 7

Quadrangle SpencerPermit No. Renewed RQA 955

WELL RECORD

Oil or Gas Well Comb
(KIND)


Company J & B Oil Company, Inc.
Address 339 $\frac{1}{2}$ Market St., Spencer, W. Va.
Farm C. H. & Cora Wines Acres 90.33
Location (waters) Boggs Fork
Well No. 7 Elev. 1094.84
District Spencer County Roane
The surface of tract is owned in fee by C. H. Wines, et al
Address Spencer, W. Va.
Mineral rights are owned by C. H. Wines, et al
Address Spencer, W. Va.
Drilling commenced June 26, 1964
Drilling completed August 7, 1964
Date Shot From To
With
Open Flow /10ths Water in Inch
/10ths Merc. in Inch
Volume Insufficient to Test Cu. Ft.
Rock Pressure " lbs. " hrs.
Oil Insufficient to Test bbls., 1st 24 hrs.
WELL ACIDIZED No

WELL FRACTURED 41,000 Gal Water-250 gal Dowell X, 125 lbs J100, 35 Gal Deterget
40 Gal Frefloc-1 Gal F33-1 Gal W 9 45,000 Sand

RESULT AFTER TREATMENT

ROCK PRESSURE AFTER TREATMENT 300 Initial in 24 hrs--15 bbls.Fresh Water Feet Salt Water Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Sand			0	10			
Red Rock			10	50			
Sand			50	60			
Red Rock			60	100			
Sand			100	165			
Slate & Shells			165	200			
Red Rock			200	220			
Sand		Hard	220	229			
Red Rock			229	245			
Sand, Dunkard			245	280			
Red Rock			280	295			
Slate & Shells			295	325			
Red Rock			325	390			
Slate & Shells			390	415			
Red Rock			415	434			
Slate & Shells			434	450			
Sand			450	465			
Red Rock			465	480			
Slate & Shells			480	540			
Sand			540	575			
Slate	White		575	620			
Slate	Blue		620	685			
Red Rock			685	705			
Slate & Shells			705	730			
Sand			730	750			
Red Rock			750	780			
Slate & Shells			780	790			
Red Rock			790	1010			
Slate	Blue		1010	1065			
Sand			1065	1159			



(over)

4708700955

Formation	Color	Hard or Soft	Top 10	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate & Shells			1159	11250			
Salt Sand			1250	11390			
Slate			1320	11400			
Sand			1460	1510			
Slate	Black		1510	1545			
Sand			1545	1585			
Slate	Black		1585	1630			
Sand			1620	1660			
Slate	Black		1660	1625			
Salt Sand			1695	1730			
Slate			1730	1740			
Sand Salt			1740	1900			
Slate & Shells			1900	1905			
Little Lime			1905	1925			
Slate	Black		1925	1940			
Maxon Sand			1940	1945			
Slate	Black		1945	1985			
Sand			1985	2028			
Lime			2028	2065			
Pencil Cave			2065	2075			
Big Lime			2075	2185			
Injun Sand			2185	2238			
Slate			2238	2243			
Squaw Sand			2243	2250			
Slate	Black		2250	2255			
Lime			2255	2260			
Slate			2260	2278	Total Depth		
			TO	0			
			0	TO			

Date August, 1964

APPROVED J & B Oil Company, Inc. Allen Board, Owner

By Allen Board (Title)

**"Pipeline"**

Select County: (087) Roane ☐ (Check All)

Enter Permit #: 988

Get Data Reset

☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

Table Description
 County Code Translations
 Permit Numbering Series
 Usage Notes
 Contact Information
 Disclaimer
 WVGES Main
 "Pipeline Plus" New

W-8

WV Geological & Economic Survey:

Well: County = 87 Permit = 988 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 8:11:08 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708700988	Roane	988	Smithfield	Spencer	Spencer	38.755462	-81.262517	477190.2	4289673.2

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST.
4708700988	1/13/1964	Original Loc	Completed	W Kaufman, E Walbrown		W-8			Alfred M Oppenheimer II	Wolf's Head Oil Refining Co., Inc.			
4708700988	10/26/1972	Worked Over	Completed	W Kaufman, K Miller		W-8			Alfred M Oppenheimer II	Pennzoil Company			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G.I
4708700988	1/13/1964	12/17/1963	1225	Ground Level	Cldr-Rsh Rn	Undf PRICE blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil and Gas	Rotary	Fractured	2430			2430	
4708700988	10/26/1972	-/-	1225	Ground Level	Cldr-Rsh Rn	Undf PRICE blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil	unknown	Acid+Frac	2430			0	

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEf	G_AFT	O_BEf	O_AFT	WATER_QNTY
4708700988	10/26/1972	Pay	Oil	Vertical	2276	Big Lime	2282	Big Lime	0	4			
4708700988	1/13/1964	Pay	Oil	Vertical	2362	Big Injun (Price&eq)	2379	Big Injun (Price&eq)	0	38			
4708700988	1/13/1964	Pay	Gas	Vertical	2362	Big Injun (Price&eq)	2379	Big Injun (Price&eq)	0	38			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700988	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Products Company	1989	1,299	134	94	99	106	136	91	119	94	105	127	99	95
4708700988	Pennzoil Products Company	1990	1,398	103	68	114	91	99	117	157	140	139	145	124	101
4708700988	Pennzoil Products Company	1991	1,046	114	76	62	19	101	100	115	85	80	116	85	93
4708700988	Pennzoil Products Company	1992	918	93	46	67	66	81	78	97	87	70	87	74	72
4708700988	Pennzoil Products Company	1993	696	52	69	69	34	66	68	65	49	46	61	56	61
4708700988	Pennzoil Products Company	1994	645	63	66	49	51	62	57	66	49	32	57	44	49
4708700988	Pennzoil Products Company	1995	514	44	61	49	41	46	41	42	36	44	29	40	41
4708700988	Pennzoil Products Company	1996	413	21	1	52	44	36	38	33	33	43	30	41	41
4708700988	Pennzoil Products Company	1997	446	49	37	35	30	32	31	34	36	30	32	44	56
4708700988	Pennzoil Products Company	1998	410	55	44	43	40	44	46	29	24	21	22	20	22
4708700988	Pennzoil Products Company	1999	239	46	48	27	22	15	0	12	12	21	22	14	
4708700988	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708700988	East Resources, Inc.	2001	370	7	0	0	55	64	66	35	11	62	63	7	
4708700988	East Resources, Inc.	2002	590	51	47	49	47	47	50	53	55	57	46	27	61
4708700988	East Resources, Inc.	2003	1,000	33	21	116	295	94	92	82	71	76	86	0	34
4708700988	East Resources, Inc.	2004	936	98	81	56	66	98	122	88	101	113	29	27	57
4708700988	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708700988	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708700988	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708700988	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708700988	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708700988	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708700988	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708700988	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708700988	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708700988	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708700988	HG Energy, LLC	2016	467	39	36	39	39	41	38	40	38	39	39	39	38
4708700988	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708700988	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708700988	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708700988	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708700988	HG Energy, LLC	2021	583	54	41	54	56	57	56	59	0	52	51	48	55
4708700988	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708700988	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28
4708700988	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under CIP															
API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700988	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1983	445	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Products Company	1989	265	25	24	27	21	22	20	23	22	21	23	20	17
4708700988	Pennzoil Products Company	1990	292	23	19	24	30	30	29	30	24	24	22	22	15
4708700988	Pennzoil Products Company	1991	189	14	4	21	19	20	16	14	20	16	18	17	10
4708700988	Pennzoil Products Company	1992	177	16	16	16	15	17	15	13	17	14	15	10	13
4708700988	Pennzoil Products Company	1993	150	14	10	13	15	14	11	10	13	12	12	12	14
4708700988	Pennzoil Products Company	1994	134	10	12	15	13	13	10	7	12	9	11	9	13
4708700988	Pennzoil Products Company	1995	86	10	8	10	9	9	7	9	6	9	9	0	0
4708700988	Pennzoil Products Company	1996	115	14	12	9	9	7	6	9	10	9	9	12	9
4708700988	Pennzoil Products Company	1997	94	8	8	9	8	9	5	7	7	7	9	9	8
4708700988	Pennzoil Products Company	1998	79	9	8	9	9	3	0	0	0	0	0	25	16
4708700988	Pennzoil Products Company	1999	33	14	15	4	0	0	0	0	0	0	0	0	0
4708700988	Pennzoil Products Company	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	East Resources, Inc.	2001	128	0	0	0	0	21	20	23	9	3	20	16	16
4708700988	East Resources, Inc.	2002	179	14	18	15	14	15	17	22	15	16	12	6	15
4708700988	East Resources, Inc.	2003	220	15	7	7	38	33	30	20	15	23	21	0	11
4708700988	East Resources, Inc.	2004	277	15	26	20	20	23	29	21	27	29	19	24	24
4708700988	East Resources, Inc.	2005	311	18	31	37	30	32	30	24	32	33	24	10	10
4708700988	East Resources, Inc.	2006	81	9	5	5	9	8	7	7	0	6	9	8	8
4708700988	East Resources, Inc.	2007	131	8	7	10	11	21	16	12	12	8	10	9	7
4708700988	East Resources, Inc.	2008	86	6	8	9	9	8	8	9	8	4	7	5	5
4708700988	East Resources, Inc.	2010	148	11	15	14	18	0	12	19	13	11	16	10	9
4708700988	East Resources, Inc.	2011	113	7	11	12	8	8	10	8	11	8	9	11	10
4708700988	HG Energy, LLC	2012	151	8	11	14	16	16	7	2	10	4	27	20	16
4708700988	HG Energy, LLC	2013	194	20	24	11	9	15	13	13	22	17	21	16	13
4708700988	HG Energy, LLC	2014	152	13	18	14	16	17	14	13	14	9	8	6	10
4708700988	HG Energy, LLC	2015	142	11	9	14	17	11	13	13	11	8	10	11	14
4708700988	HG Energy, LLC	2016	123	9	12	12	10	11	14	9	15	8	7	6	10
4708700988	HG Energy, LLC	2017	33	7								6	5	9	6
4708700988	HG Energy, LLC	2018	76	8	8	7	4	6	8	6	5	4	7	5	8
4708700988	HG Energy, LLC	2019	88	11	5	7	8	10	6	8	4	5	10	7	7
4708700988	HG Energy, LLC	2020	91	8	8	6	10	8	7	10	7	8	5	5	9
4708700988	HG Energy, LLC	2021	93	8	6	7	8	6	10	7	9	8	7	7	10
4708700988	HG Energy, LLC	2022	89	8	6	10	7	9	7	8	8	8	8	5	5
4708700988	Delta Helix Energy, LLC	2023	8	0	0	0	0	0	0	0	0	0	0	4	4
4708700988	HG Energy, LLC	2023	64	6	6	6	7	9	7	7	5	4	7	0	0

4708700988

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700988	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2016	0												
4708700988	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700988	HG Energy, LLC	2016	0												
4708700988	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700988	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700988	Original Loc	Little Lime	Well Record	2166	Reasonable	49	Reasonable	1225	Ground Level
4708700988	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	2215	Reasonable	147	Reasonable	1225	Ground Level
4708700988	Original Loc	Big Lime	Well Record	2215	Reasonable	133	Reasonable	1225	Ground Level
4708700988	Original Loc	Keener	Well Record	2348	Reasonable	14	Reasonable	1225	Ground Level
4708700988	Original Loc	Big Injun (Price&eq)	Past WVGES Staff Geologist	2362	Reasonable	17	Reasonable	1225	Ground Level
4708700988	Original Loc	Undf PRICE blw INJN	Well Record	2379	Reasonable	0	Reasonable	1225	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well

4708700988



GEORGE A. MITCHELL, JR., GOVERNOR

W-8

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Quadrangle SPENCERPermit No. ROA-988

WELL RECORD

Oil or Gas Well Comb.

Company WOLF'S HEAD OIL REFINING COMPANY, INC.
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres > 800
Location (waters) Millstone Run
Well No. W-8 Elev. 1,224.85
District Smithfield County Roane
The surface of tract is owned in fee by Eugene Walbrown
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer, II,
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced December 17, 1963
Drilling completed January 13, 1964
Date Shot - From - To -
With -
Open Flow /10ths Water in Inch
/10ths Merc. in Inch
Volume Show Oil & Gas (Drilled w/Rotary) Cu. Ft.
Rock Pressure None Taken lbs. hrs.
Oil - bbls., 1st 24 hrs.
WELL ACIDIZED

WELL FRACTURED 1/22/64 Used: 40,000 Gals. Water, 45,000 Lbs. Sand, 40 Gals. Morflo,
30 Gals. Suds, 300 Gals. Acid 15% MCA and 350 Lbs. WAC-8,
RESULT AFTER TREATMENT Gas = 38,000 Cu. Ft.
Oil = 38 bbls.


ROCK PRESSURE AFTER TREATMENT 500 Lbs.Fresh Water - Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Shale			0	850			
Red Rock			850	949			
Shale			949	1400			
Sand			1400	1480			
Shale			1480	1485			
Sand			1485	1525			
Sandy Shale			1525	1540			
Sand			1540	1685			
Shale			1685	1725			
Sand			1725	1765			
Shale			1765	1775			
Sand			1775	1875			
Sand & Lime			1875	1910			
Shale			1910	1925			
Lime-Shale			1925	1975			
Sand			1975	2005			
Sand & Chert			2005	2040			
Lime & Sand			2040	2100			
Sandy Shale			2100	2125			
Shale			2125	2166			
Little Lime			2166	2215			
Big Lime			2215	2348			
Keener Sand			2348	2362			
Big Injun			2362	2379			
Shale			2379	2430	Oil & Gas	2362-2379	Show Only
4 1/2" Casing				2427			
TOTAL DEPTH				2430			

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			Steel Shoe
10			Float Collar
8 5/8"	266'	266'	Guide Shoe
6 3/4"			Size of OD
4 1/2"	2427'	2427'	4 1/2" OD
3			Depth set
2 3/8" Tbg.	2379'	2379'	2379'
Liners Used			Perf. top
			Perf. bottom
			Perf. top
			Perf. bottom

CASING CEMENTED 8 5/8" SIZE 266 No. Ft. 12/20/63 Date
4 1/2" 2427 1/14/64

COAL WAS ENCOUNTERED AT - FEET - INCHES
- FEET - INCHES - FEET - INCHES
- FEET - INCHES - FEET - INCHES



4708700988

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
LOIST	DELI			5430			
5430-5431			5430	5431			
5431-5432			5431	5432	Oil & Gas	5325-5318	2000 out
5432-5433			5325	5318			
5433-5434			5325	5325			
5434-5435			5312	5308			
5435-5436			5312	5312			
5436-5437			5312	5312			
5437-5438			5312	5312			
5438-5439			5312	5312			
5439-5440			5312	5312			
5440-5441			5312	5312			
5441-5442			5312	5312			
5442-5443			5312	5312			
5443-5444			5312	5312			
5444-5445			5312	5312			
5445-5446			5312	5312			
5446-5447			5312	5312			
5447-5448			5312	5312			
5448-5449			5312	5312			
5449-5450			5312	5312			
5450-5451			5312	5312			
5451-5452			5312	5312			
5452-5453			5312	5312			
5453-5454			5312	5312			
5454-5455			5312	5312			
5455-5456			5312	5312			
5456-5457			5312	5312			
5457-5458			5312	5312			
5458-5459			5312	5312			
5459-5460			5312	5312			
5460-5461			5312	5312			
5461-5462			5312	5312			
5462-5463			5312	5312			
5463-5464			5312	5312			
5464-5465			5312	5312			
5465-5466			5312	5312			
5466-5467			5312	5312			
5467-5468			5312	5312			
5468-5469			5312	5312			
5469-5470			5312	5312			
5470-5471			5312	5312			
5471-5472			5312	5312			
5472-5473			5312	5312			
5473-5474			5312	5312			
5474-5475			5312	5312			
5475-5476			5312	5312			
5476-5477			5312	5312			
5477-5478			5312	5312			
5478-5479			5312	5312			
5479-5480			5312	5312			
5480-5481			5312	5312			
5481-5482			5312	5312			
5482-5483			5312	5312			
5483-5484			5312	5312			
5484-5485			5312	5312			
5485-5486			5312	5312			
5486-5487			5312	5312			
5487-5488			5312	5312			
5488-5489			5312	5312			
5489-5490			5312	5312			
5490-5491			5312	5312			
5491-5492			5312	5312			
5492-5493			5312	5312			
5493-5494			5312	5312			
5494-5495			5312	5312			
5495-5496			5312	5312			
5496-5497			5312	5312			
5497-5498			5312	5312			
5498-5499			5312	5312			
5499-5500			5312	5312			
5500-5501			5312	5312			
5501-5502			5312	5312			
5502-5503			5312	5312			
5503-5504			5312	5312			
5504-5505			5312	5312			
5505-5506			5312	5312			
5506-5507			5312	5312			
5507-5508			5312	5312			
5508-5509			5312	5312			
5509-5510			5312	5312			
5510-5511			5312	5312			
5511-5512			5312	5312			
5512-5513			5312	5312			
5513-5514			5312	5312			
5514-5515			5312	5312			
5515-5516			5312	5312			
5516-5517			5312	5312			
5517-5518			5312	5312			
5518-5519			5312	5312			
5519-5520			5312	5312			
5520-5521			5312	5312			
5521-5522			5312	5312			
5522-5523			5312	5312			
5523-5524			5312	5312			
5524-5525			5312	5312			
5525-5526			5312	5312			
5526-5527			5312	5312			
5527-5528			5312	5312			
5528-5529			5312	5312			
5529-5530			5312	5312			
5530-5531			5312	5312			
5531-5532			5312	5312			
5532-5533			5312	5312			
5533-5534			5312	5312			
5534-5535			5312	5312			
5535-5536			5312	5312			
5536-5537			5312	5312			
5537-5538			5312	5312			
5538-5539			5312	5312			
5539-5540			5312	5312			
5540-5541			5312	5312			
5541-5542			5312	5312			
5542-5543			5312	5312			
5543-5544			5312	5312			
5544-5545			5312	5312			
5545-5546			5312	5312			
5546-5547			5312	5312			
5547-5548			5312	5312			
5548-5549			5312	5312			
5549-5550			5312	5312			
5550-5551			5312	5312			
5551-5552			5312	5312			
5552-5553			5312	5312			
5553-5554			5312	5312			
5554-5555			5312	5312			
5555-5556			5312	5312			
5556-5557			5312	5312			
5557-5558			5312	5312			
5558-5559			5312	5312			
5559-5560			5312	5312			
5560-5561			5312	5312			
5561-5562			5312	5312			
5562-5563			5312	5312			
5563-5564			5312	5312			
5564-5565			5312	5312			
5565-5566			5312	5312			
5566-5567			5312	5312			
5567-5568			5312	5312			
5568-5569			5312	5312			
5569-5570			5312	5312			
5570-5571			5312	5312			
5571-5572			5312	5312			
5572-5573			5312	5312			
5573-5574			5312	5312			
5574-5575			5312	5312			
5575-5576			5312	5312			
5576-5577			5312	5312			
5577-5578			5312	5312			
5578-5579			5312	5312			
5579-5580			5312	5312			
5580-5581			5312	5312			
5581-5582			5312	5312			
5582-5583			5312	5312			
5583-5584			5312	5312			
5584-5585			5312	5312			
5585-5586			5312	5312			
5586-5587			5312	5312			
5587-5588			5312	5312			
5588-5589			5312	5312			
5589-5590			5312	5312			
5590-5591			5312	5312			
5591-5592			5312	5312			
5592-5593			5312	5312			
5593-5594			5312	5312			
5594-5595			5312	5312			
5595-5596			5312	5312			
5596-5597			5312	5312			
5597-5598			5312	5312			
5598-5599			5312	5312			
5599-5600			5312	5312			
5600-5601			5312	5312			
5601-5602			5312	5312			
5602-5603			5312	5312			
5603-5604			5312	5312			
5604-5605			5312	5312			
5605-5606			5312	5312			
5606-5607			5312	5312			
5607-5608			5312	5312			
5608-5609			5312	5312			
5609-5610			5312	5312			
5610-5611			5312	5312			
5611-5612			5312	5312			
5612-5613			5312	5312			
5613-5614			5312	5312			
5614-5615			5312	5312			
5615-5616			5312	5312			
5616-5617			5312	5312			
5617-5618			5312	5312			
5618-5619			5312	5312			
5619-5620			5312	5312			
5620-5621			5312	5312			
5621-5622			5312	5312			
5622-5623			5312	5312			
5623-5624			5312	5312			
5624-5625			5312	5312			
5625-5626			5312	5312			
5626-5627			5312	5312			
5627-5628			5312	5312			
5628-5629			5312	5312			
5629-5630			5312	5312			
5630-5631			5312	5312			
5631-5632			5312	5312			
5632-5633			5312	5312			
5633-5634			5312	5312			
5634-5635			5312	5312			
5635-5636			5312	5312			
5636-5637			5312	5312			
5637-5638			5312	5312			
5638-5639			5312	5312			
5639-5640			5312	5312			
5640-5641			5312	5312			
5641-5642			5312	5312			
5642-5643			5312	5312			
5643-5644			5312	5312			
5644-5645			5312	5312			
5645-5646			5312	5312			
5646-5647			5312	5312			
5647-5648			5312	5312			
5648-5649			5312	5312			

1. OUR FATHERS' DIALECT:

RECEIVED ON FILE Date

ΕΛΛΗΝΙΚΗ ΔΗΜΟΚΡΑΤΙΑ

~~APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC.~~ owner

George W. Wilsman, (Title) Agent

W-8

[illegible]

INITIAL PRODUCTION FIRST 24 HOURS			TACKER RECORD			
			KIND	SIZE	DEPTH SET	DATE SET
Open Flow	/10ths Water in	Inch	Steel Shoe	4-5/8" OD	266'	12-20-63
	/10ths Merc. in	Inch	Float Collar	1 1/2" OD	2397'	1-14-64
Volume	Shoe Oil & Gas (Drilled w/Retort)	Cu. Ft.	Inside Shoe	1 1/2" OD	2427'	1-14-64
Rock Pressure	Read Taken	lbs.				
Oil		bbls., First 24 hrs.				

ACIDIZING OR FRACTURING RECORD		CASING CEMENTED SURFACES TO:
DATE WELL ACIDIZED..... 1-22-63	2-5/8"	SIZE 286 FT.
DATE WELL FRACTURED.....		DAI 12-20-63
NAME OF COMPANY... Halliburton Company	1 1/2"	SIZE 2127 FT.
(List below materials used in Acidizing or Fracturing, i.e., Sand, Crude Oil, Gasoline, Water, Kerosene, Mothballs, Acid, etc., giving gallons, barrels and pounds).		DAI 1-14-64
Sands 10,000 Gals. Water		SIZE _____ Ft.
Sands 15,000 Lbs. Sand		DAI _____
Sands 10 Gals. Mottlo:		USED IN CEMENTING 2-5/8" CASINGS:
Sands 10 Gals. Buds		35 - Bags Cement
Sands 100 G.A.S. acid 15% HCL		I - Bag Calcium Chloride
Sands 150 lbs. Wax-oil		Cemented by: Well Service, Inc.
		USED IN CEMENTING 1 1/2" CASINGS:
		65 - Bags Cement
		500 - Gals. Mud Acid
		Cemented by: Swell
BREAKDOWN PRESSURE... 5000		
PUMPING PRESSURE... 1000 to 2000		
AVERAGE PUMP RATE/MINUTE... 20 bbls.		
PUMPING TIME... 30 min.		
RESULT AFTER TREATMENT } GAS... 30 bbls.	CU. FT.	
OIL... 30 bbls.	BBLS.	
ROCK PRESSURE AFTER TREATMENT... 5000	LBS.	

8. m.

REMARKS: Drilled 10-5/8" hole from surface to 254'
Drilled 7-7/8" hole from 254' to 2180'

~~Note: Rotary Scale Used.~~
~~Note: 5 Centigrade Used.~~

~~Motor Approx. \$31.00 of \$55.00 casing was damaged beyond repair by Contractor.~~

Notes: This call detailed concerning to Rule 11, under subsection 13 of Article 4, Chapter 22 of the Code of the Department of Justice, that was the subject of the

APPROVED

C C C TOLSON



"Pipeline"

Select County: (087) Roane ☐ (Check All)

Enter Permit #: 994

☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

W-12

WV Geological & Economic Survey:

Well: County = 87 Permit = 994 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 8:05:48 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LONG_DD	UTME	UTMN
4708700994	Roane	994	Smithfield	Spencer	Spencer	38.759694	-81.265731	476912.3	4290143.6

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST
4708700994	10/28/1963	Original Loc	Completed	W Kaufman, R Rhodes	W-12				Alfred M Oppenheimer II	Wolfs Head Oil Refining Co., Inc.			
4708700994	11/15/1972	Worked Over	Completed	W Kaufman, Roy Rhodes	W-12				Alfred M Oppenheimer II	Pennzoil Company			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_E
4708700994	10/28/1963	10/26/1963	1152	Ground Level	Chr-Rsh Rn	Undf PRICE blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil and Gas	Rotary	Fractured	2380		2380		2380
4708700994	11/15/1972	-/-	1152	Ground Level	Chr-Rsh Rn	Undf PRICE blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil	unknown	Acid+Frac	2380				0

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEFF	G_AFT	O_BEFF	O_AFT	WATER_QNTY
4708700994	10/28/1963	Show	Oil	Vertical	2220	Big Lime	2240	Big Lime	0	0			
4708700994	10/28/1963	Pay	Oil	Vertical	2316	Big Injun (Price&eq)	2330	Big Injun (Price&eq)	0	35			
4708700994	10/28/1963	Pay	Gas	Vertical	2316	Big Injun (Price&eq)	2330	Big Injun (Price&eq)	0	40			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700994	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Pennzoil Products Company	1989	1,290	128	94	103	106	136	95	119	80	101	133	104	91
4708700994	Pennzoil Products Company	1990	1,196	103	73	114	82	86	82	73	97	98	145	124	119
4708700994	Pennzoil Products Company	1991	983	114	86	84	91	92	89	98	0	63	93	90	83
4708700994	Pennzoil Products Company	1992	823	93	46	50	50	61	73	75	82	76	87	68	62
4708700994	Pennzoil Products Company	1993	688	52	69	69	34	50	59	60	63	64	61	51	56
4708700994	Pennzoil Products Company	1994	624	63	57	29	51	62	53	51	59	54	52	44	49
4708700994	Pennzoil Products Company	1995	514	39	61	49	41	42	41	42	41	44	38	35	41
4708700994	Pennzoil Products Company	1996	406	21	1	52	44	32	34	42	33	38	27	41	41
4708700994	Pennzoil Products Company	1997	448	32	37	35	30	32	31	34	36	43	32	50	56
4708700994	Pennzoil Products Company	1998	409	55	52	43	40	35	46	29	24	21	22	20	22
4708700994	Pennzoil Products Company	1999	227	46	48	27	22	15	0	0	0	12	21	22	14
4708700994	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708700994	East Resources, Inc.	2001	648	7	42	63	70	79	70	66	58	61	62	63	7
4708700994	East Resources, Inc.	2002	623	54	47	49	50	50	53	53	55	43	46	58	65
4708700994	East Resources, Inc.	2003	540	31	21	0	23	54	61	57	52	56	70	78	37
4708700994	East Resources, Inc.	2004	619	46	50	45	49	64	55	67	58	54	29	27	77
4708700994	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708700994	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708700994	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708700994	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708700994	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708700994	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708700994	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708700994	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708700994	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708700994	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708700994	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	39	38
4708700994	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708700994	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708700994	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708700994	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708700994	HG Energy, LLC	2021	315	32	28	33	35	37	34	0	0	26	28	31	31
4708700994	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708700994	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0
4708700994	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700994	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Pennzoil Company	1983	445	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Pennzoil Products Company	1989	265	26	24	27	22	22	17	22	23	22	22	20	18
4708700994	Pennzoil Products Company	1990	250	23	17	21	21	14	20	21	24	24	26	22	17
4708700994	Pennzoil Products Company	1991	178	19	19	19	17	17	0	11	16	17	16	17	10
4708700994	Pennzoil Products Company	1992	160	12	12	15	14	13	14	14	17	13	13	10	13
4708700994	Pennzoil Products Company	1993	147	14	10	10	13	13	14	14	13	11	11	12	12
4708700994	Pennzoil Products Company	1994	131	6	12	15	12	10	12	12	11	9	11	8	13
4708700994	Pennzoil Products Company	1995	87	10	8	9	9	9	8	9	8	8	9	0	0
4708700994	Pennzoil Products Company	1996	109	14	12	8	8	9	6	8	9	9	9	8	9
4708700994	Pennzoil Products Company	1997	98	8	8	9	8	9	9	7	7	8	9	9	7
4708700994	Pennzoil Products Company	1998	76	9	8	7	9	3	0	0	0	0	0	24	16
4708700994	Pennzoil Products Company	1999	33	14	15	4	0	0	0	0	0	0	0	0	0
4708700994	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	East Resources, Inc.	2001	236	0	27	26	23	30	22	23	15	17	20	16	17
4708700994	East Resources, Inc.	2002	187	15	18	15	15	16	18	22	15	12	12	13	16
4708700994	East Resources, Inc.	2003	144	14	7	0	3	19	20	14	11	17	17	7	15
4708700994	East Resources, Inc.	2004	157	7	16	16	15	15	13	16	15	14	12	7	11
4708700994	East Resources, Inc.	2005	156	11	15	13	12	13	13	11	16	13	12	15	12
4708700994	East Resources, Inc.	2006	77	8	5	6	7	9	7	6	0	6	8	8	7
4708700994	East Resources, Inc.	2007	76	8	4	7	7	7	5	6	9	6	5	5	7
4708700994	East Resources, Inc.	2008	63	6	8	5	5	5	6	5	4	4	5	4	6
4708700994	East Resources, Inc.	2010	122	16	11	13	15	0	12	11	8	8	10	8	10
4708700994	East Resources, Inc.	2011	104	8	7	9	10	8	10	8	10	9	8	8	9
4708700994	HG Energy, LLC	2012	99	8	10	8	8	10	8	4	10	9	13	5	6
4708700994	HG Energy, LLC	2013	149	10	13	11	12	14	10	15	13	15	15	12	9
4708700994	HG Energy, LLC	2014	141	10	11	10	12	20	13	12	14	10	10	9	10
4708700994	HG Energy, LLC	2015	155	13	11	11	15	10	12	15	12	12	16	13	15
4708700994	HG Energy, LLC	2016	157	12	14	17	12	11	16	13	17	13	11	9	12
4708700994	HG Energy, LLC	2017	130	12	11	12	9	12	9	9	14	12	9	12	9
4708700994	HG Energy, LLC	2018	104	10	8	10	8	8	10	8	8	10	5	11	11
4708700994	HG Energy, LLC	2019	96	13	8	8	8	10	6	9	4	6	10	7	7
4708700994	HG Energy, LLC	2020	92	8	8	7	10	8	8	10	8	8	6	5	6
4708700994	HG Energy, LLC	2021	82	8	4	4	10	8	9	6	7	5	5	5	11
4708700994	HG Energy, LLC	2022	92	7	6	10	8	10	7	8	7	7	10	5	6
4708700994	HG Energy, LLC	2023	73	6	8	7	7	7	5	7	8	8	10	0	0
4708700994	Delta Helix Energy, LLC	2023	14	0	0	0	0	0	0	0	0	0	0	0	7

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700994	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2016	0												
4708700994	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

4708700994

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700994	HG Energy, LLC	2016	0												
4708700994	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700994	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700994	Original Loc	Little Lime	Well Record	2135	Reasonable	15	Reasonable	1152	Ground Level
4708700994	Original Loc	Pencil Cave	Past WVGES Staff Geologist	2150	Reasonable	35	Reasonable	1152	Ground Level
4708700994	Original Loc	Big Lime	Well Record	2185	Reasonable	109	Reasonable	1152	Ground Level
4708700994	Original Loc	Greenbrler Group	Past WVGES Staff Geologist	2185	Reasonable	125	Reasonable	1152	Ground Level
4708700994	Original Loc	Keener	Well Record	2294	Reasonable	16	Reasonable	1152	Ground Level
4708700994	Original Loc	Big Injun (Price&eq)	Past WVGES Staff Geologist	2310	Reasonable	25	Reasonable	1152	Ground Level
4708700994	Original Loc	Undf PRICE blw INJN	Well Record	2335	Reasonable	0	Reasonable	1152	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708700994

C6018G N. H. J. B. S. (L. H. S.) B. S. H. C.

W-12

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 15

NOV 1963

16 03

Quadrangle SPENCER

Permit No. ROA-994

WELL RECORD

Oil or Gas Well

(KIND)

Company WOLF'S HEAD OIL REFINING COMPANY, INC.

Address P. O. Box 1588, Parkersburg, W. Va.

Farm Wm. Kaufman Acres 800

Location (waters) Slab Camp Run

Well No. W-12 Elev. 1152.09

District Smithfield County Roane

The surface of tract is owned in fee by Roy Rhodes c/o Bernard Burgess

Otto Route Address Spencer, W. Va.

Mineral rights are owned by Alfred M. Oppenheimer II, et al.

300 South Lang Avenue Address Pittsburgh 8, Pa.

Drilling commenced October 26, 1963

Drilling completed October 28, 1963

Date Shot From To

With

Open Flow /10ths Water in Inch

/10ths Merc. in Inch

Volume Show Oil & Gas (Drilled w/Rotary) Cu. Ft.

Rock Pressure lbs. hrs.

Oil bbls., 1st 24 hrs.

WELL ACIDIZED


WELL FRACTURED November 18, 1963

RESULT AFTER TREATMENT Gas 40,000 Cu. Ft. Oil 35 Bbls.

ROCK PRESSURE AFTER TREATMENT 510 Lbs.

Fresh Water NONE Feet Salt Water Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Sand & Shale			0	120			
Red Rock			120	185			
Sand			185	205			
Red Rock			205	225			
Sand			225	250			
Shale			250	275			
Sand			275	325			
Red Rock			325	335			
Sand			335	344			
Red Rock			344	630			
Blue Shale			630	720			
Red Rock			720	870			
Sand			870	985			
Shale			985	1010			
Sand			1010	1385			
Shale			1385	1435			
Sand			1435	1510			
Slate			1510	1730			
Shale			1730	1915			
Sand			1915	1955			
Shale			1955	2135			
Little Lime			2135	2150			
Shale			2150	2155			
Sand			2155	2158			
Shale			2158	2185			
Big Lime			2185	2294			
Keener Sand			2294	2310	Oil	2220-2240	Show Only
Big Injun			2310	2335			
			2332	2390	Oil & Gas	2316-2330	



Formation Color Hard or Soft Top Bottom Oil, Gas or Water Depth Remarks

4708700994

Formation	Color	Hard or Soft	Top 15	Bottom	Oil, Gas or Water	Depth Found	Remarks
Shale			2335	2380	Oil & Gas	3310-3320	
4 1/2" Casing			3310	2377			
3300-3310			3307	3310			
TOTAL DEPTH				2380	Oil	3350-3360	2300-2310
218 1/2"			3182	3307			
217 1/2"			3128	3182			
216 1/2"			3122	3128			
215 1/2"			3120	3122			
175 1/2" 1750			3122	3120			
217 1/2"			3022	3122			
201 1/2"			3012	3022			
218 1/2"			3010	3012			
217 1/2"			3002	3010			
216 1/2"			3000	3002			
215 1/2"			2992	3000			
214 1/2"			2982	2992			
213 1/2"			2972	2982			
212 1/2"			2962	2972			
211 1/2"			2952	2962			
210 1/2"			2942	2952			
209 1/2"			2932	2942			
208 1/2"			2922	2932			
207 1/2"			2912	2922			
206 1/2"			2902	2912			
205 1/2"			2892	2902			
204 1/2"			2882	2892			
203 1/2"			2872	2882			
202 1/2"			2862	2872			
201 1/2"			2852	2862			
200 1/2"			2842	2852			
199 1/2"			2832	2842			
198 1/2"			2822	2832			
197 1/2"			2812	2822			
196 1/2"			2802	2812			
195 1/2"			2792	2802			
194 1/2"			2782	2792			
193 1/2"			2772	2782			
192 1/2"			2762	2772			
191 1/2"			2752	2762			
190 1/2"			2742	2752			
189 1/2"			2732	2742			
188 1/2"			2722	2732			
187 1/2"			2712	2722			
186 1/2"			2702	2712			
185 1/2"			2692	2702			
184 1/2"			2682	2692			
183 1/2"			2672	2682			
182 1/2"			2662	2672			
181 1/2"			2652	2662			
180 1/2"			2642	2652			
179 1/2"			2632	2642			
178 1/2"			2622	2632			
177 1/2"			2612	2622			
176 1/2"			2602	2612			
175 1/2"			2592	2602			
174 1/2"			2582	2592			
173 1/2"			2572	2582			
172 1/2"			2562	2572			
171 1/2"			2552	2562			
170 1/2"			2542	2552			
169 1/2"			2532	2542			
168 1/2"			2522	2532			
167 1/2"			2512	2522			
166 1/2"			2502	2512			
165 1/2"			2492	2502			
164 1/2"			2482	2492			
163 1/2"			2472	2482			
162 1/2"			2462	2472			
161 1/2"			2452	2462			
160 1/2"			2442	2452			
159 1/2"			2432	2442			
158 1/2"			2422	2432			
157 1/2"			2412	2422			
156 1/2"			2402	2412			
155 1/2"			2392	2402			
154 1/2"			2382	2392			
153 1/2"			2372	2382			
152 1/2"			2362	2372			
151 1/2"			2352	2362			
150 1/2"			2342	2352			
149 1/2"			2332	2342			
148 1/2"			2322	2332			
147 1/2"			2312	2322			
146 1/2"			2302	2312			
145 1/2"			2292	2302			
144 1/2"			2282	2292			
143 1/2"			2272	2282			
142 1/2"			2262	2272			
141 1/2"			2252	2262			
140 1/2"			2242	2252			
139 1/2"			2232	2242			
138 1/2"			2222	2232			
137 1/2"			2212	2222			
136 1/2"			2202	2212			
135 1/2"			2192	2202			
134 1/2"			2182	2192			
133 1/2"			2172	2182			
132 1/2"			2162	2172			
131 1/2"			2152	2162			
130 1/2"			2142	2152			
129 1/2"			2132	2142			
128 1/2"			2122	2132			
127 1/2"			2112	2122			
126 1/2"			2102	2112			
125 1/2"			2092	2102			
124 1/2"			2082	2092			
123 1/2"			2072	2082			
122 1/2"			2062	2072			
121 1/2"			2052	2062			
120 1/2"			2042	2052			
119 1/2"			2032	2042			
118 1/2"			2022	2032			
117 1/2"			2012	2022			
116 1/2"			2002	2012			
115 1/2"			1992	2002			
114 1/2"			1982	1992			
113 1/2"			1972	1982			
112 1/2"			1962	1972			
111 1/2"			1952	1962			
110 1/2"			1942	1952			
109 1/2"			1932	1942			
108 1/2"			1922	1932			
107 1/2"			1912	1922			
106 1/2"			1902	1912			
105 1/2"			1892	1902			
104 1/2"			1882	1892			
103 1/2"			1872	1882			
102 1/2"			1862	1872			
101 1/2"			1852	1862			
100 1/2"			1842	1852			
99 1/2"			1832	1842			
98 1/2"			1822	1832			
97 1/2"			1812	1822			
96 1/2"			1802	1812			
95 1/2"			1792	1802			
94 1/2"			1782	1792			
93 1/2"			1772	1782			
92 1/2"			1762	1772			
91 1/2"			1752	1762			
90 1/2"			1742	1752			
89 1/2"			1732	1742			
88 1/2"			1722	1732			
87 1/2"			1712	1722			
86 1/2"			1702	1712			
85 1/2"			1692	1702			
84 1/2"			1682	1692			
83 1/2"			1672	1682			
82 1/2"			1662	1672			
81 1/2"			1652	1662			
80 1/2"			1642	1652			
79 1/2"			1632	1642			
78 1/2"			1622	1632			
77 1/2"			1612	1622			
76 1/2"			1602	1612			
75 1/2"			1592	1602			
74 1/2"			1582	1592			
73 1/2"			1572	1582			
72 1/2"			1562	1572			
71 1/2"			1552	1562			
70 1/2"			1542	1552			
69 1/2"			1532	1542			
68 1/2"			1522	1532			
67 1/2"			1512	1522			
66 1/2"			1502	1512			
65 1/2"			1492	1502			
64 1/2"			1482	1492			
63 1/2"			1472	1482			
62 1/2"			1462	1472			
61 1/2"			1452	1462			
60 1/2"			1442	1452			
59 1/2"			1432	1442			
58 1/2"			1422	1432			
57 1/2"			1412	1422			
56 1/2"			1402	1412			
55 1/2"			1392	1402			
54 1/2"			1382	1392			
53 1/2"			1372	1382			
52 1/2"			1362	1372			
51 1/2"			1352	1362			
50 1/2"			1342	1352			
49 1/2"			1332	1342			
48 1/2"			1322	1332			
47 1/2"			1312	1322			
46 1/2"			1302	1312			
45 1/2"			1292	1302			
44 1/2"			1282	1292			
43 1/2"			1272	1282			
42 1/2"			1262	1272			
41 1/2"			1252	1262			
40 1/2"			1242	1252			
39 1/2"			1232	1242			
38 1/2"			1222	1232			
37 1/2"			1212	1222			
36 1/2"			1202	1212			
35 1/2"			1192	1202			
34 1/2"			1182	1192			
33 1/2"			1172	1182			
32 1/2"			1162	1172			
31 1/2"			1152	1162			
30 1/2"			1142	1152			
29 1/2"			1132	1142			
28 1/2"			1122	1132			
27 1/2"			1112	1122			
26 1/2"			1102	1112			
25 1/2"			1092	1102			
24 1/2"			1082	1092			
23 1/2"			1072	1082			
22 1/2"			1062	1072			
21 1/2"			1052	1062			
20 1/2"			1042	1052			
19 1/2"			1032	1042			
18 1/2"			1022	1032			
17 1/2"			1012	1022			
16 1/2"			1002	1012			
15 1/2"			992	1002			
14 1/2"			982	992			
13 1/2"			972	982			
12 1/2"			962	972			
11 1/2"			952	962			
10 1/2"			942	952			
9 1/2"			932	942			
8 1/2"			922	932			
7 1/2"			912	922			
6 1/2"			902	912			
5 1/2"			892	902			
4 1/2"			882	892			
3 1/2"			872	882			
2 1/2"			862	872			
1 1/2"			852	862			
1/2"			842	852			
0 1/2"</							

OFFICE OF THE DIRECTOR
DEPARTMENT OF THE ARMY
WASHINGTON, D. C.

December 10 19 63

TABLE OF CONTENTS

APPROVED ~~WOLF'S~~ HEAD OIL REFINING COMPANY, INC. Owner

By George W. Wilsman
George W. Wilsman (Title) Agent



NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION SOUTH-PENNSYLVANIA COMPANY

4708700994

NEW WELL REPORT

W-12

No. 0129 ACRES 0.00 WORKING DISTRICT Traverse A
 Loc. Traverse FARM W-12 N. 47 E. 77
Traverse DISTRICT OR TOWNSHIP Traverse COUNTY Traverse QUAD.
 LOCATION MADE September 27, 19 69 DRILLING COMMENCED October 22, 19 69
 RIG COMMENCED October 26, 19 69 DRILLING COMPLETED November 6, 19 69
 RIG COMPLETED October 28, 19 69 DEPTH 2050' SAND Big Ingot
 RIG CONTRACTOR Traverse Drilling Co., Inc. DRILLING CONTRACTOR Traverse Drilling Co., Inc.
 ELEVATION: FLOOR 1152.00 GROUND 1152.00 WORK ORDER NO. W-12-59-11, Va.

FORMATION RECORD

KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST	KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST
Oil & Gas	0	100							
Oil & Gas	100	105							
Oil & Gas	105	110							
Oil & Gas	110	115							
Oil & Gas	115	120							
Oil & Gas	120	125							
Oil & Gas	125	130							
Oil & Gas	130	135							
Oil & Gas	135	140							
Oil & Gas	140	145							
Oil & Gas	145	150							
Oil & Gas	150	155							
Oil & Gas	155	160							
Oil & Gas	160	165							
Oil & Gas	165	170							
Oil & Gas	170	175							
Oil & Gas	175	180							
Oil & Gas	180	185							
Oil & Gas	185	190							
Oil & Gas	190	195							
Oil & Gas	195	200							
Oil & Gas	200	205							
Oil & Gas	205	210							
Oil & Gas	210	215							
Oil & Gas	215	220							
Oil & Gas	220	225							
Oil & Gas	225	230							
Oil & Gas	230	235							
Oil & Gas	235	240							
Oil & Gas	240	245							
Oil & Gas	245	250							
Oil & Gas	250	255							
Oil & Gas	255	260							
Oil & Gas	260	265							
Oil & Gas	265	270							
Oil & Gas	270	275							
Oil & Gas	275	280							
Oil & Gas	280	285							
Oil & Gas	285	290							
Oil & Gas	290	295							
Oil & Gas	295	300							
Oil & Gas	300	305							
Oil & Gas	305	310							
Oil & Gas	310	315							
Oil & Gas	315	320							
Oil & Gas	320	325							
Oil & Gas	325	330							
Oil & Gas	330	335							
Oil & Gas	335	340							
Oil & Gas	340	345							
Oil & Gas	345	350							
Oil & Gas	350	355							
Oil & Gas	355	360							
Oil & Gas	360	365							
Oil & Gas	365	370							
Oil & Gas	370	375							
Oil & Gas	375	380							
Oil & Gas	380	385							
Oil & Gas	385	390							
Oil & Gas	390	395							
Oil & Gas	395	400							
Oil & Gas	400	405							
Oil & Gas	405	410							
Oil & Gas	410	415							
Oil & Gas	415	420							
Oil & Gas	420	425							
Oil & Gas	425	430							
Oil & Gas	430	435							
Oil & Gas	435	440							
Oil & Gas	440	445							
Oil & Gas	445	450							
Oil & Gas	450	455							
Oil & Gas	455	460							
Oil & Gas	460	465							
Oil & Gas	465	470							
Oil & Gas	470	475							
Oil & Gas	475	480							
Oil & Gas	480	485							
Oil & Gas	485	490							
Oil & Gas	490	495							
Oil & Gas	495	500							
Oil & Gas	500	505							
Oil & Gas	505	510							
Oil & Gas	510	515							
Oil & Gas	515	520							
Oil & Gas	520	525							
Oil & Gas	525	530							
Oil & Gas	530	535							
Oil & Gas	535	540							
Oil & Gas	540	545							
Oil & Gas	545	550							
Oil & Gas	550	555							
Oil & Gas	555	560							
Oil & Gas	560	565							
Oil & Gas	565	570							
Oil & Gas	570	575							
Oil & Gas	575	580							
Oil & Gas	580	585							
Oil & Gas	585	590							
Oil & Gas	590	595							
Oil & Gas	595	600							
Oil & Gas	600	605							
Oil & Gas	605	610							
Oil & Gas	610	615							
Oil & Gas	615	620							
Oil & Gas	620	625							
Oil & Gas	625	630							
Oil & Gas	630	635							
Oil & Gas	635	640							
Oil & Gas	640	645							
Oil & Gas	645	650							
Oil & Gas	650	655							
Oil & Gas	655	660							
Oil & Gas	660	665							
Oil & Gas	665	670							
Oil & Gas	670	675							
Oil & Gas	675	680							
Oil & Gas	680	685							
Oil & Gas	685	690							
Oil & Gas	690	695							
Oil & Gas	695	700							
Oil & Gas	700	705							
Oil & Gas	705	710							
Oil & Gas	710	715							
Oil & Gas	715	720							
Oil & Gas	720	725							
Oil & Gas	725	730							
Oil & Gas	730	735							
Oil & Gas	735	740							
Oil & Gas	740	745							
Oil & Gas	745	750							
Oil & Gas	750	755							
Oil & Gas	755	760							
Oil & Gas	760	765							
Oil & Gas	765	770							
Oil & Gas	770	775							
Oil & Gas	775	780							
Oil & Gas	780	785							
Oil & Gas	785	790							
Oil & Gas	790	795							
Oil & Gas	795	800							
Oil & Gas	800	805							
Oil & Gas	805	810							
Oil & Gas	810	815							
Oil & Gas	815	820							
Oil & Gas	820	825							
Oil & Gas	825	830							
Oil & Gas	830	835							
Oil & Gas	835	840							
Oil & Gas	840	845							
Oil & Gas	845	850							
Oil & Gas	850	855							
Oil & Gas	855	860							
Oil & Gas	860	865							
Oil & Gas	865	870							
Oil & Gas	870	875							
Oil & Gas	875	880							
Oil & Gas	880	885							
Oil & Gas	885	890							
Oil & Gas	890	895							
Oil & Gas	895	900							
Oil & Gas	900	905							
Oil & Gas	905	910							
Oil & Gas	910	915							
Oil & Gas	915	920							
Oil & Gas	920	925							
Oil & Gas	925	930							
Oil & Gas	930	935							
Oil & Gas	935	940							
Oil & Gas	940	945							
Oil & Gas	945	950							
Oil & Gas	950	955							
Oil & Gas	955	960							
Oil & Gas	960	965							
Oil & Gas	965	970							
Oil & Gas	970	975							
Oil & Gas	975	980							
Oil & Gas	980	985							
Oil & Gas	985	990							
Oil & Gas	990	995							
Oil & Gas	995	1000							

(OVER)

W-12

INITIAL TORPEDO RECORD		CASING AND TUBING RECORD					
Date of Shot	SIZE	PUT IN WELL			PULLED OUT		
		TRANSFER NO.	FEET	INCH	TRANSFER NO.	FEET	INCH
Name of Torpedo Co.	3-1/8"	211	244	1			
No. of Quarts	3-1/8"	211	244	2			
Length of Shell	3-1/8"	211	244	2			
Diameter of Shell							
Length of Anchor							
Top of Shot							
Bottom of Shot							
Feet of Fluid in Hole When Shot							
Results:							

INITIAL PRODUCTION FIRST 24 HOURS		KIND	SIZE	DEPTH SET	DATE SET
Open Flow	/10ths Water in _____ Inch	Steel Shot	3-1/8" G	250	11-27-45
	/10ths Merc. in _____ Inch	First Collar	1 1/2" G	257	11-7-45
Volume	Flow Oil & Gas (Gallons w/Barrel) Cu. Ft.	Cable Shot	1 1/2" G	257	11-7-45
Rock Pressure	_____ lbs.				
Oil	Oil _____ bbls. First 24 hrs.				

[illegible]

CORNER CEMENT

8-1/2"	SIZE	340	10-17-43	DA"
4-1/2"	SIZE	5077	11- 7-43	DA"
	SIZE			DA"

USED IN CONSTRUCTION OF S/WAY CULVERT:

20 Bags - Cement

Contracted by: Gerald D. Jones

USED IN CONSTRUCTION AND GRAVEL:

500 Gal. - Hot Fluid

65 Gals. - Fluids Cement (Consists
of 35 Gals. Columbia Cement &
30 Gals. of Pozzolan A & I Reinf.
Burton Sol.)

50' - Reinf-Wall Concrete & 5 Cuts
Horse.

14 - Ballikurten Hold-A

Contracted by: Ballikurten Co.

REMARKS: Revised 12/2/76: Note from Natchez on 12/2/76 Revised 12/2/76: Note from Natchez on 12/2/76 Revised 12/2/76: Note from Natchez on 12/2/76

विषय: विद्यार्थी का विवेक और विवेक के विकास के लिए शिक्षा का योगदान

[illegible]

APPROVED

CC C

SUPERINTENDENT



Page 2 of 2

Get Data

W-13

4708700995	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

4708700995

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708700995	HG Energy, LLC	2016	0												
4708700995	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708700995	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708700995	Original Loc	Little Lime	Well Record	2065	Reasonable	45	Reasonable	1096	Ground Level
4708700995	Original Loc	Pencil Cave	Well Record	2110	Reasonable	5	Reasonable	1096	Ground Level
4708700995	Original Loc	Greenbrier Group	Past WVGES Staff Geologist	2115	Reasonable	135	Reasonable	1096	Ground Level
4708700995	Original Loc	Big Lime	Well Record	2115	Reasonable	120	Reasonable	1096	Ground Level
4708700995	Original Loc	Keener	Well Record	2235	Reasonable	15	Reasonable	1096	Ground Level
4708700995	Original Loc	Big Injun (Price&eq)	Past WVGES Staff Geologist	2250	Reasonable	15	Reasonable	1096	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708700995

W-13

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 16

Quadrangle SPENCERPermit No. ROA-995

WELL RECORD


Oil or Gas Well _____ (K.L.)

Company WOLF'S HEAD OIL REFINING COMPANY, INC.
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres 800
Location (waters) Slab Camp Run
Well No. W-13 Elev. 1096.46
District Smithfield County Roane
The surface of tract is owned in fee by Romie Smith
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer II, et al.
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced November 10, 1963
Drilling completed November 17, 1963
Date Shot - From - To -
With -
Open Flow - /10ths Water in - Inch
- /10ths Merc. in - Inch
Volume Show Oil & Gas (Drilled w/Rotary) Cu. Ft.
Rock Pressure - lbs. - hrs.
Oil - bbls., 1st 24 hrs.
WELL ACIDIZED -

WELL FRACTURED November 27, 1963RESULT AFTER TREATMENT Gas - 37,000 Cu. Ft.
Oil - 13 bbls.ROCK PRESSURE AFTER TREATMENT 497 Lbs.Fresh Water NONE Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Clay & Shale			0	350			
Shale & Red Rock			350	400			
Sand & Shale			400	690			
Sand			690	735			
Red Rock			735	740			
Shale			740	785			
Sand & Shale			785	790			
Sand			790	805			
Shale			805	880			
Red Rock			880	930			
Sand & Shale			930	1120			
Sand			1120	1135			
Shale			1135	1145			
Sand			1145	1480			
Shale			1480	1490			
Red Rock			1490	1500			
Shale			1500	1535			
Sand			1535	1815			
Shale & Lime			1815	1870			
Sand			1870	2025			
Shale			2025	2050			
Sand			2050	2065			
Little Lime			2065	2110			
Pencil Cave			2110	2115			
Big Lime			2115	2235			
Keener Sand			2235	2250			
Big Inj.			2250	2265			
Shale			2265	2313	Oil & Gas	2253-2261	

(over)



4708700995

Formation	Color	Hard or Soft	Top /6	Bottom	Oil, Gas or Water	Depth Found	Remarks
4½" Casing				2313			
TOTAL DEPTH				2313			

Date December 10, 1963

APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC. owner

By George W. Wilsman
George W. Wilsman (Title) Agent

Ree

(OVER)

Note: This well was drilled according to Rule 11, under Section 13, of Article 4, Chapter 22, of the Code of the Department of Mines, Oil & Gas Division.

C. C. C.
SUPERINTENDENT

**"Pipeline"**

Select County: (087) Roane

Enter Permit #: 1032

Get Data

Reset

Select datatypes: ☐ (Check All)

- ☒ Location
- ☒ Production
- ☒ Plugging
- ☒ Owner/Completion
- ☒ Stratigraphy
- ☒ Sample
- ☒ Pay/Show/Water
- ☒ Logs
- ☒ Btm Hole Loc

[Table Descriptions](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)**W-16**

WV Geological & Economic Survey:

Well: County = 87 Permit = 1032 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 8:11:31 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708701032	Roane	1032	Smithfield	Spencer	Spencer	38.75558	-81.259991	477409.7	4289685.6

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708701032	5/-1964	Original Loc	Completed	William Kaufman	23	W-16				Wolf's Head Oil Refining Co., Inc.			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEFG
4708701032	5/-1964	-/-	1163	Ground Level	Clvr-Rsh Rn	Price Fm & equivs	Price Fm & equivs	Development Well	Development Well	Oil and Gas	unknown	Fractured	2371		2371		0

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEFG	G_AFT	O_BEFG	O_AFT	WATER_QNTY
4708701032	5/-1964	Water	Unknown Water	Vertical			930						0
4708701032	5/-1964	Water	Unknown Water	Vertical			1850						0
4708701032	5/-1964	Pay	Oil & Gas	Vertical			2330	Big Inj (Price&eq)	0		0		

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701032	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1989	904	0	0	0	88	111	91	124	84	101	127	99	79
4708701032	Pennzoil Products Company	1990	442	108	64	0	0	53	66	47	24	23	18	21	18
4708701032	Pennzoil Products Company	1991	251	26	20	13	14	19	21	23	21	29	23	16	26
4708701032	Pennzoil Products Company	1992	125	22	19	21	17	20	26	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1993	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1994	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1995	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1996	22	21	1	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1997	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1998	109	0	0	0	0	0	0	24	21	22	20	22	
4708701032	Pennzoil Products Company	1999	106	0	0	0	22	15	0	0	12	21	22	14	
4708701032	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708701032	East Resources, Inc.	2001	14	7	0	0	0	0	0	0	0	0	0	0	7
4708701032	East Resources, Inc.	2002	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2003	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2004	56	0	0	0	0	0	0	0	0	0	29	27	0
4708701032	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708701032	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708701032	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708701032	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708701032	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708701032	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708701032	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708701032	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708701032	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708701032	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708701032	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	38	
4708701032	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708701032	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708701032	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708701032	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708701032	HG Energy, LLC	2021	99	10	7	6	9	10	9	10	9	8	8	7	6
4708701032	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708701032	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0
4708701032	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701032	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Company	1983	444	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1989	225	0	20	22	21	23	18	22	22	21	19	21	16
4708701032	Pennzoil Products Company	1990	89	20	0	13	17	9	5	5	3	4	4	5	4
4708701032	Pennzoil Products Company	1991	47	3	3	4	4	4	5	4	3	5	4	4	
4708701032	Pennzoil Products Company	1992	18	5	4	4	5	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1993	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1994	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1995	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1996	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1997	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1998	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Pennzoil Products Company	1999	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2001	32	0	0	0	0	0	0	0	0	32	0	0	0
4708701032	East Resources, Inc.	2002	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2003	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2004	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2005	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2006	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2007	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2008	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2010	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	East Resources, Inc.	2011	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2012	442	0	0	0	0	0	0	87	135	68	52	53	47
4708701032	HG Energy, LLC	2013	369	51	50	41	36	31	29	26	31	21	20	17	16
4708701032	HG Energy, LLC	2014	167	20	17	17	16	20	11	10	12	9	12	11	12
4708701032	HG Energy, LLC	2015	153	12	10	13	13	10	13	16	11	12	14	12	17
4708701032	HG Energy, LLC	2016	165	11	16	17	13	12	16	12	16	12	16	11	13
4708701032	HG Energy, LLC	2017	149	13	9	14	11	13	12	12	15	12	12	15	11
4708701032	HG Energy, LLC	2018	141	15	12	12	11	13	12	12	13	10	11	8	12
4708701032	HG Energy, LLC	2019	119	13	8	12	8	12	9	14	8	9	14	5	7
4708701032	HG Energy, LLC	2020	111	10	8	9	14	8	11	8	10	8	8	8	9
4708701032	HG Energy, LLC	2021	93	8	5	6	10	6	10	6	8	9	7	8	10
4708701032	HG Energy, LLC	2022	89	8	7	10	8	10	8	6	7	7	7	7	4
4708701032	HG Energy, LLC	2023	61	6	5	6	5	8	6	4	9	6	6	0	0
4708701032	Delta Helix Energy, LLC	2023	8	0	0	0	0	0	0	0	0	0	0	4	4

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701032	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2016	0												
4708701032	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

4708701032

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701032	HG Energy, LLC	2016	0												
4708701032	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701032	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708701032

REGISTERED

W-16

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 17

Quadrangle SPENCERPermit No. ROA-1032

WELL RECORD


Oil or Gas Well O & G
(KIND)Company WOLF'S HEAD OIL REFINING COMPANY, INC.Address P. O. Box 1588, Parkersburg, W. Va.Farm Wm. Kaufman Acres 800Location (waters) Millstone RunWell No. W-16 Elev. 1162.93District Smithfield County RoaneThe surface of tract is owned in fee by Kenneth MillerAddress Clover, W. Va.Mineral rights are owned by Alfred M. Oppenheimer, II300 South Lang Avenue Address Pittsburgh 8, Pa.Drilling commenced 4/29/64Drilling completed 5/9/64Date Shot - From - To -With -Open Flow /10ths Water in Inch/10ths Merc. in InchVolume Drilled w/Rotary Cu. Ft.Rock Pressure None Taken lbs. hrs.Oil - bbls., 1st 24 hrs.

WELL ACIDIZED

WELL FRACTURED May 15, 1964 Used: 1,000 Bbl. Water, 48000 # Sand 20-40, 300 Gal. MCA 15%, 400 # WAC-8,25 Gal. Aqua Frac and 40 Gal. Mor Flow-IIRESULT AFTER TREATMENT Oil - 15 Bbls.ROCK PRESSURE AFTER TREATMENT 520 Lbs.Fresh Water - Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	10			
10" Casing				10			
Red Rock			10	20			
Sand			20	50			
Slate			50	100			
Red Rock			100	125			
Sand			125	170			
Slate			170	200			
Sand			200	270			
Red Rock			270	280			
Slate			280	300			
Red Rock			300	320			
Slate			320	380			
Red Rock			380	385			
Slate & Shell			385	400			
Sand			400	450			
Slate			450	500			
Red Rock			500	520			
Slate			520	530			
Red Rock			530	560			
8" Casing			560	571			
Slate			571	760			
Sand			760	790			
Red Rock			790	800			
Slate			800	870			
Red Rock			870	900			
Sand			900	930			
Slate			930	1185			
Sand			1185	1220			

OIL & GAS REG. NO. 3312-3330



Water

- 930

4708701032

Formation	Color	Hard or Soft	Top /7	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate			1220	1320			
Sand			1320	1340			
Slate			1340	1400			
Sand			1400	1535			
Slate			1535	1555			
Sand			1555	1635			
Slate			1635	1665			
Sand			1665	1740			
Slate			1740	1755			
Sand			1755	1800			
Slate			1800	1825			
Sand			1825	1990			
Mayon Sand			1990	2020	Water	1850-1900	
Slate			2020	2115			
Little Lime			2115	2167			
Pencil Cave			2167	2175			
Big Lime			2175	2300			
Injun Sand			2300	2330			
Slate			2330	2371	Oil & Gas	2315-2330	
Casing			2371	2365			Log Steel Line Mm.
TOTAL DEPTH			2371	2371			
Log Book			100	100			
Log Book			20	20			
Log Book			30	30			
Log Book			10	10			
Log Book			0	0			

August 12, 1964

APPROVED WOLF S. HEAD OIL REFINING COMPANY, INC. Owner

George W. Wilsman, (Title) Agent

WOLF'S HEAD OIL REFINING CO. INC.
SOUTHERN OIL COMPANY

NEW WELL REPORT

Aco ✓

4708701032
W-16

No. 2217 ACRES 200 WORKING DISTRICT SEABOARD # 1

Mr. Kaufman FARM W-16 N. 47 E. 37

Smithfield DISTRICT OR TOWNSHIP Boone COUNTY QUAD.

LOCATION MADE 1-21- 1964 DRILLING COMMENCED 1-29- 1964

RIG COMMENCED 1-27- 1964 DRILLING COMPLETED 5-9- 1964

RIG COMPLETED 5-29- 1964 DEPTH 2371' SAND Big Injun

RIG CONTRACTOR Gerald Jones DRILLING CONTRACTOR Gerald Jones

ELEVATION: FLOOR 1162.93 GROUND 1162.93 WORK ORDER NO. APR # WH-20-W-Va.

FORMATION RECORD

KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST	KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST
Soil	0	10			Slate	2020	2115		
Casing		10'	10'		Little Line	2115	2167		
Rock	10	20			Pencil Gave	2167	2175		
nd	20	50			Big Line	2175	2200		
ate	50	100			Injun Sand	2200	2320		
Rock	100	125			Oil & Gas Pay	2315	2320		
nd	125	170			Slate	2320	2371		Log
ate	170	200			1 1/2" Casing		2355		
nd	200	270			Total Depth		2371	2371	
Rock	270	280							
ate	280	300							
Rock	300	320							
	320	350							
	350	365							
ate & Shell	365	400							
nd	400	450							
ate	450	500							
Rock	500	520							
ate	520	530							
Rock	530	540							
Casing		571'	571'						
ate	560	760							
nd	760	790							
Rock	790	800							
ate	800	870							
Rock	870	900							
nd	900	930							
ter		930'							
ate	930	1155							
nd	1155	1220							
ate	1220	1320							
nd	1320	1340							
ate	1340	1400							
nd	1400	1535							
ate	1535	1555							
nd	1555	1635							
ate	1635	1665							
nd	1665	1740							
ate	1740	1755							
nd	1755	1800							
ate	1800	1825							
nd	1825	1855							
ate	1855	1900							
nd	1900	1970							
ate	1970	2020							

(OVER)

W16

SUPERINTENDENT

**"Pipeline"**

Select County: (087) Roane

Select datatypes: ☐ (Check All)

Enter Permit #: 1053

☒ Location☒ Production☒ Plugging☒ Owner/Completion☒ Stratigraphy☒ Sample☒ Pay/Show/Water☒ Logs☒ Btm Hole Loc

Get Data

Reset

Table of Contents
County Code Translations
Permit-Numbering Series
Usage Notes
Contact Information
Disclaimer
WVGES Main
"Pipeline-Plus" New

4708701053

W-17

WV Geological & Economic Survey:

Well: County = 87 Permit = 1053 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 8:10:31 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708701053	Roane	1053	Smithfield	Spencer	Spencer	38.757402	-81.263649	477092.4	4289888.7

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708701053	5/1964	Original Loc	Completed	William Kaufman	24	W17				Wolfs Head Oil Refining Co., Inc.			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEFG
4708701053	5/1964	-/-	971	Ground Level	Civ-Rsh Rn	Price Fm & equivs	Price Fm & equivs	Development Well	Development Well	Oil and Gas	unknown	Fractured	2190		2190	0

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEFG	G_AFT	O_BEFG	O_AFT	WATER_QNTY
4708701053	5/1964	Water	Unknown Water	Vertical			190						1
4708701053	5/1964	Pay	Oil & Gas	Vertical			2136	Big Inj (Price&eq)	0	0			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701053	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Products Company	1989	2,378	210	153	175	176	212	165	232	183	215	272	198	187
4708701053	Pennzoil Products Company	1990	2,919	195	141	218	87	214	250	325	261	260	364	320	284
4708701053	Pennzoil Products Company	1991	3,736	306	293	267	216	357	315	379	340	314	336	302	311
4708701053	Pennzoil Products Company	1992	3,463	324	297	267	257	314	319	298	303	287	282	299	216
4708701053	Pennzoil Products Company	1993	3,350	336	369	331	144	257	240	296	260	260	282	266	309
4708701053	Pennzoil Products Company	1994	3,015	288	265	131	228	261	243	254	296	256	270	252	271
4708701053	Pennzoil Products Company	1995	2,772	260	233	230	200	253	244	241	249	226	233	198	205
4708701053	Pennzoil Products Company	1996	2,115	21	1	199	153	210	191	200	242	242	161	243	252
4708701053	Pennzoil Products Company	1997	2,366	223	223	175	176	148	201	150	172	225	236	207	230
4708701053	Pennzoil Products Company	1998	1,299	227	155	172	171	183	155	127	24	21	22	20	22
4708701053	Pennzoil Products Company	1999	513	144	141	122	22	15	0	0	12	21	22	14	
4708701053	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708701053	East Resources, Inc.	2001	1,148	7	95	124	147	111	112	118	104	115	114	94	7
4708701053	East Resources, Inc.	2002	846	83	71	78	77	69	71	65	59	75	54	45	99
4708701053	East Resources, Inc.	2003	403	0	9	0	23	60	61	49	42	56	53	0	50
4708701053	East Resources, Inc.	2004	274	39	50	34	13	30	21	0	0	0	29	27	31
4708701053	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708701053	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708701053	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708701053	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708701053	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708701053	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708701053	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708701053	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708701053	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708701053	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708701053	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	39	38
4708701053	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708701053	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708701053	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708701053	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708701053	HG Energy, LLC	2021	99	10	7	6	9	10	9	10	9	8	8	7	6
4708701053	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708701053	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	0	28
4708701053	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701053	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1983	444	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Pennzoil Products Company	1989	500	44	40	42	38	43	39	47	47	42	45	38	35
4708701053	Pennzoil Products Company	1990	651	44	18	52	64	62	54	56	60	62	62	59	58
4708701053	Pennzoil Products Company	1991	722	60	45	74	60	66	64	55	58	57	60	59	64
4708701053	Pennzoil Products Company	1992	701	64	62	66	61	52	52	53	55	57	45	65	69
4708701053	Pennzoil Products Company	1993	681	67	42	51	53	64	58	57	60	57	61	55	56
4708701053	Pennzoil Products Company	1994	639	27	54	63	55	50	60	57	57	52	61	53	50
4708701053	Pennzoil Products Company	1995	480	47	39	55	53	52	49	46	49	45	45	0	0
4708701053	Pennzoil Products Company	1996	604	54	42	53	45	43	44	51	53	53	56	55	55
4708701053	Pennzoil Products Company	1997	480	40	47	42	52	40	43	37	51	33	37	37	21
4708701053	Pennzoil Products Company	1998	268	36	34	37	30	13	0	0	0	0	0	68	50
4708701053	Pennzoil Products Company	1999	106	44	44	18	0	0	0	0	0	0	0	0	0
4708701053	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	East Resources, Inc.	2001	392	0	61	51	48	42	35	41	27	0	37	24	26
4708701053	East Resources, Inc.	2002	253	23	27	24	23	22	24	27	16	21	14	10	22
4708701053	East Resources, Inc.	2003	104	0	3	0	3	21	20	12	9	17	13	0	6
4708701053	East Resources, Inc.	2004	50	6	16	12	4	7	5	0	0	0	0	0	0
4708701053	East Resources, Inc.	2005	267	0	0	0	3	37	31	24	38	37	24	41	32
4708701053	East Resources, Inc.	2006	479	40	32	52	34	52	50	45	0	43	41	41	49
4708701053	East Resources, Inc.	2007	474	56	47	52	51	39	25	39	36	32	30	36	31
4708701053	East Resources, Inc.	2008	397	30	25	31	34	29	34	32	38	41	41	30	32
4708701053	East Resources, Inc.	2010	209	20	17	19	24	0	15	23	18	15	22	20	16
4708701053	East Resources, Inc.	2011	131	8	9	12	11	8	11	11	11	10	10	16	14
4708701053	HG Energy, LLC	2012	178	13	17	13	12	17	20	5	21	16	16	12	14
4708701053	HG Energy, LLC	2013	209	18	19	16	16	18	17	22	15	16	19	17	16
4708701053	HG Energy, LLC	2014	176	16	8	7	16	19	14	14	17	14	13	15	23
4708701053	HG Energy, LLC	2015	176	20	15	16	20	19	12	15	12	12	13	9	13
4708701053	HG Energy, LLC	2016	130	9	12	12	9	7	12	12	15	11	12	9	10
4708701053	HG Energy, LLC	2017	85	11	7	9	7	8	6	6	7	4	4	8	8
4708701053	HG Energy, LLC	2018	106	8	8	10	12	10	10	9	7	6	10	6	10
4708701053	HG Energy, LLC	2019	122	15	10	8	11	13	10	10	8	9	13	8	7
4708701053	HG Energy, LLC	2020	108	10	8	7	12	8	8	11	8	10	9	8	9
4708701053	HG Energy, LLC	2021	65	8	5	4	10	8	9	7	10	0	0	0	4
4708701053	HG Energy, LLC	2022	93	9	8	9	8	10	8	7	7	7	9	7	4
4708701053	Delta Helix Energy, LLC	2023	8	0	0	0	0	0	0	0	0	0	0	0	4
4708701053	HG Energy, LLC	2023	73	8	7	9	8	6	6	7	7	7	10	0	0

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701053	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2016	0												
4708701053	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

4708701053

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701053	HG Energy, LLC	2016	0												
4708701053	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701053	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708701053

W-17

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 12

Quadrangle SPENCERPermit No. ROA-1053**WELL RECORD**Oil or Gas Well Gas-Oil
(KIND)

Company WOLF'S HEAD OIL REFINING COMPANY, INC.
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres 800
Location (waters) Millstone Run
Well No. W-17 Elev. 971.38
District Smithfield County Roane
The surface of tract is owned in fee by Romie Smith
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer, II
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced May 14, 1964
Drilling completed May 21, 1964
Date Shot _____ From _____ To _____
Wit's _____
Open Flow _____ /10ths Water in _____ Inch
_____ /10ths Merc. in _____ Inch
Volume Drilled w/Rotary _____ Cu. Ft.
Rock Pressure None lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
WFL ACIDIZED _____

WELL FRACTURED 6/2/64 - Used: 1,050 Bbls. Water, 50,000 # Sand 20-40, 300 Gal. M. C. A.,
350 # WAC-8, 25 Gal. Aqua Frac and 40 Gal. Morflo
Gas - 30,000 Cu. Ft.
Oil - 30 Bbls.

RESULT AFTER TREATMENT _____
ROCK PRESSURE AFTER TREATMENT 450 Lbs.


Fresh Water _____ Feet _____ Salt Water _____ Feet _____

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	5			
10" Casing				10			
Sand			5	80			
Red Rock			80	90			
Sand			90	120			
Red Rock			120	130			
Slate			130	180			
Sand			180	250			
Red Rock			250	275			
Slate			275	300			
Red Rock			300	325			
Slate			325	340			
Sand			340	375			
Red Rock			375	395			
Slate			395	400			
Red Rock			400	420			
Slate			420	460			
8" Casing				470			
Sand			460	500			
Slate			500	600			
Red Rock			600	640			
Slate			640	780			
Red Rock			780	800			
Slate & Shells			800	860			
Red Rock			860	890			
Slate			890	900			
Red Rock			900	915			
Slate			915	920			

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			Steel Shoe
10 3/4" OD	10.00'	10.00'	Float Collar
8 5/8" OD	470.00'	470.00'	Guide Shoe
6 3/4"			Size of 8"
4 1/2" OD	2204.00'	2204.00'	Depth set
3			2150'
2			2190'
Liners Used			Perf. top
			Perf. bottom
			Perf. top
			Perf. bottom

Surface to: _____
CASING CEMENTED 8 5/8" SIZE 470 No. Ft. 5/16/64 Date
4 1/2" 2190 5/22/64

COAL WAS ENCOUNTERED AT _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES



(over)

4708701053

Formation	Color	Hard or Soft	Top / 2	Bottom	Oil, Gas or Water	Depth Found	Remarks
Red Rock			920	930			
Slate			930	1035			
Sand			1035	1115			
Slate			1115	1195			
Sand			1195	1285			
Slate			1285	1335			
Red Rock			1335	1355			
Slate			1355	1400			
Sand			1400	1440			
Red Rock			1440	1465			
Sand			1465	1500			
Slate			1500	1580			
Sand			1580	1675			
Slate			1675	1700			
Sand			1700	1875			
Black Sand			1875	1905			
Sand			1905	1965			
Little Lime			1965	1970			
Slate			1970	1980			
Big Lime			1980	2100	Oil & Gas	2020-2035	Show
Keener			2100	2110			
Big Injun			2110	2136	Oil & Gas	2110-2122	
Slate			2136	2190	Oil & Gas	2125-2136	Show
4½" Casing				2190			
TOTAL DEPTH				2190			

Date June 12, 19 64APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC.By George W. Wilsman, (Title) Agent

WOLF'S HEAD OIL REFINING COMPANY, INC.
SOUTH PENN. OIL COMPANY

NEW WELL REPORT

Rec

4708701053

W-17

No. 51219 600 ACRES WORKING DISTRICT Spencer # 1

Mr. Kaufman FARM WELL NO. W-17 N. S 47 E. W 37

Smithfield DISTRICT OR TOWNSHIP Range COUNTY GUAD.

LOCATION MADE 4-21- 19 64 DRILLING COMMENCED 5-14- 19 64

RIG COMMENCED 5-11- 19 64 DRILLING COMPLETED 5-21- 19 64

RIG COMPLETED 5-14- 19 64 DEPTH 2150' SAND Big Injun

RIG CONTRACTOR Gerald D. Jones DRILLING CONTRACTOR Gerald D. Jones

ELEVATION: FLOOR 971.96 GROUND 971.96 WORK ORDER NO. AFB # W-23-M. Va.

FORMATION RECORD

KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST	KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST
in Soil	0	5			Black Sand	1675	1685		
in Gravel		10	10		Sand	1905	1965		
in	5	30			Little Lane	1965	1970		
in Rock	30	90			Slate	1970	1980		
in	90	120			Oil & Gas	2020	2035		Show
in Rock	120	130			Big Lane	1980	2100		
late	130	160			Reamer	2100	2110		
in	160	250			Oil & Gas	2110	2122		
in		190		1/2 Miller Hr.	Big Injun	2110	2125		
in Rock	250	275			Oil & Gas	2125	2136		Show
late	275	300			Slate	2136	2150		
in Rock	300	325			14" casing		2190	2190	
	325	340							
	340	375			Total Depth		2190	2190	
in	375	395							
late	395	400							
in Rock	400	420							
late	420	460							
in Casing		470	470						
in	460	500							
late	500	600							
in Rock	600	640							
late	640	700							
in Rock	700	800							
late & Shale	800	860							
in Rock	860	890							
late	890	910							
in Rock	910	915							
late	915	920							
in Rock	920	930							
late	930	1005							
in	1005	1115							
late	1115	1175							
in	1175	1205							
late	1205	1235							
in Rock	1235	1305							
late	1305	1400							
in	1400	1440							
in Rock	1440	1460							
in	1460	1500							
late	1500	1520							
in	1520	1675							
in	1675	1700							
in	1700	1875							

(OVER)

4708701053

W-17

NEW WELL REPORT - CONTINUED

INITIAL TORPEDO RECORD		CASING AND TUBING RECORD						
Date of Shot		SIZE	PUT IN WELL			PULLED OUT		
			TRANSFER NO.	FEET	INCH	TRANSFER NO.	FEET	INCH
Name of Torpedo Co.		10-3/4" I.D. S.L.N.		18	00			
No. of Quarts		8-5/8" I.D. S.L.N.		170	00			
Length of Shell		1 1/2" O.D. Kelly		2204	00			
Diameter of Shell								
Length of Anchor								
Top of Shot								
Bottom of Shot								
Feet of Fluid in Hole When Shot								
Results:								

INITIAL PRODUCTION FIRST 24 HOURS			PACKER RECORD			
			KIND	SIZE	DEPTH SET	DATE SET
Open Flow	/10ths Water in	Inch	Steel Shoe	2-5/8"	170	5-16-64
	/10ths Merc. in	Inch	Float Collar	1 1/2"	2199'	5-22-64
Volume	Drilled w/ Rotary	Cu. Ft.	Guide Shoe	1 1/2"	2199'	5-22-64
Rock Pressure	None	lbs.				
Oil		bbls., First 24 hrs.				

ACIDIZATION OR FRACTURING RECORD		CASING CEMENTED	
DATE WELL ACIDIZED		Surface test	
DATE WELL FRACTURED 6-2-64		2-5/8" SIZE 170 FT. 5-16-64 DA	
NAME OF COMPANY Halliburton		1 1/2" SIZE 2199' FT. 5-22-64 DA	
(List below materials used in Acidizing or Fracturing, i.e., Sand, Crude Oil, Gasoline, Water, Kerosene, Methylal, Acid, etc., giving gallons, barrels and pounds.)		SIZE FT. DA	
Used 1/2 gal. HCl			
Used 50.000 # Sand 20-40		Used in Cementing 2-5/8" casing	
Used 300 gal. H.C.L.		100 Bags Portland Cement	
Used 350 # W.C.C.		2 Bags Aquagel	
Used 25 gal. Aqua Floc		A HA-5	
Used 40 gal. Koflo		Cemented by Halliburton	
		Used in Cementing 1 1/2" casing	
		40 Bags Reg. Cement	
		3 - 100# Bentonite	
		50# Lime	
		Cemented by Dowell	
BREAKDOWN PRESSURE 1000			
PUMPING PRESSURE 1500 - 2000			
AVERAGE PUMPING RATE/MINUTE 20			
PUMPING TIME 50 Mins.			
RESULT AFTER TREATMENT		CU. FT.	
GAS 30.000		BBLs.	
OIL 30		LBS.	
ROCK PRESSURE AFTER TREATMENT 450			

REMARKS: Notes Drilled w/ Rotary

Notes Drilled 1 1/2" hole from surface to 170'

Drilled 7-7/8" hole from 170' to 2199'

Notes This Well was Logged by Schlumberger on 5-22-64

Notes Perforated by Basin Surveys on 6-1-64

3 - Holes @ 2111'-9" 3 Holes @ 2133'-9"

Notes This Well was drilled according to Rule 11, under Section 13 of Article 6, Chapter 22 of the Code of the Department of Mines, Oil and Gas Division.

APPROVED

C. C. C. [Signature]

SUPERINTENDENT

**"Pipeline"**

Select County: (087) Roane

Enter Permit #: 1055

Get Data

Reset

Select datatypes: ☐ (Check All)

- ☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/ShowWater ☒ Logs ☒ Btm Hole Loc

[Table of Contents](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

4708701055

W-18

WV Geological & Economic Survey:

Well: County = 87 Permit = 1055 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 8:34:06 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708701055	Roane	1055	Smithfield	Spencer	Spencer	38.757692	-81.259094	477488.3	4289919.8

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708701055	6/-1964	Original Loc	Completed	William Kaufman	25	W18				Wolf's Head Oil Refining Co., Inc.			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEFG
4708701055	6/-1964	-/-	875	Ground Level	Chr-Rsh Rn	Price Frm & equlvs	Price Frm & equlvs	Development Well	Development Well	Oil and Gas	unknown	Fractured	2097		2097		0

Pay/ShowWater Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEFG	G_AFT	O_BEFG	O_AFT	WATER_QNTY
4708701055	6/-1964	Water	Unknown Water	Vertical			1645						0
4708701055	6/-1964	Pay	Oil & Gas	Vertical			2026	Big Injun (Price&eq)	0	0			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701055	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Pennzoil Company	1982	989	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Pennzoil Company	1984	1,470	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Pennzoil Products Company	1989	1,127	122	94	83	44	111	74	119	89	101	121	90	79
4708701055	Pennzoil Products Company	1990	1,424	108	73	104	82	99	113	152	135	144	164	145	105
4708701055	Pennzoil Products Company	1991	1,136	109	96	89	91	97	100	69	112	97	98	85	93
4708701055	Pennzoil Products Company	1992	856	88	74	63	58	71	63	80	82	76	61	68	72
4708701055	Pennzoil Products Company	1993	689	52	64	64	34	50	63	65	54	50	61	61	51
4708701055	Pennzoil Products Company	1994	589	58	62	29	47	54	53	61	59	36	52	44	44
4708701055	Pennzoil Products Company	1995	470	39	47	34	26	42	37	48	41	44	38	35	41
4708701055	Pennzoil Products Company	1996	402	21	1	37	40	48	38	42	33	33	27	41	41
4708701055	Pennzoil Products Company	1997	416	32	33	31	30	28	31	34	36	30	37	44	50
4708701055	Pennzoil Products Company	1998	309	55	30	34	0	30	31	20	24	21	22	20	22
4708701055	Pennzoil Products Company	1999	227	46	48	27	22	15	0	0	12	21	22	14	
4708701055	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708701055	East Resources, Inc.	2001	14	7	0	0	0	0	0	0	0	0	0	0	7
4708701055	East Resources, Inc.	2002	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2003	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2004	56	0	0	0	0	0	0	0	0	0	29	27	0
4708701055	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708701055	East Resources, Inc.	2006	509	36	37	41	41	45	44	48	33	36	43	50	53
4708701055	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708701055	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708701055	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708701055	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708701055	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708701055	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708701055	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708701055	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708701055	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	39	38
4708701055	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708701055	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708701055	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708701055	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708701055	HG Energy, LLC	2021	558	55	40	45	38	46	49	52	51	47	48	40	47
4708701055	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708701055	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0
4708701055	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701055	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Pennzoil Company	1983	444	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Pennzoil Products Company	1989	231	21	10	22	17	22	19	22	21	19	19	21	18
4708701055	Pennzoil Products Company	1990	297	21	17	24	29	29	28	31	27	28	23	21	19
4708701055	Pennzoil Products Company	1991	211	20	19	20	19	12	21	17	17	16	18	16	16
4708701055	Pennzoil Products Company	1992	159	15	14	14	12	14	14	14	12	13	15	10	12
4708701055	Pennzoil Products Company	1993	144	13	10	10	14	14	12	11	13	13	10	11	13
4708701055	Pennzoil Products Company	1994	122	6	11	13	12	12	8	11	9	10	8	10	10
4708701055	Pennzoil Products Company	1995	81	7	5	9	8	10	8	9	8	9	0	0	0
4708701055	Pennzoil Products Company	1996	107	10	11	12	9	9	6	7	9	9	9	8	8
4708701055	Pennzoil Products Company	1997	90	7	8	8	8	9	5	8	7	8	9	4	
4708701055	Pennzoil Products Company	1998	62	7	6	6	6	2	0	0	0	0	0	20	15
4708701055	Pennzoil Products Company	1999	33	14	15	4	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2001	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2002	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2003	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2004	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2005	267	0	0	0	3	37	31	24	38	37	24	41	32
4708701055	East Resources, Inc.	2006	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2007	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2008	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	East Resources, Inc.	2010	148	21	15	19	19	0	9	15	10	10	13	8	9
4708701055	East Resources, Inc.	2011	121	9	9	9	11	11	10	8	9	9	10	14	12
4708701055	HG Energy, LLC	2012	58	10	10	8	8	12	10	0	0	0	0	0	0
4708701055	HG Energy, LLC	2013	135	10	16	16	14	14	12	15	12	8	6	4	8
4708701055	HG Energy, LLC	2014	125	11	14	12	12	16	8	8	10	8	10	8	8
4708701055	HG Energy, LLC	2015	75	10	7	8	10	8	7	10	5	0	0	0	10
4708701055	HG Energy, LLC	2016	108	9	12	10	8	9	10	7	10	7	8	8	10
4708701055	HG Energy, LLC	2017	98	8	9	13	10	9	10	10	14	12	3		
4708701055	HG Energy, LLC	2018	87	10	6	7	8	7	7	7	5	6	6	8	10
4708701055	HG Energy, LLC	2019	131	13	12	8	10	16	11	14	8	9	14	6	10
4708701055	HG Energy, LLC	2020	117	10	8	10	14	9	10	12	9	10	9	9	7
4708701055	HG Energy, LLC	2021	113	8	6	8	10	7	13	10	11	10	11	8	11
4708701055	HG Energy, LLC	2022	102	11	9	12	7	10	8	7	9	8	8	8	5
4708701055	HG Energy, LLC	2023	85	8	8	9	8	10	8	8	9	7	10	0	0
4708701055	Delta Helix Energy, LLC	2023	11	0	0	0	0	0	0	0	0	0	0	5	6

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

4708701055

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701055	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2016	0												
4708701055	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701055	HG Energy, LLC	2016	0												
4708701055	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701055	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well



4708701055

W-18

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Quadrangle SPENCER

Permit No. ROA-1055

WELL RECORD

Oil or Gas Well Oil & Gas
(KIND)


Company WOLF'S HEAD OIL REFINING COMPANY, INC.
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres 800
Location (waters) Millstone Run
Well No. W-18 Elev. 875.44
District Smithfield County Roane
The surface of tract is owned in fee by C. W. Webb
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer, II.
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced June 1, 1964
Drilling completed June 6, 1964
Date Shot - From - To -
With -
Open Flow - /10ths Water in - Inch
- /10ths Merc. in - Inch
Volume Drilled w/Rotary (Show Only) - Cu. Ft.
Rock Pressure None lbs. - hrs.
Oil - bbls., 1st 24 hrs.
WELL ACIDIZED -

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			Steel Shoe
10 3/4"OD	15'	15'	Float Collar
8 5/8"OD	396'	396'	Guide Shoe
6 5/8"			Size of "OD"
5 1/2"OD	2109'	2109'	4 1/2"OD
3			Depth set
2 3/8"OD	2039.71'	2039.71'	2095'
Liners Used			Perf. top
			Perf. bottom
			Perf. top
			Perf. bottom

Surface to:
CASING CEMENTED 8 5/8" SIZE 393 No. Ft. 6/2/64 Date
4 1/2" 2095 6/6/64
COAL WAS ENCOUNTERED AT - FEET - INCHES
- FEET - INCHES - FEET - INCHES
- FEET - INCHES - FEET - INCHES

WELL FRACTURED 6/12/64 - Used: 1,020 Bbl. Water, 60,000 # Sand, 250 Gal. B.D.A., 175# J-98,
350# J-84, 20 Gal. Deterger and 35 Gal. Freflo
RESULT AFTER TREATMENT Gas - 30,000 Cu. Ft.
Oil - 9 bbls.
ROCK PRESSURE AFTER TREATMENT 46 1/2 Lbs.
Fresh Water - Feet - Salt Water - Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	5			
Conductor				15			
Sand			5	20			
Red Rock			20	30			
Sand			30	50			
Slate			50	100			
Sand			100	140			
Slate			140	160			
Sand			160	181			
Slate			185	195			
Red Rock			195	210			
Sand			210	250			
Slate			250	305			
Sand			305	340			
Slate			340	390			
Sand			390	420			
Red Rock			420	450			
Sand			450	500			
Slate			500	600			
Sand			600	625			
Red Rock			625	650			
Slate			650	780			
Sand			780	800			
Slate			800	900			
Sand			900	950			
Shale			950	1000			
Sand			1000	1050			
Slate			1050	1100			
Sand			1100	1175			



4708701055

Formation	Color	Hard or Soft	Top 9	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate			1175	1200			
Sand			1200	1300			
Slate			1300	1350			
Sand			1350	1400			
Slate			1400	1450			
Sand			1450	1500			
Slate			1500	1645			
Salt Sand			1645	1725			Water
Black Slate			1725	1845			
Little Lime			1845	1885			
Big Lime			1885	2005			
Big Injun			2005	2035			
Brake			2035	2040	Oil & Gas	2009-2026	Show Only
Big Injun			2040	2047			
Slate			2047	2097			
4½" Casing				2095			
TOTAL DEPTH				2097			

Date July 13, 1964APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC. OwnerBy George W. Wilsman
George W. Wilsman, (Title) Agent

[illegible]

PACKER RECORD

FICKER RECORD			
KIND	SIZE	DEPTH SET	DATE SET
Steel Shoe	6-5/8" O.D.	322"	6-2-64
Float Collar	6" O.D.	206"	6-6-64
Guide Shoe	1 1/2" O.D.	209 1/2"	6-6-64

CASING CEMENTED

Surface to:
6-5/8" SIZE 300 FT. 6-2-61
4 1/2" SIZE 2005 FT. 6-6-61
SIZE FT.
Used in Constructing 6-5/8" Girders
55 Bags Marquette Cement Bulk Cement
2-1/2" x 5" Blended SF
Cemented by: Hollaburton
Used in Constructing 4 1/2" Columns
40 Bags Cement
4 Bags Aquapal
1 Bag Lime
5 Gal. Rustment
Cemented by Well Service, Inc.

BREAKDOWN PRESSURE 12500

PUMPING PRESSURE 22000 ± 32000

AVERAGE PUMPING RATE/MINUTE 21.4

PUMPING TIME 56 MIN.

RESULT AFTER TREATMENT

}	GAS	<u>22,000</u>	
	OIL	<u>0</u>	CU. FT.

ROCK PRESSURE AFTER TREATMENT 445

			BBLs.
			LBS.

Notes: Used 5 Centralizers
2064, 2033, 2002, 1971 & 1940

Notet Perforated @ 2010' with 1 - 6 way Jet on Single Plane by Basin Surveys, Inc.

Notes: This well was drilled according to Rule 11, under Section 13 of Article 4, Chapter 22 of the code of the Department of Mines, Oil and Gas Division.

APPROVED

C C C

SUPERINTENDENT

WOLF'S HEAD OIL REFINING CO., INC.
SOUTHERN PENNAC COMPANY

rec

4708701055
W-18

NEW WELL REPORT

No. 51219 800 ACRESWORKING DISTRICT Spencer # 1Mr. McFarman FARMWELL No. W-18 N. S. 47 E. W. 37Bedford DISTRICT OR
TOWNSHIPRoanoke COUNTY QUAD.LOCATION MADE May 1, 1964DRILLING COMMENCED June 1, 1964RIG COMMENCED May 28, 1964DRILLING COMPLETED June 6, 1964RIG COMPLETED May 29, 1964DEPTH 2097' SAND Big InjunRIG CONTRACTOR Gerald D. JonesDRILLING CONTRACTOR Gerald D. JonesELEVATION: FLOOR GROUND 575.44WORK ORDER NO. AWC # 141-30-M, Va.

FORMATION RECORD

KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST	KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST
Top Soil	0	5			late	2047	2097		
Drift		15	15		4" casing		2095	2095	
and	5	20			Total Depth		2097	2097	
of Rock	20	30							
and	30	50							
late	50	100							
and	100	140							
late	140	160							
and	160	185							
late	185	195							
of Rock	195	210							
and	210	250							
	250	305							
	305	340							
late	340	390							
and	390	420							
of Rock	420	450							
and	450	500							
late	500	600							
and	600	625							
of Rock	625	650							
late	650	700							
and	700	800							
late	800	900							
and	900	950							
late	950	1000							
and	1000	1050							
late	1050	1100							
and	1100	1175							
late	1175	1200							
and	1200	1300							
late	1300	1350							
and	1350	1400							
late	1400	1450							
and	1450	1500							
late	1500	1645							
lit Sand	1645	1725		Water					
black Slate	1725	1845							
light Sand	1845	1895							
lg Sand	1895	2005							
lg Injun	2005	2095							
lg Sand	2095	2097		Show Only					
lg Sand	2095	2040							
lg Sand	2040	2047							

(OVER)



Select County: (087) Roane ☐ (Check All)

Enter Permit #: 1056

☒ Location ☒ Production ☒ Plugging

☒ Owner/Completion ☒ Stratigraphy ☒ Sample

☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Use Tips](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
[Pipeline-Plus New](#)

W-19

WV Geological & Economic Survey:

Well: County = 087 Permit = 1056 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 7:47:40 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708701056	Roane	1056	Smithfield	Spencer	Spencer	38.759355	-81.26243	477199	4290105.2

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_E
4708701056	6/19/1964	Original Loc	Completed	Maxel Smith	W-19	26	William Kaufman	81219	Alfred M Oppenheimer	Wolf's Head Oil Refining Co., Inc.			
4708701056	-/-	Worked Over	Completed	Maxel Smith	W-19					Pennzoil Products Company		Big Injun (Price&eq)	

Completion Information:

API	CMP_DT	SPUD_DT	ELEV DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD G.
4708701056	6/19/1964	6/12/1964	1061 Ground Level	Civr-Rsh Rn	Undf PRICE blw INJN	Big Injun (Price&eq)	Development Well	Development Well	Oil and Gas	Rotary	Acid-Frac	2277			2277
4708701056	-/-	-/-	1061 Ground Level	Civr-Rsh Rn	Undf PRICE blw INJN	Big Injun (Price&eq)	Service Well	Unsuccessful	Salt Water Disp	unknown	unknown	2277			0

Comment: -/- Injection zone footage in pays is proposed.

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEF	G_AFT	O_BEF	O_AFT	WATER_QNTY
4708701056	6/19/1964	Water	Unknown Water	Vertical			1990						0
4708701056	6/19/1964	Show	Oil & Gas	Vertical	2115	Big Lime	2120	Big Lime	0	0			
4708701056	6/19/1964	Pay	Gas	Vertical	2206	Big Injun (Price&eq)	2216	Big Injun (Price&eq)	0	50			
4708701056	6/19/1964	Pay	Oil	Vertical	2206	Big Injun (Price&eq)	2216	Big Injun (Price&eq)	0	25			
4708701056	-/-	Horizon	Injection	Vertical	2202	Big Injun (Price&eq)	2235	Big Injun (Price&eq)					

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701056	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Philco Gas Co.	1984	1,471	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Pennzoil Products Company	1989	1,263	146	90	107	106	111	91	124	89	101	121	90	87
4708701056	Pennzoil Products Company	1990	1,182	108	73	109	82	82	82	126	97	98	121	103	101
4708701056	Pennzoil Products Company	1991	1,110	109	71	84	82	97	95	115	90	91	98	90	88
4708701056	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701056	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Pennzoil Company	1983	444	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Philco Gas Co.	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Pennzoil Products Company	1989	258	27	24	22	21	23	19	22	21	19	21	21	18
4708701056	Pennzoil Products Company	1990	242	22	17	20	21	24	20	21	20	20	22	21	14
4708701056	Pennzoil Products Company	1991	203	19	17	20	18	20	17	16	17	17	17	15	10
4708701056	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701056	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701056	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701056	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708701056	Original Loc	Little Lime	Well Record	2027	Reasonable	35	Reasonable	1061	Ground Level
4708701056	Original Loc	Pencil Cave	Well Record	2062	Reasonable	16	Reasonable	1061	Ground Level
4708701056	Original Loc	Big Lime	Well Record	2078	Reasonable	115	Reasonable	1061	Ground Level
4708701056	Original Loc	Keener	Well Record	2193	Reasonable	9	Reasonable	1061	Ground Level
4708701056	Original Loc	Big Injun (Price&eq)	Well Record	2202	Reasonable	33	Reasonable	1061	Ground Level
4708701056	Original Loc	Undf PRICE blw INJN	Well Record	2235	Reasonable			1061	Ground Level

Wireline (E-Log) Information:

- * There is no Scanned/Raster Log data for this well
 - * There is no Digitized/LAS Log data for this well
 - * There is no Scanned or Digital Logs available for download
- There is no Plugging data for this well
- There is no Sample data for this well



4708701056

GEORGE H. HUBBARD (Jr.) VICE

W-19


STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 16

Quadrangle SPENCERPermit No. ROA-1056

WELL RECORD

Oil or Gas Well Oil & Gas
(KIND)Company WOLF'S HEAD OIL REFINING COMPANY, INC.Address P. O. Box 1588, Parkersburg, W. Va.Farm Wm. Kaufman Acres 800Location (waters) Millstone RunWell No. W-19 Elev. 1060.85District Smithfield County RoaneThe surface of tract is owned in fee by Maxel SmithOtto Route Address Spencer, W. Va.Mineral rights are owned by Alfred M. Oppenheimer, II,300 South Lang Avenue Address Pittsburgh 8, Pa.Drilling commenced June 12, 1964Drilling completed June 19, 1964Date Shot - From - To -With -Open Flow /10ths Water in - Inch/10ths Merc. in - InchVolume Drilled w/Rotary (Show Only) - Cu. Ft.Rock Pressure No Test lbs. - hrs.Oil - bbls., 1st 24 hrs.WELL ACIDIZED -WELL FRACTURED 6/27/64 - Used: 1,050 Bbls. Water, 46,000 # Sand, 300 Gal. BDA Acid, 175# J-98,350# J-84, 20 Gal. Deterger and 35 Gal. FrefloRESULT AFTER TREATMENT Gas = 50,000 Cu. Ft.ROCK PRESSURE AFTER TREATMENT 400 Lbs.Fresh Water - Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	10			
Conductor				9			
Red Rock			10	20			
Slate			20	85			
Sand			85	200			
Slate			200	230			
Red Rock			230	265			
Slate			265	295			
Sand			295	395			
Slate			395	420			
Red Rock			420	430			
Sand			430	470			
Slate			470	485			
Red Rock			485	495			
Slate			495	515			
Red Rock			515	525			
Slate			525	675			
Red Rock			675	735			
Sand			735	765			
Red Rock			765	815			
Slate			815	840			
Sand			840	905			
Red Rock			905	925			
Slate			925	965			
Red Rock			965	985			
Slate			985	1245			
Sand			1245	1350			
Slate			1350	1375			
Sand			1375	1400			



Location - Color - Soil - (over) - Oil - Gas - Depth - Remarks -

4708701056

[illegible]

DATE OF PREPAREDNESS Date July 13, 19 64

APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC.

By George W. Wilsman
George W. Wilsman, (Title) Agent

4708701056

Ft No 7 W-19

Form OG-10



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 10

JUL 24
RECEIVED COPY

Quadrangle SPENCERPermit No. ROA-1056

WELL RECORD

Oil or Gas Well Oil &

Company WOLF'S HEAD OIL REFINING COMPANY, INC.
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres 800
Location (waters) Millstone Run
Well No. W-19 Elev. 1060.85
District Smithfield County Roane
The surface of tract is owned in fee by Maxel Smith
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer, II.
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced June 12, 1964
Drilling completed June 19, 1964
Date Shot - From - To -
With -
Open Flow /10ths Water in Inch
/10ths Merc. in Inch
Volume Drilled w/Rotary (Show Only) Cu. Ft.
Rock Pressure No Test lbs. hrs.
Oil - bbls, 1st 24 hrs.
WELL ACIDIZED

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
15			
13			
10 3/4" OD	9'	9'	Kind of Pack-
8 3/8" OD	466'	466'	Steel Shoe
6 3/4"			Float Coll.
4 1/2" OD			Guide Shoe
3 1/2" S.L.M.	2272'	2272'	Size of "
2 3/8" OD	2251.83'	2251.83'	2 1/2" OD
			Depth set
			2272'
			2272'
			Perf. top
			Perf. bottom
			Perf. top
			Perf. bottom

Surface test
Casing cemented 8 5/8" size 454 No. Ft. 6/13/64
4 1/2" 2272 6/20/64
COAL WAS ENCOUNTERED AT - FEET - INCH
FEET - INCHES FEET - INCH
FEET - INCHES FEET - INCH


WELL FRACTURED 6/27/64 - Used: 1,050 Bbls. Water, 46,000 # Sand, 300 Gal. HDA Acid, 175# 350# J-84, 20 Gal. Deterger and 35 Gal. Freflo

RESULT AFTER TREATMENT Oil 25 Bbls.
Gas 25 Bbls.

ROCK PRESSURE AFTER TREATMENT 400 lbs.

Fresh Water - Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	10			
Conductor				9			
Red Rock			10	20			
Slate			20	85			
Sand			85	200			
Slate			200	230			
Red Rock			230	265			
Slate			265	295			
Sand			295	395			
Slate			395	420			
Red Rock			420	430			
Sand			430	470			
Slate			470	485			
Red Rock			485	495			
Slate			495	515			
Red Rock			515	525			
Slate			525	675			
Red Rock			675	735			
Sand			735	765			
Slate			765	815			
Red Rock			815	840			
Sand			840	905			
Slate			905	925			
Red Rock			925	965			
Sand			965	985			
Slate			985	1245			
Red Rock			1245	1350			
Sand			1350	1375			
Slate			1375	1400			



4708701056

W-19

Formation	Color	Hard or Soft	Top /0	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate			1400	1570			
Sand			1570	1620			
Slate			1620	1730			
Sand			1730	1760			
Slate			1760	1805			
Sand			1805	1920			
Slate			1920	1990			
Sand			1990	2027			Water
Little Lime			2027	2062			
Pencil Cave			2062	2078			
Big Lime			2078	2193	Oil & Gas	2115-2120	Show Only
Keener			2193	2202			
Big Injun			2202	2235			
Pay			2206	2216			Show
Slate			2235	2277			
4 1/2" Casing				2272			
TOTAL DEPTH				2277			

W19

Date July 13, 19 64

APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC.

By George W. Williams
George W. Williams, (Title) Agent



"Pipeline"

Select County: (087) Roane

Enter Permit #: 1068

Get Data

Reset

Select datatypes: ☐ (Check All)

- ☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

[Table Description](#)
[County Code Translations](#)
[Permit-Numbering Series](#)
[Usage Notes](#)
[Contact Information](#)
[Disclaimer](#)
[WVGES Main](#)
["Pipeline-Plus" New](#)

4708701068

W-20

WV Geological & Economic Survey:

Well: County = 87 Permit = 1068 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 8:08:15 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX_DISTRICT	QUAD_75	QUAD_15	LAT_DD	LON_DD	UTME	UTMN
4708701068	Roane	1068	Smithfield	Spencer	Spencer	38.762653	-81.261226	477304.6	4290470.8

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708701068	7/8/1964	Original Loc	Completed	William Kaufman	27	W20				Wolf's Head Oil Refining Co., Inc.			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_BEFF	G_
4708701068	7/8/1964	6/27/1964	1022	Ground Level	Clvr-Rsh Rn	Price Fm & equivs	Price Fm & equivs	Development Well	Development Well	Oil and Gas	unknown	Fractured	2255		2255			0

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEFF	G_AFT	O_BEFF	O_AFT	WATER_QNTY
4708701068	7/8/1964	Water	Unknown Water	Vertical			1300						0
4708701068	7/8/1964	Water	Unknown Water	Vertical			1780						0
4708701068	7/8/1964	Pay	Oil & Gas	Vertical			2202	Big Injun (Price&eq)	0	0			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701068	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Pennzoil Company	1984	1,471	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Pennzoil Products Company	1989	1,220	146	90	75	106	111	74	119	89	101	127	99	83
4708701068	Pennzoil Products Company	1990	1,291	103	68	114	91	103	125	163	140	126	0	134	124
4708701068	Pennzoil Products Company	1991	1,135	119	96	89	72	101	95	98	96	97	104	85	83
4708701068	Pennzoil Products Company	1992	859	71	74	63	62	76	63	92	87	70	61	68	72
4708701068	Pennzoil Products Company	1993	680	67	64	69	34	61	59	65	54	59	56	51	41
4708701068	Pennzoil Products Company	1994	597	58	43	29	47	54	53	61	44	58	57	53	40
4708701068	Pennzoil Products Company	1995	517	39	61	49	41	42	41	46	41	44	33	44	36
4708701068	Pennzoil Products Company	1996	439	21	1	52	40	48	34	46	50	38	27	41	41
4708701068	Pennzoil Products Company	1997	267	28	33	35	30	32	31	34	32	12	0	0	0
4708701068	Pennzoil Products Company	1998	109	0	0	0	0	0	0	0	24	21	22	20	22
4708701068	Pennzoil Products Company	1999	213	59	48	0	22	15	0	0	0	12	21	22	14
4708701068	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708701068	East Resources, Inc.	2001	562	7	37	63	67	66	42	66	50	58	52	47	7
4708701068	East Resources, Inc.	2002	522	40	39	46	50	50	47	51	41	39	46	27	46
4708701068	East Resources, Inc.	2003	385	31	21	0	0	57	52	53	38	50	49	0	34
4708701068	East Resources, Inc.	2004	465	20	50	42	49	51	42	67	49	39	29	27	0
4708701068	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708701068	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	63
4708701068	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708701068	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708701068	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708701068	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708701068	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708701068	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708701068	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708701068	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708701068	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	39	38
4708701068	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708701068	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708701068	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708701068	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708701068	HG Energy, LLC	2021	217	17	14	14	17	21	21	29	0	3	29	25	27
4708701068	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708701068	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	30	28
4708701068	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701068	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Pennzoil Company	1983	444	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Pennzoil Company	1984	382	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Pennzoil Products Company	1989	245	19	24	22	17	22	19	22	22	21	20	20	17
4708701068	Pennzoil Products Company	1990	281	23	19	25	32	31	29	27	0	26	27	23	19
4708701068	Pennzoil Products Company	1991	205	20	15	21	18	17	18	17	18	16	16	13	16
4708701068	Pennzoil Products Company	1992	165	15	15	14	12	16	15	13	12	13	15	13	12
4708701068	Pennzoil Products Company	1993	139	14	10	12	13	14	12	13	12	11	8	11	9
4708701068	Pennzoil Products Company	1994	129	6	11	13	12	12	9	13	12	11	9	8	13
4708701068	Pennzoil Products Company	1995	88	10	8	9	9	10	8	9	7	10	8	0	0
4708701068	Pennzoil Products Company	1996	114	14	11	12	8	10	9	8	9	9	9	7	8
4708701068	Pennzoil Products Company	1997	52	8	8	9	8	9	8	2	0	0	0	0	0
4708701068	Pennzoil Products Company	1998	37	0	0	0	0	0	0	0	0	0	0	21	16
4708701068	Pennzoil Products Company	1999	33	18	15	0	0	0	0	0	0	0	0	0	0
4708701068	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	East Resources, Inc.	2001	203	0	24	26	22	25	13	23	13	16	17	12	12
4708701068	East Resources, Inc.	2002	163	11	15	14	15	16	16	21	11	11	12	6	15
4708701068	East Resources, Inc.	2003	106	14	7	0	0	20	17	13	8	15	12	0	0
4708701068	East Resources, Inc.	2004	123	3	16	15	15	12	10	16	13	10	3	3	7
4708701068	East Resources, Inc.	2005	100	8	12	11	8	10	13	10	14	12	2	0	0
4708701068	East Resources, Inc.	2006	70	0	0	0	0	0	0	7	0	6	19	15	23
4708701068	East Resources, Inc.	2007	197	23	20	27	27	24	12	17	9	7	10	10	11
4708701068	East Resources, Inc.	2008	113	11	9	10	8	7	8	6	16	17	10	7	4
4708701068	East Resources, Inc.	2010	168	20	17	19	20	0	13	16	13	13	15	12	10
4708701068	East Resources, Inc.	2011	146	9	9	12	12	11	10	11	11	13	14	20	14
4708701068	HG Energy, LLC	2012	200	13	19	22	21	23	22	10	21	16	17	8	8
4708701068	HG Energy, LLC	2013	174	12	15	16	14	16	15	20	18	11	15	12	12
4708701068	HG Energy, LLC	2014	107	14	10	8	8	11	8	8	10	8	6	8	8
4708701068	HG Energy, LLC	2015	91	10	8	8	10	8	8	10	8	5	5	4	7
4708701068	HG Energy, LLC	2016	83	5	7	9	5	4	8	6	10	6	5	8	10
4708701068	HG Energy, LLC	2017	74	8	8	9	6	7	6	6	7	4	4	5	4
4708701068	HG Energy, LLC	2018	85	7	8	8	8	10	8	6	5	5	5	5	10
4708701068	HG Energy, LLC	2019	98	10	8	8	8	13	10	10	6	6	7	5	7
4708701068	HG Energy, LLC	2020	92	10	8	7	10	6	6	9	8	8	7	7	6
4708701068	HG Energy, LLC	2021	74	4	4	4	10	8	9	6	5	7	5	5	7
4708701068	HG Energy, LLC	2022	60	5	5	6	8	8	7	5	7	7	2	0	0
4708701068	Delta Helix Energy, LLC	2023	8	0	0	0	0	0	0	0	0	0	0	0	4
4708701068	HG Energy, LLC	2023	6	0	0	0	0	0	0	0	0	1	5	0	0

4708701068

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701068	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2016	0												
4708701068	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701068	HG Energy, LLC	2016	0												
4708701068	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701068	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

There is no Stratigraphy data for this well

Wireline (E-Log) Information:

* Scanned/Raster Log Information:

API	STATUS	LOG_TOP	LOG_BOT	DEEPEST_FML	LOGS_AVAIL	SCAN	GR_TOP	GR_BOT	D_TOP	D_BOT	N_TOP	N_BOT	I_TOP	I_BOT	T_TOP	T_BOT	S_TOP	S_BOT	O_TOP	O_BOT	INCH2	IN
4708701068	Regular Entry	1850	2254		D.C.*	Y			1850	2254									1850	2254	N	Y

Scanned/Raster Comment: *logs: caliper, bit size

* There is no Digitized/LAS Log data for this well

Downloadable Log Images/Data: We advise you to save the scanned log or digitized log file(s) to your PC for viewing. To do so, right-click the file of interest and select the save option. Then you can direct the file to a location of your choice. Please note the scanned log images vary in size and some may take several minutes to download.

Quick Reference Guide for Log File Names For more info about WVGES scanned logs click [here](#)

Scanned/Raster Logs

FILENAME
4708701068dco.tif

geologic log types:

- d density (includes bulk density, compensated density, density, density porosity, grain density, matrix density, etc.)
- e photoelectric adsorption (PE or Pe, etc.)
- g gamma ray
- i induction (includes dual induction, medium induction, deep induction, etc.)
- f laterolog
- m dipmeter
- n neutron (includes neutron porosity, sidewall neutron-SWN, etc.)
- o other¹
- s sonic or velocity
- t temperature (includes borehole temperature, BHT, differential temperature, etc.)
- z spontaneous potential or potential

mechanical log types:

- b cement bond
- c caliper
- o other¹
- p perforation depth control or perforate

¹other logs may include, but are not limited to, such curves as audio, bit size, CCL--casing collar locator, continuous meter, directional survey, gas detector, guard, NCTL--Nuclear Cement Top Locator, radioactive tracer, tension

There is no Plugging data for this well

There is no Sample data for this well



4708701068

W-20

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 18Quadrangle SPENCERPermit No. ROA-1068

WELL RECORD


Oil or Gas Well _____
(KIND)

Company WOLF'S HEAD OIL REFINING COMPANY, INC.
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres 800
Location (waters) Millstone Run
Well No. W-20 Elev. -
District Smithfield County Roane
The surface of tract is owned in fee by Romie Smith
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer, II,
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced June 27, 1964
Drilling completed July 8, 1964
Date Shot - From - To -
With -
Open Flow /10ths Water in - Inch
/10ths Merc. in - Inch
Volume Show (Drilled w/Rotary) - Cu. Ft.
Rock Pressure No Test - lbs. - hrs.
Oil - bbls., 1st 24 hrs.
WELL ACIDIZED -

WELL FRACTURED 7/15/64 - Used: 35,500 Gals. Water, 48,500 # 20-40, 300 Gal. MCA 15%,
500 # WAC-8, 35 Gal. Morflo and 20 Gal. Aquafrac
RESULT AFTER TREATMENT Gas - 40,000 Cu. Ft.
Oil - 20 Bbls.
ROCK PRESSURE AFTER TREATMENT 340 Lbs.

Fresh Water - Feet - Salt Water - Feet -

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	10			
Conductor				9			
Slate			10	20			
Sand			20	80			
Slate			80	100			
Sand			100	145			
Slate			145	195			
Red Rock			195	215			
Sand			215	295			
Slate			295	330			
Red Rock			330	350			
Slate			350	370			
Red Rock			370	395			
Slate			395	410			
Red Rock			410	430			
Sand			430	450			
Slate			450	475			
Red Rock			475	500			
Slate			500	520			
Sand			520	540			
Red Rock			540	565			
Slate			565	580			
Sand			580	600			
Slate			600	625			
Red Rock			625	650			
Slate			650	700			
Sand			700	760			
Slate			760	795			
Red Rock			795	825			
Slate			825	865			



(over)

4708701068

Formation	Color	Hard or Soft	Top /8	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand			865	900			
Slate			900	925			
Red Rock			925	940			
Slate			940	955			
Red Rock			955	975			
Sand			975	1000			
Slate			1000	1065			
Red Rock			1065	1090			
Sand			1090	1125			
Slate			1125	1165			
Sand			1165	1200			
Slate			1200	1250			
Sand			1250	1300			
Slate			1300	1400			Water
Sand			1400	1470			
Slate			1470	1505			
Sand			1505	1525			
Slate			1525	1575			
Sand			1575	1625			
Slate			1625	1685			
Sand			1685	1720			
Slate			1720	1780			
Sand			1780	1910			Water
Black Slate			1910	1995			
Little Lime			1995	2032			
Pencil Cave			2032	2063			
Big Lime			2063	2170			
Keener			2170	2193			
					Oil & Gas	2170-2175	Show
					Oil & Gas	2180-2193	Show
Big Injun			2193	2213			
					Oil & Gas	2193-2202	Show
Slate			2213	2255			
4½" Casing				2253			
TOTAL DEPTH				2255			

Date August 11, 1964

APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC. owner

By George W. Wilsman
George W. Wilsman, (Title) Agent

WOLF'S HEAD OIL REFINING CO., INC.
~~REVENUE DEPARTMENT~~

RCC

4708701068

W-20

NEW-WELL REPORT

No. 51219 809 ACRES WORKING DISTRICT Spencer # 4

Mr. Kaufman FARM WELL No. W-20 N. 47 E. 37

Smithfield DISTRICT OR TOWNSHIP Reame COUNTY QUAD.

LOCATION MADE May 21, 1964 DRILLING COMMENCED June 27, 1964

RIG COMMENCED June 26, 1964 DRILLING COMPLETED July 8, 1964

RIG COMPLETED June 27, 1964 DEPTH 2255' SAND Big Injun

RIG CONTRACTOR Gerald D. Jones DRILLING CONTRACTOR Gerald D. Jones

ELEVATION: FLOOR GROUND WORK ORDER No. APP # WH-32-M. Va.

FORMATION RECORD

KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST	KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST
Soil	0	10			Sand	1490	1470		
Industor		9	9		Slate	1470	1505		
late	10	20			Sand	1505	1525		
nd	20	60			Slate	1525	1575		
late	60	100			Sand	1575	1625		
nd	100	145			Slate	1625	1685		
late	145	195			Sand	1685	1720		
ad Rock	195	215			Slate	1720	1780		
nd	215	295			Sand	1780	1910		Water
late	295	330			Black Slate	1910	1995		
ad Rock	330	350			Little Lime	1995	2032		
late	350	370			Pencil Cave	2032	2063		
ad Rock	370	395			Big Lime	2063	2170		
late	395	410			leaner	2170	2193		
ad Rock	410	430			Oil & Gas	2170	2175		Show
nd	430	450	437		Oil & Gas	2180	2193		Show
late	450	475			Big Injun	2193	2213		
ad Rock	475	500			Oil & Gas	2193	2202		Show
late	500	520			Slate	2213	2255		
nd	520	540			1 1/2" Casing	2255	2253	2253.96	
ad Rock	540	565			Total Depth		2255	2255	Drillers
late	565	580							
nd	580	600							
late	600	625							
ad Rock	625	650							
late	650	700							
nd	700	760							
late	760	795							
ad Rock	795	825							
late	825	865							
nd	865	900							
late	900	925							
ad Rock	925	940							
late	940	955							
ad Rock	955	975							
nd	975	1000							
late	1000	1065							
ad Rock	1065	1090							
nd	1090	1125							
late	1125	1165							
nd	1165	1200							
late	1200	1250							
nd	1250	1300							
late	1300	1400		Water					

(OVER)



"Pipeline"

Select County: (087) Roane ☐ (Check All)

Enter Permit #: 1079

Get Data Reset

☒ Location ☒ Production ☒ Plugging
☒ Owner/Completion ☒ Stratigraphy ☒ Sample
☒ Pay/Show/Water ☒ Logs ☒ Btm Hole Loc

Table Description
County Code Translations
Permit-Numbering Series
Usage Notes
Contact Information
Disclaimer
WVGES Main
"Pipeline-Plus" Now

4708701079

W-21

WV Geological & Economic Survey:

Well: County = 87 Permit = 1079 [Link to all digital records for well](#)

Report Time: Thursday, April 03, 2025 8:09:10 PM

Location Information: [View Map](#)

API	COUNTY	PERMIT	TAX DISTRICT	QUAD_75	QUAD_15	LAT_DD	LONG_DD	UTME	UTMN
4708701079	Roane	1079	Smithfield	Spencer	Spencer	38.760719	-81.258731	477520.7	4290255.7

There is no Bottom Hole Location data for this well

Owner Information:

API	CMP_DT	SUFFIX	STATUS	SURFACE_OWNER	WELL_NUM	CO_NUM	LEASE	LEASE_NUM	MINERAL_OWN	OPERATOR_AT_COMPLETION	PROP_VD	PROP_TRGT_FM	TFM_EST_PR
4708701079	7/19/1964	Original Loc	Completed	William Kaufman	28	W21				Wolf's Head Oil Refining Co., Inc.			
4708701079	8/30/1986	Worked Over	Completed	William Kaufman		W-21				Pennzoil Company			

Completion Information:

API	CMP_DT	SPUD_DT	ELEV	DATUM	FIELD	DEEPEST_FM	DEEPEST_FMT	INITIAL_CLASS	FINAL_CLASS	TYPE	RIG	CMP_MTHD	TVD	TMD	NEW_FTG	KOD	G_
4708701079	7/19/1964	7/13/1964	1046	Ground Level	Civ-Rsh Rn	Big Injun (Price&eq)	Big Injun (Price&eq)	Development Well	Development Well	Oil and Gas	unknown	Fractured	2260			2260	
4708701079	8/30/1986	8/20/1986	1045	Ground Level	Civ-Rsh Rn	Big Injun (Price&eq)	Big Injun (Price&eq)	Development Well	Development Well	Oil w/ Gas Show	unknown	Acid+Frac	2260				0

Pay/Show/Water Information:

API	CMP_DT	ACTIVITY	PRODUCT	SECTION	DEPTH_TOP	FM_TOP	DEPTH_BOT	FM_BOT	G_BEQ	G_AFT	O_BEQ	O_AFT	WATER_QNTY
4708701079	8/30/1986	Show	Gas	Vertical	2122	Big Lime	2182	Big Lime	0	10			
4708701079	8/30/1986	Pay	Oil	Vertical	2122	Big Lime	2182	Big Lime	0	3			
4708701079	7/19/1964	Pay	Oil	Vertical	2233	Big Injun (Price&eq)	2260	Big Injun (Price&eq)	0	12			
4708701079	7/19/1964	Pay	Gas	Vertical	2233	Big Injun (Price&eq)	2260	Big Injun (Price&eq)	0	39			

Production Gas Information: (Volumes in Mcf)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_GAS	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701079	Pennzoil Company	1981	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Pennzoil Company	1982	999	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Pennzoil Company	1983	1,492	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Pennzoil Company	1984	1,471	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Pennzoil Products Company	1989	1,575	163	108	119	123	136	100	151	103	137	179	132	124
4708701079	Pennzoil Products Company	1990	1,735	149	97	153	120	119	125	163	154	149	194	170	142
4708701079	Pennzoil Products Company	1991	1,536	145	111	125	87	130	116	161	128	114	162	138	119
4708701079	Pennzoil Products Company	1992	1,346	126	98	88	87	107	105	126	128	114	123	110	134
4708701079	Pennzoil Products Company	1993	1,145	114	118	104	45	116	104	111	99	91	89	93	61
4708701079	Pennzoil Products Company	1994	865	0	66	44	72	91	97	97	64	49	95	92	98
4708701079	Pennzoil Products Company	1995	1,117	98	84	88	92	101	101	93	97	98	91	97	77
4708701079	Pennzoil Products Company	1996	853	21	1	99	58	87	81	88	99	81	61	78	99
4708701079	Pennzoil Products Company	1997	585	85	77	75	67	56	70	79	64	12	0	0	0
4708701079	Pennzoil Products Company	1998	109	0	0	0	0	0	0	24	21	22	20	22	
4708701079	Pennzoil Products Company	1999	358	98	93	61	22	15	0	0	12	21	22	14	
4708701079	East Resources, Inc.	2000	150	13	14	10	0	17	8	0	20	14	16	16	22
4708701079	East Resources, Inc.	2001	586	7	37	63	58	66	64	66	54	65	52	47	7
4708701079	East Resources, Inc.	2002	540	40	39	46	50	53	53	52	39	42	27	46	
4708701079	East Resources, Inc.	2003	313	31	21	0	0	60	61	49	47	10	0	0	34
4708701079	East Resources, Inc.	2004	56	0	0	0	0	0	0	0	0	0	28	27	0
4708701079	East Resources, Inc.	2005	383	22	22	21	24	40	34	29	39	41	40	33	38
4708701079	East Resources, Inc.	2006	509	38	37	41	41	45	44	48	33	36	43	50	53
4708701079	East Resources, Inc.	2007	430	51	38	42	30	27	23	27	34	31	32	49	46
4708701079	East Resources, Inc.	2008	479	40	39	40	37	41	39	40	41	41	45	38	38
4708701079	East Resources, Inc.	2010	506	49	35	40	42	43	40	41	41	40	46	47	42
4708701079	East Resources, Inc.	2011	547	44	41	47	47	47	43	47	48	46	48	44	45
4708701079	HG Energy, LLC	2012	525	40	35	39	40	44	40	28	52	57	57	47	46
4708701079	HG Energy, LLC	2013	533	48	35	38	39	51	47	42	48	45	50	44	46
4708701079	HG Energy, LLC	2014	383	42	37	42	36	1	9	15	35	42	42	39	43
4708701079	HG Energy, LLC	2015	464	37	32	33	37	42	41	42	40	40	40	37	43
4708701079	HG Energy, LLC	2016	467	39	38	39	39	41	38	40	38	39	39	39	38
4708701079	HG Energy, LLC	2017	404	37	32	33	31	34	30	32	32	34	36	37	36
4708701079	HG Energy, LLC	2018	426	36	33	38	36	38	37	39	36	34	33	32	34
4708701079	HG Energy, LLC	2019	365	35	32	34	31	24	24	26	32	30	33	34	30
4708701079	HG Energy, LLC	2020	358	35	31	35	17	29	32	33	32	28	28	29	29
4708701079	HG Energy, LLC	2021	65	9	6	6	7	8	7	6	4	2	3	3	4
4708701079	HG Energy, LLC	2022	339	28	21	29	27	29	28	31	31	29	29	29	28
4708701079	Delta Helix Energy, LLC	2023	58	0	0	0	0	0	0	0	0	0	0	0	28
4708701079	HG Energy, LLC	2023	313	30	27	31	32	32	30	32	32	34	33	0	0

Production Oil Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_OIL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701079	Pennzoil Company	1981	440	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Pennzoil Company	1982	307	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Pennzoil Company	1983	444	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Pennzoil Company	1984	363	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Pennzoil Products Company	1989	330	30	28	27	23	28	22	30	31	28	30	29	24
4708701079	Pennzoil Products Company	1990	358	31	25	29	32	31	32	32	32	33	31	28	22
4708701079	Pennzoil Products Company	1991	288	28	18	27	22	28	24	20	28	26	23	23	21
4708701079	Pennzoil Products Company	1992	265	21	21	21	20	22	22	21	24	21	28	22	22
4708701079	Pennzoil Products Company	1993	211	21	13	23	23	24	22	20	19	20	12	0	14
4708701079	Pennzoil Products Company	1994	212	9	17	22	22	19	13	11	20	19	22	20	18
4708701079	Pennzoil Products Company	1995	197	18	18	22	22	20	19	20	19	22	17	0	0
4708701079	Pennzoil Products Company	1996	237	27	16	22	19	19	18	17	20	17	22	21	19
4708701079	Pennzoil Products Company	1997	108	17	18	18	18	21	16	2	0	0	0	0	0
4708701079	Pennzoil Products Company	1998	79	0	0	0	0	0	0	0	0	0	0	40	39
4708701079	Pennzoil Products Company	1999	68	30	29	9	0	0	0	0	0	0	0	0	0
4708701079	East Resources, Inc.	2000	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	East Resources, Inc.	2001	210	0	24	26	19	25	20	23	14	18	17	12	12
4708701079	East Resources, Inc.	2002	169	11	15	14	15	17	18	22	14	11	11	6	15
4708701079	East Resources, Inc.	2003	87	14	7	0	0	21	20	12	10	3	0	0	0
4708701079	East Resources, Inc.	2004	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	East Resources, Inc.	2005	250	0	0	0	0	31	29	23	35	36	22	39	35
4708701079	East Resources, Inc.	2006	444	36	28	42	32	49	45	44	0	41	41	38	48
4708701079	East Resources, Inc.	2007	446	53	43	51	50	37	22	38	35	32	28	33	24
4708701079	East Resources, Inc.	2008	70	0	0	0	0	0	0	0	0	27	18	12	13
4708701079	East Resources, Inc.	2010	167	21	16	19	19	0	13	16	12	14	15	12	10
4708701079	East Resources, Inc.	2011	163	9	9	12	11	13	9	3	22	14	19	22	20
4708701079	HG Energy, LLC	2012	200	15	19	22	21	23	20	10	21	16	17	8	8
4708701079	HG Energy, LLC	2013	156	12	15	16	14	15	15	20	16	7	10	8	8
4708701079	HG Energy, LLC	2014	106	10	10	8	8	10	8	8	10	8	10	8	8
4708701079	HG Energy, LLC	2015	100	10	6	8	8	8	7	10	8	8	10	7	9
4708701079	HG Energy, LLC	2016	98	8	8	10	8	6	9	7	10	7	7	8	10
4708701079	HG Energy, LLC	2017	124	8	9	10	10	11	10	9	12	12	12	14	7
4708701079	HG Energy, LLC	2018	110	10	8	8	10	11	9	9	10	9	10	7	9
4708701079	HG Energy, LLC	2019	114	14	10	8	9	15	10	10	6	8	10	7	7
4708701079	HG Energy, LLC	2020	94	10	8	6	11	6	8	9	8	8	6	7	7
4708701079	HG Energy, LLC	2021	83	5	4	4	10	8	10	6	6	8	6	8	8
4708701079	HG Energy, LLC	2022	87	7	6	9	8	10	7	8	7	7	6	8	4
4708701079	Delta Helix Energy, LLC	2023	8	0	0	0	0	0	0	0	0	0	0	0	3

4708701079	HG Energy, LLC	2023	71	7	7	8	8	4	7	8	9	5	8	0	0
------------	----------------	------	----	---	---	---	---	---	---	---	---	---	---	---	---

4708701079

Production NGL Information: (Volumes in Bbl) ** some operators may have reported NGL under Oil

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_NGL	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701079	HG Energy, LLC	2013	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2014	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2015	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2016	0												
4708701079	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Production Water Information: (Volumes in Gallons)

API	PRODUCING_OPERATOR	PRD_YEAR	ANN_WTR	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DCM
4708701079	HG Energy, LLC	2016	0												
4708701079	HG Energy, LLC	2018	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2019	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2020	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2021	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2022	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	HG Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0
4708701079	Delta Helix Energy, LLC	2023	0	0	0	0	0	0	0	0	0	0	0	0	0

Stratigraphy Information:

API	SUFFIX	FM	FM_QUALITY	DEPTH_TOP	DEPTH_QUALITY	THICKNESS	THICKNESS_QUALITY	ELEV	DATUM
4708701079	Original Loc	Little Lime	Well Record	2040	Reasonable	39	Reasonable	1046	Ground Level
4708701079	Original Loc	Big Lime	Well Record	2079	Reasonable	111	Reasonable	1046	Ground Level
4708701079	Original Loc	Big Injun (Price&eq)	Well Record	2190	Reasonable	22	Reasonable	1046	Ground Level

Wireline (E-Log) Information:

* There is no Scanned/Raster Log data for this well

* There is no Digitized/LAS Log data for this well

* There is no Scanned or Digital Logs available for download

There is no Plugging data for this well

There is no Sample data for this well

4708701079



RECEIVED (1115) V8888

W-21

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 18

Quadrangle SPENCERPermit No. ROA-1079

WELL RECORD

Oil or Gas Well

(KIND)

Company WOLF'S HEAD OIL REFINING COMPANY
Address P. O. Box-1588, Parkersburg, W. Va.
Farm Wm. Kaufman Acres 800
Location (waters) Millstone Run
Well No. W-21 Elev. 1045.56
District Smithfield County Roane
The surface of tract is owned in fee by Romie Smith
Otto Route Address Spencer, W. Va.
Mineral rights are owned by Alfred M. Oppenheimer, II
300 South Lang Avenue Address Pittsburgh 8, Pa.
Drilling commenced July 13, 1964
Drilling completed July 19, 1964
Date Shot - From - To -
With -
Open Flow /10ths Water in Inch
/10ths Merc. in Inch
Volume Show (drilled w/Rotary) Cu. Ft.
Rock Pressure No Test lbs.
Oil Show bbls., 1st 24 hrs.
WELL ACIDIZED

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			Steel Shoe
13			Float Collar
10 3/4" OD	10'	10'	Guide Shoe
8 5/8" OD	435'	435'	Size of 8" OD
4 1/2" OD	2274'	2274'	4 1/2" OD
5 3/16			Depth set
3			2260'
2 3/8" Tbg.	2211'	2211'	Perf. top
Liners Used			Perf. bottom
			Perf. top
			Perf. bottom

Surface to:


CASING CEMENTED 8 5/8" SIZE 432 No. Ft. 7/15/64 Date
4 1/2" 2260 7/19/64

COAL WAS ENCOUNTERED AT - FEET - INCHES
- FEET - INCHES - FEET - INCHES
- FEET - INCHES - FEET - INCHES

WELL FRACTURED 7/24/64 - Used: 42,916 Gals. Water, 53,500 # Sand, 250 Gals. MCA, 400 # WAC-8,
25 Gals. Deterger and 35 Gals. Morflo
RESULT AFTER TREATMENT Gas - 39,000 Cu. Ft.
Oil - 12 Bbls.
ROCK PRESSURE AFTER TREATMENT 240 Lbs.

Fresh Water - Feet Salt Water - Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Top Soil			0	10			
Conductor				10			
Sand			10	35			
Red Rock			35	60			
Sand			60	100			
Slate			100	170			
Sand			170	205			
Red Rock			205	225			
Slate			225	300			
Sand			300	320			
Slate			320	430			
Sand			430	470			
Slate			470	500			
Red Rock			500	535			
Slate & Shale			535	600			
Red Rock			600	625			
Slate			625	705			
Sand			705	740			
Slate			740	770			
Red Rock			770	785			
Sand			785	820			
Slate			820	1120			
Sand			1120	1150			
Slate			1150	1225			
Lime			1225	1250			
Slate			1250	1350			
Sand			1350	1370			
Slate			1370	1465			
Sand			1465	1550			



4708701079

[illegible]

FOR THE GOVERNMENT OF THE DISTRICT OF COLUMBIA
Date August 12, 1964

APPROVED WOLF'S HEAD OIL REFINING COMPANY, INC. Owner

George W. Walsman, (Title) Agent

WOLF'S HEAD OIL REFINING COMPANY, INC.
SOUTHERN PENNSYLVANIA COMPANY

NEW WELL REPORT

RC 4708701079

W-21

E No. W-21 800 ACRES WORKING DISTRICT Spencer 41
 No. Kantner FARM WELL No. W-21 N. 47 E. 37
Smithfield DISTRICT OR TOWNSHIP Rams COUNTY QUAD.
 LOCATION MADE June 9, 19 64 DRILLING COMMENCED July 13, 19 64
 RIG COMMENCED July 13, 19 64 DRILLING COMPLETED July 19, 19 64
 RIG COMPLETED July 13, 19 64 DEPTH 2260' SAND Big Injun
 RIG CONTRACTOR Gerald D. Jones DRILLING CONTRACTOR Gerald D. Jones
 ELEVATION: FLOOR 1045.56 GROUND 1045.56 WORK ORDER No. APR 35-W-21

FORMATION RECORD

KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST	KIND	TOP	BOTTOM	STEEL LINE MEAS.	TEST
Top Soil	0	10							
Conductor		10	10						
Sand	10	35							
Red Rock	35	60							
Sand	60	100							
Slate	100	170							
Sand	170	205							
Red Rock	205	225							
Slate	225	300							
Sand	300	320							
Slate	320	430							
Sand	430	470	430						
Sh	470	500							
Sh & Slate	500	525							
Red Rock	525	600							
Slate	600	625							
Sand	625	705							
Slate	705	740							
Red Rock	740	770							
Sand	770	785							
Slate	785	820							
Sand	820	1120	1120						
Slate	1120	1150							
Slate	1150	1225							
Line	1225	1250							
Slate	1250	1350							
Sand	1350	1570							
Slate	1570	1655							
Sand	1655	1690							
Slate	1690	1730							
Sand	1730	1750							
Slate	1750	1910							
Slate	1910	2010							
Slate	2010	2079							
Big Line	2079	2170							
Oil & Gas	2170	2185		Show					
Oil & Gas	2185	2210		Show					
Big Injun	2210	2222							
Oil & Gas	2222	2230		Show					
Slate	2230	2260							
Top casing		2260	2260						
Full depth		2260	2260						

(OVER)

4708701079

W-21

NEW WELL REPORT - CONTINUED

INITIAL TORPEDO RECORD		CASING AND TUBING RECORD			
		PUT IN WELL		PULLED OUT	
Date of Shot	SIZE	TRANSFER NO.	FEET	INCH	TRANSFER NO.
Name of Torpedo Co.	10-3/4" 40	10-3/4" 40	10	40	
No. of Quarts	2-5/8" 40	2-5/8" 40	45	40	
Length of Shell	1 1/2" 40	1 1/2" 40	27 1/2	40	
Diameter of Shell	2-5/8" 40	2-5/8" 40	27 1/2	40	
Length of Anchor	1 1/2" 40	1 1/2" 40	27 1/2	40	
Top of Shot					
Bottom of Shot					
Feet of Fluid in Hole When Shot					
Results:					

INITIAL PRODUCTION FIRST 24 HOURS		PACKER RECORD	
		KIND	SIZE
Open Flow / 10ths Water in	Inch	Steel Case	2-5/8" 40
Volume (drilled w/ Rotary)	Cu. Ft.	Steel Case	2-5/8" 40
Rock Pressure	lbs.	Steel Case	2-5/8" 40
Oil	bbls., First 24 hrs.	Steel Case	2-5/8" 40

ACIDIZATION OR FRACTURING RECORD		CASING CEMENTED	
DATE WELL ACIDIZED	July 24, 1964	2-5/8" SIZE	7-15-64
DATE WELL FRACTURED	July 24, 1964	1 1/2" SIZE	7-19-64
NAME OF COMPANY	Seaboard		
(List below materials used in Acidizing or Fracturing, i.e., Sand, Crude Oil, Gasoline, Water, Kerosene, Methyls, Acid, etc., giving gallons, barrels and pounds.)			
Used 25,000 lb. Sand			
Used 250 gal. = 250			
Used 100 gal. = 100			
Used 25 gal. = 25			
Used 25 gal. = 25			
Used 25 gal. = 25			
BREAKDOWN PRESSURE	2000		
PUMPING PRESSURE	2000		
AVERAGE PUMPING RATE/MINUTE	20.2		
PUMPING TIME	27.000		
RESULT AFTER TREATMENT	GAS		
	OIL		
ROCK PRESSURE AFTER TREATMENT			

REMARKS: Note: Drilled 2 1/2" Hole Area Surface to 100'

Note: This well was logged by Seaboard on 7-19-64.

Note: This well was perforated by Seaboard on 7-22-64 at 217' - 5 way jet

Note: This well was drilled according to Rule 11, under Section 13 of Article 4, Chapter 22 of the Code of the Department of Mines, Oil & Gas Division.

APPROVED

C. C. C. [Signature]

SUPERINTENDENT